

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	16.000 EA				
0020	201.24 REMOVING STUMP	11.000 EA				
0030	202.15 REMOVING MANHOLE OR CATCH BASIN	3.000 EA				
0040	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	12000.000 SY				
0050	202.202 REMOVING PAVEMENT SURFACE	3900.000 SY				
0060	202.203 PAVEMENT BUTT JOINTS	50.000 SY				
0070	203.20 COMMON EXCAVATION	11000.000 CY				
0080	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0090	203.2333 DISPOSAL OF SPECIAL EXCAVATION	50.000 T				
0100	203.24 COMMON BORROW	105.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	25.000 CY				
0120	304.09 AGGREGATE BASE COURSE - CRUSHED	2600.000 CY				
0130	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1850.000 CY				
0140	403.1021 TEXTURED ASPHALT PAVEMENT	200.000 SY				
0150	403.207 HOT MIX ASPHALT 19.0 MM HMA	2500.000 T				
0160	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	2000.000 T				
0170	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T				
0180	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	70.000 SY				
0190	603.159 12 INCH CULVERT PIPE OPTION III	16.000 LF				
0200	603.161 15 INCH CORRUGATED METAL PIPE	120.000 LF				
0210	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	95.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	603.169 15 INCH CULVERT PIPE OPTION III	910.000 LF				
0230	603.179 18 INCH CULVERT PIPE OPTION III	260.000 LF				
0240	604.071 CATCH BASIN TYPE A1-P	18.500 EA				
0250	604.15 MANHOLE	1.600 EA				
0260	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA				
0270	604.2403 SPECIAL BASIN R3303	2.400 EA				
0280	604.2403 SPECIAL BASIN R3303 - FLAT TOP - 5' DIA.	1.200 EA				
0290	604.242 CATCH BASIN TYPE F3	2.000 EA				
0300	605.09 6 INCH UNDERDRAIN TYPE B	320.000 LF				
0310	605.12 15 INCH UNDERDRAIN TYPE C	600.000 LF				
0320	607.22 CEDAR RAIL FENCE	170.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	608.26 CURB RAMP DETECTABLE WARNING FIELD	160.000 SF				
0340	609.11 VERTICAL CURB TYPE 1	1700.000 LF				
0350	609.111 SPECIAL GRANITE CURB - 24"	400.000 LF				
0360	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	65.000 LF				
0370	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	43.000 EA				
0380	609.2371 TERMINAL CURB TYPE 1- 7 FT - CIRCULAR	9.000 EA				
0390	609.38 RESET CURB TYPE 1	1000.000 LF				
0400	610.08 PLAIN RIPRAP	125.000 CY				
0410	610.18 STONE DITCH PROTECTION	40.000 CY				
0420	613.319 EROSION CONTROL BLANKET	200.000 SY				
0430	615.07 LOAM	270.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	22.000 UN				
0450	619.1201 MULCH - PLAN QUANTITY	22.000 UN				
0460	619.1401 EROSION CONTROL MIX	140.000 CY				
0470	620.58 EROSION CONTROL GEOTEXTILE	55.000 SY				
0480	621.275 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP C	10.000 EA				
0490	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	60.000 EA				
0500	627.407 REFLECTORIZED PLASTIC WHITE OR YELLOW PAVEMENT MARKING	2200.000 SF				
0510	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	10500.000 LF				
0520	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0530	627.95 STREETPRINT DURATHERM PAVEMENT MARKING	4300.000 SF				
0540	635.31 PREFAB CONCRETE BLOCK GRAVITY WALL	1250.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	639.19 FIELD OFFICE TYPE B	1.000 EA				
0560	643.86 TRAFFIC SIGNAL LOOP DETECTORS	3.000 EA				
0570	645.291 ROADSIDE GUIDE SIGNS TYPE II	145.000 SF				
0580	652.38 FLAGGER	10000.000 HR				
0590	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0600	653.22 2 INCH POLYSTYRENE PLASTIC INSULATION	13.000 SY				
0610	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0620	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	12.000 SY				
0630	659.10 MOBILIZATION	LUMP	LUMP			
0640	801.03 TEST PITS	13.000 EA				
0650	801.17 8 INCH PVC SANITARY SEWER (SDR-35)	1300.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	803.011 TEST PITS	48.000 CY				
0670	803.134 4 INCH SERVICE LEADS	185.000 LF				
0680	803.135 6 INCH SERVICE LEADS	155.000 LF				
0690	812.16 SEWER MANHOLE	6.000 EA				
0700	812.162 ADJUSTING SEWER MANHOLE TO GRADE	4.000 EA				
0710	812.164 REBUILDING SEWER MANHOLE	2.000 EA				
0720	822.321 4 INCH CLASS 52 DUCTILE IRON PIPE	15.000 LF				
0730	822.322 6 INCH DUCTILE IRON PIPE	30.000 LF				
0740	822.3224 6" SEWER - FILL & ABANDON	1370.000 LF				
0750	822.33 6 INCH CLASS 52 DUCTILE IRON PIPE	52.000 LF				
0760	822.36 12 INCH DUCTILE IRON PIPE	804.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	822.40 6 INCH COUPLING	1.000 EA				
0780	822.401 4 INCH COUPLING	1.000 EA				
0790	823.31 12 INCH GATE VALVE	2.000 EA				
0800	823.313 12 " TEE 12" X 12"	1.000 EA				
0810	823.3131 12" X 6" TEE	1.000 EA				
0820	823.325 8 INCH GATE VALVE	2.000 EA				
0830	823.331 6 INCH GATE VALVE	1.000 EA				
0840	823.3311 6" SLEEVE	2.000 EA				
0850	823.3353 4 INCH BEND	2.000 EA				
0860	823.337 6 " BEND	2.000 EA				
0870	823.34 BLOW OFF VALVE ASSEMBLY	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0880	824.30 FIRE HYDRANT	1.000 EA				
0890	824.3011 HYDRANT ASSEMBLY (TAPPING SLEEVE/GATE VALVE)	2.000 EA				
0900	824.3021 HYDRANT ASSEMBLY (TEE/GATE VALVE)	1.000 EA				
0910	825.434 1" COPPER SERVICE LONGSIDE	3.000 EA				
0920	825.434 1" COPPER SERVICE SHORTSIDE	6.000 EA				
0930	827.301 ROCK EXCAVATION WATER MAIN	150.000 CY				
0940	827.302 UNSUITABLE SOIL EXCAVATION - BELOW GRADE	150.000 CY				
0950	827.312 SELECT BACKFILL	150.000 CY				
SECTION 0001 TOTAL						.

SECTION 0002 PORTLAND WATER DISTRICT

0960	823.011 GATE VALVE BOX, INSTALL ONLY	2.000 EA				
------	--------------------------------------	-------------	--	--	--	--

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013107.00

PROJECT(S): NH-1310(700)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	823.332 GATE VALVE BOX, ADJUST TO GRADE	10.000 EA				
SECTION 0002 TOTAL						.
SECTION 0003 GAS UTILITY						
0980	827.361 GAS MAIN TRENCH RELOCATION	500.000 LF				
SECTION 0003 TOTAL						
TOTAL BID						