

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 1

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 ITEMS

0010	201.23 REMOVING SINGLE TREE TOP ONLY	EA	2.000			
0020	201.24 REMOVING STUMP	EA	4.000			
0030	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	LF	260.000			
0040	202.15 REMOVING MANHOLE OR CATCH BASIN	EA	2.000			
0050	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0060	203.20 COMMON EXCAVATION	CY	1100.000			
0070	203.25 GRANULAR BORROW	CY	680.000			
0080	203.35 CRUSHED STONE FILL	CY	45.000			
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY	1015.000			
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T	186.000			

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	29.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	186.000 T				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	44.000 G				
0140	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0150	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0160	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0170	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	7500.000 LB				
0180	503.13 REINFORCING STEEL, PLACING	7500.000 LB				
0190	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0200	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0210	505.08 SHEAR CONNECTORS	LUMP	LUMP			

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 3

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	506.30 SHOP COATING OF STRUCTURAL STEEL	LUMP	LUMP			
0230	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0240	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0250	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	SY 450.000				
0260	519.301 GALVANIZING NEW STRUCTURAL STEEL	LUMP	LUMP			
0270	523.52 BEARING INSTALLATION	EA 10.000				
0280	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	EA 5.000				
0290	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	EA 5.000				
0300	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0310	526.34 PERMANENT CONCRETE TRANSITION BARRIER	EA 4.000				
0320	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	EA 2.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	527.34 WORK ZONE CRASH CUSHIONS	UN 4.000				
0340	603.16 15 INCH CULVERT PIPE OPTION I	LF 50.000				
0350	603.169 15 INCH CULVERT PIPE OPTION III	LF 69.000				
0360	603.17 18 INCH CULVERT PIPE OPTION I	LF 70.000				
0370	604.072 CATCH BASIN TYPE A1-C	EA 3.000				
0380	604.092 CATCH BASIN TYPE B1-C	EA 1.000				
0390	605.09 6 INCH UNDERDRAIN TYPE B	LF 397.000				
0400	605.10 6 INCH UNDERDRAIN OUTLET	LF 20.000				
0410	605.11 12 INCH UNDERDRAIN TYPE C	LF 148.000				
0420	606.1721 BRIDGE TRANSITION - TYPE 1	EA 4.000				
0430	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 295.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 5

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	48.000 LF				
0450	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	10.000 EA				
0460	606.356 UNDERDRAIN DELINEATOR POST	2.000 EA				
0470	606.369 GUARDRAIL REMOVED AND STACKED	533.000 LF				
0480	606.651 MODIFIED GUARDRAIL THRIE BEAM - SINGLE RAIL	150.000 LF				
0490	606.70 TRANSITION SECTION THRIE BEAM	4.000 EA				
0500	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0510	607.17 CHAIN LINK FENCE - 6 FOOT	147.000 LF				
0520	607.184 CHAIN LINK SNOW FENCE 3 FOOT	147.000 LF				
0530	609.11 VERTICAL CURB TYPE 1	197.000 LF				
0540	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	1.000 EA				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 6

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	609.247 TERMINAL CURB TYPE 2 - 7 FOOT	EA 1.000				
0560	609.31 CURB TYPE 3	LF 136.000				
0570	610.08 PLAIN RIPRAP	CY 10.000				
0580	613.319 EROSION CONTROL BLANKET	SY 645.000				
0590	615.07 LOAM	CY 90.000				
0600	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	UN 14.000				
0610	619.12 MULCH	UN 14.000				
0620	619.1401 EROSION CONTROL MIX	CY 180.000				
0630	620.54 STABILIZATION GEOTEXTILE	SY 470.000				
0640	620.56 DRAINAGE GEOTEXTILE	SY 15.000				
0650	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	LF 2600.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 7

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	SF 2500.000				
0670	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0680	627.77 REMOVING PAVEMENT MARKINGS	SF 2945.000				
0690	629.05 HAND LABOR, STRAIGHT TIME	HR 10.000				
0700	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 10.000				
0710	631.14 GRADER (INCLUDING OPERATOR)	HR 10.000				
0720	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	HR 10.000				
0730	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	HR 10.000				
0740	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	HR 10.000				
0750	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	HR 10.000				
0760	636.40 MECHANICALLY STABILIZED EARTH RETAINING WALL	SF 5100.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 8

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	639.18 FIELD OFFICE TYPE A	EA 1.000				
0780	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 1.000				
0790	652.312 TYPE III BARRICADE	EA 12.000				
0800	652.33 DRUM	EA 30.000				
0810	652.34 CONE	EA 10.000				
0820	652.35 CONSTRUCTION SIGNS	SF 1200.000				
0830	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0840	652.38 FLAGGER	HR 100.000				
0850	652.381 TRAFFIC OFFICER	HR 50.000				
0860	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	EA 3.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 9

SCHEDULE OF ITEMS

DATE: 120314

REVISED:

CONTRACT ID: 015108.00

PROJECT(S): BH-1510(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0870	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0880	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					