

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015988.00

PROJECT(S): STP-1598(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.203 PAVEMENT BUTT JOINTS	SY	780.000			
0020	203.20 COMMON EXCAVATION	CY	370.000			
0030	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0040	203.2333 DISPOSAL OF SPECIAL EXCAVATION	T	25.000			
0050	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	CY	370.000			
0060	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	T	20.000			
0070	403.210 HOT MIX ASPHALT 9.5 MM	T	240.000			
0080	403.211 HOT MIX ASPHALT (SHIMMING)	T	150.000			
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	T	70.000			
0100	409.15 BITUMINOUS TACK COAT - APPLIED	G	180.000			4

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015988.00

PROJECT(S): STP-1598(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	10.000 CY				
0120	609.31 CURB TYPE 3	320.000 LF				
0130	613.319 EROSION CONTROL BLANKET	80.000 SY				
0140	615.07 LOAM	40.000 CY				
0150	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	6.000 UN				
0160	619.1201 MULCH - PLAN QUANTITY	6.000 UN				
0170	620.54 STABILIZATION GEOTEXTILE	100.000 SY				
0180	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2280.000 LF				
0190	627.811 TEMPORARY BI-DIRECTIONAL YELLOW DELINEATORS	20.000 EA				
0200	627.812 TEMP. BI-DIRECTIONAL WHITE DELINEATORS	30.000 EA				
0210	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				5

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015988.00

PROJECT(S): STP-1598(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR				
0230	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR				
0240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0250	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	10.000 HR				
0260	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0270	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	4.000 HR				
0280	652.33 DRUM	10.000 EA				
0290	652.34 CONE	20.000 EA				
0300	652.35 CONSTRUCTION SIGNS	320.000 SF				
0310	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	47.000 CD				
0320	652.38 FLAGGER	700.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015988.00

PROJECT(S): STP-1598(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0340	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					