

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

MAINE DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF ITEMS

PAGE: 1
 DATE: 121113
 REVISED:

CONTRACT ID: 016350.00 PROJECT(S): SR-A635(000)X
 17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 Project Items						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	9.000 EA				
0020	201.24 REMOVING STUMP	10.000 EA				
0030	202.15 REMOVING MANHOLE OR CATCH BASIN	6.000 EA				
0040	202.203 PAVEMENT BUTT JOINTS	385.000 SY				
0050	203.20 COMMON EXCAVATION	1300.000 CY				
0060	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0070	203.2333 DISPOSAL OF SPECIAL EXCAVATION	100.000 T				
0080	203.25 GRANULAR BORROW	60.000 CY				
0090	203.26 GRAVEL BORROW	60.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2610.000 CY				
0120	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	265.000 T				
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	210.000 T				
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	265.000 T				
0150	409.15 BITUMINOUS TACK COAT - APPLIED	65.000 G				
0160	603.159 12 INCH CULVERT PIPE OPTION III	142.000 LF				
0170	603.161 15 INCH CORRUGATED METAL PIPE	18.000 LF				
0180	603.169 15 INCH CULVERT PIPE OPTION III	88.000 LF				
0190	603.179 18 INCH CULVERT PIPE OPTION III	75.000 LF				

SCHEDULE OF ITEMS

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	603.199 24 INCH CULVERT PIPE OPTION III	72.000 LF				
0210	604.072 CATCH BASIN TYPE A1-C	1.000 EA				
0220	604.092 CATCH BASIN TYPE B1-C	1.000 EA				
0230	604.15 MANHOLE	2.000 EA				
0240	604.166 REBUILDING MANHOLE	1.000 EA				
0250	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0260	604.245 CATCH BASIN TYPE F4-C	2.000 EA				
0270	604.252 CATCH BASIN TYPE A5-C	8.000 EA				
0280	604.262 CATCH BASIN TYPE B5-C	4.000 EA				
0290	605.09 6 INCH UNDERDRAIN TYPE B	1100.000 LF				
0300	605.11 12 INCH UNDERDRAIN TYPE C	800.000 LF				

SCHEDULE OF ITEMS

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	605.12 15 INCH UNDERDRAIN TYPE C	290.000 LF				
0320	605.13 18 INCH UNDERDRAIN TYPE C	310.000 LF				
0330	605.15 24 INCH UNDERDRAIN TYPE C	110.000 LF				
0340	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	20.000 LF				
0350	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0360	606.35 GUARDRAIL DELINEATOR POST	3.000 EA				
0370	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0380	606.47 SINGLE WOOD POST	6.000 EA				
0390	606.48 SINGLE GALVANIZED STEEL POST	3.000 EA				
0400	606.551 GUARDRAIL TYPE 3 - SINGLE RAIL WITH RUB RAIL	15.000 LF				

SCHEDULE OF ITEMS

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0410	607.163 CHAIN LINK FENCE - 4 FOOT P.V.C. COATED	35.000 LF				
0420	607.35 BRACING ASSEMBLY CHAIN LINK FENCE PVC COATED	2.000 EA				
0430	608.08 REINFORCED CONCRETE SIDEWALK	12.000 SY				
0440	608.26 CURB RAMP DETECTABLE WARNING FIELD	104.000 SF				
0450	609.11 VERTICAL CURB TYPE 1	1100.000 LF				
0460	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	80.000 LF				
0470	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	5.000 EA				
0480	609.2341 TERMINAL CURB TYPE 1 - 4 FOOT - CIRCULAR	6.000 EA				
0490	609.238 TERMINAL CURB TYPE 1 - 8 FOOT	27.000 EA				
0500	609.2381 TERMINAL CURB TYPE 1 - 8' CIRCULAR	11.000 EA				
0510	609.31 CURB TYPE 3	1350.000 LF				

SCHEDULE OF ITEMS

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0520	610.08 PLAIN RIPRAP	12.000 CY				
0530	615.07 LOAM	250.000 CY				
0540	618.13 SEEDING METHOD NUMBER 1	21.000 UN				
0550	619.12 MULCH	21.000 UN				
0560	620.58 EROSION CONTROL GEOTEXTILE	25.000 SY				
0570	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3300.000 LF				
0580	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1300.000 SF				
0590	627.77 REMOVING PAVEMENT MARKINGS	400.000 SF				
0600	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0610	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0620	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0630	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	15.000 HR				
0640	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				
0650	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR				
0660	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
0670	639.18 FIELD OFFICE TYPE A	1.000 EA				
0680	642.17 CAST-IN-PLACE CONCRETE STEPS	2.000 CY				
0690	643.60 FLASHING BEACON AT:	LUMP	LUMP			
0700	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	14.000 EA				
0710	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	14.000 EA				
0720	652.31 TYPE I BARRICADE	4.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 016350.00

PROJECT(S): SR-A635(000)X
17106.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0730	652.311 TYPE II BARRICADE	4.000 EA				
0740	652.33 DRUM	30.000 EA				
0750	652.34 CONE	50.000 EA				
0760	652.35 CONSTRUCTION SIGNS	500.000 SF				
0770	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0780	652.38 FLAGGER	1000.000 HR				
0790	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0800	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					