

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 SECTION NO.1						
0010	202.15 REMOVING MANHOLE OR CATCH BASIN	1.000 EA				
0020	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0030	202.1913 REMOVE ABANDONED ASBESTOS-CONTAINING PIPE	75.000 LF				
0040	202.1914 REMOVE OR ABANDON SEWER SERVICE	LUMP	LUMP			
0050	203.20 COMMON EXCAVATION	790.000 CY				
0060	203.24 COMMON BORROW	5.000 CY				
0070	203.25 GRANULAR BORROW	165.000 CY				
0080	203.33 SPECIAL FILL	150.000 CY				
0090	203.35 CRUSHED STONE FILL	190.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	715.000 CY				
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1510.000 CY				
0120	403.207 HOT MIX ASPHALT 19.0 MM HMA	326.000 T				
0130	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	184.000 T				
0140	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	48.000 T				
0150	403.213 HOT MIX ASPHALT 12.5 MM BASE	184.000 T				
0160	409.15 BITUMINOUS TACK COAT - APPLIED	106.000 G				
0170	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	5.000 CY				
0180	502.83 PRECAST BLOCK MAT	900.000 SF				
0190	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	530.000 LB				
0200	503.13 REINFORCING STEEL, PLACING	530.000 LB				5

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0220	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0230	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0240	513.22 CRUSHED STONE SLOPE PROTECTION	175.000 SY				
0250	525.325 DRY-LAID STONE RETAINING WALL	715.000 SF				
0260	525.34 GRANITE MASONRY FACING	200.000 SF				
0270	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	60.000 LF				
0280	528.9101 GLUE - LAMINATED TIMBER BRIDGE RAIL	LUMP	LUMP			
0290	528.9101 GLUE - LAMINATED TIMBER BRIDGE RAIL TRANSITION	LUMP	LUMP			
0300	528.9104 GLUE-LAM TIMBER BRIDGE RAIL, 4 BAR	LUMP	LUMP			
0310	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	603.159 12 INCH CULVERT PIPE OPTION III	88.000 LF				
0330	604.072 CATCH BASIN TYPE A1-C	6.000 EA				
0340	604.201 12 INCH STORM WATER CHECK VALVE	2.000 EA				
0350	605.09 6 INCH UNDERDRAIN TYPE B	510.000 LF				
0360	605.11 12 INCH UNDERDRAIN TYPE C	424.000 LF				
0370	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0380	607.22 CEDAR RAIL FENCE	294.000 LF				
0390	608.26 CURB RAMP DETECTABLE WARNING FIELD	19.000 SF				
0400	609.11 VERTICAL CURB TYPE 1	878.000 LF				
0410	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	128.000 LF				
0420	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	10.000 EA				
0440	609.26 CURB TRANSITION SECTION B TYPE 1	1.000 EA				
0450	610.08 PLAIN RIPRAP	210.000 CY				
0460	610.16 HEAVY RIPRAP	600.000 CY				
0470	610.18 STONE DITCH PROTECTION	3.000 CY				
0480	613.329 EXTENDED USE EROSION CONTROL BLANKETS	20.000 SY				
0490	615.07 LOAM	11.000 CY				
0500	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	3.000 UN				
0510	619.1201 MULCH - PLAN QUANTITY	2.000 UN				
0520	620.58 EROSION CONTROL GEOTEXTILE	300.000 SY				
0530	620.65 REINFORCEMENT GEOGRID	110.000 SY				8

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	621.541 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP B	25.000 EA				
0550	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1800.000 LF				
0560	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	160.000 SF				
0570	627.77 REMOVING PAVEMENT MARKINGS	115.000 SF				
0580	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0590	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0600	631.131 SMALL BULLDOZER-GRADER (INCLUDING OPERATOR)	10.000 HR				
0610	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0620	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0630	639.19 FIELD OFFICE TYPE B	1.000 EA				
0640	641.891 RELOCATE KIOSK	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 9.000				
0660	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	SF 2.500				
0670	652.312 TYPE III BARRICADE	EA 4.000				
0680	652.33 DRUM	EA 12.000				
0690	652.34 CONE	EA 12.000				
0700	652.35 CONSTRUCTION SIGNS	SF 600.000				
0710	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 90.000				
0720	652.38 FLAGGER	HR 160.000				
0730	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	EA 1.000				
0740	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0750	659.10 MOBILIZATION	LUMP	LUMP			10

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	801.17 8 INCH PVC SANITARY SEWER (SDR-35)	19.000 LF				
0770	801.18 12 INCH PVC SANITARY SEWER (SDR-35)	10.000 LF				
0780	803.01 TEST PITS	5.000				
0790	803.16 4 FOOT DIAMETER PRECAST SEWER MANHOLE	2.000 EA				
0800	812.164 REBUILDING SEWER MANHOLE	2.000 EA				
0810	822.3403 8 INCH CLASS 51 DUCTILE IRON PIPE	63.000 LF				
0820	822.3403 8 INCH CLASS 51 DUCTILE IRON PIPE CONCRETE ENCASED	50.000 LF				
0830	825.30 ROCK EXCAVATION FOR SANITARY SEWER	10.000 CY				
0840	827.331 TRENCH INSULATION	22.000 SY				
0850	832.07 OWNERS TESTING ALLOWANCE	LUMP	LUMP			
	SECTION 0001 TOTAL					.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016718.00

PROJECT(S): 016718.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0860	603.1576 12 INCH RESTRAINED END CAP WELDED	2.000 EA				
0870	825.60 12" HIGH DENSITY POLYETHYLENE WATER MAIN SDR 11	120.000 LF				
0880	827.33 TRENCH INSULATION	600.000 LF				
0890	830.14 WATER MAIN BRIDGE CROSSING INSTALL ONLY	LUMP	LUMP			
	SECTION 0002 TOTAL					
	TOTAL BID					