

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016756.00

PROJECT(S): BH-1675(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.1292 REMOVE EXISTING STRUCTURAL TIMBER	LUMP	LUMP			
0020	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	60.000 LF				
0030	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	60.000 LF				
0040	501.903 PILE TIPS - ROCK INJECTOR POINT	2.000 EA				
0050	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0060	504.70 STRUCTURAL STEEL FABRICATED AND DELIVERED	LUMP	LUMP			
0070	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0080	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0090	528.01 STRUCTURAL TIMBER, FABRICATED AND DELIVERED	LUMP	LUMP			
0100	528.02 STRUCT TIMBER, ERECTION	LUMP	LUMP			4

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016756.00

PROJECT(S): BH-1675(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0120	652.312 TYPE III BARRICADE	6.000 EA				
0130	652.33 DRUM	10.000 EA				
0140	652.34 CONE	20.000 EA				
0150	652.35 CONSTRUCTION SIGNS	185.000 SF				
0160	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0170	652.38 FLAGGER	100.000 HR				
0180	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0190	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					