

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 HIGHWAY ITEMS						
0010	201.11 CLEARING	5.000 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	9.000 EA				
0030	202.202 REMOVING PAVEMENT SURFACE	349000.000 SY				
0040	202.204 RUMBLE STRIPS	3.000 GP				
0050	202.205 RUMBLE STRIPS - SHOULDER	208000.000 LF				
0060	203.216 EXPLORATORY DRILLING	24.000 HR				
0070	203.24 COMMON BORROW	180.000 CY				
0080	205.512 WIDENING OF EXISTING SHOULDER	650.000 SY				
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	27515.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	18500.000 T				
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	35.000 T				
0120	403.210 HOT MIX ASPHALT 9.5 MM	675.000 T				
0130	403.211 HOT MIX ASPHALT (SHIMMING)	3800.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	24200.000 G				
0150	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	31.000 CY				
0160	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	11200.000 LB				
0170	424.3333 LOW MODULUS JOINT SEALER, APPLIED	111000.000 LF				
0180	504.07 CONCRETE PIPE TIES	179.000 GP				
0190	527.301 ENERGY ABSORBING SYSTEM (C-A-T)	5.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	16.000 LF				
0210	603.17 18 INCH CULVERT PIPE OPTION I	16.000 LF				
0220	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	496.000 LF				
0230	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	1320.000 LF				
0240	603.205 30 INCH REINFORCED CONCRETE PIPE CLASS III	88.000 LF				
0250	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	320.000 LF				
0260	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	56.000 LF				
0270	603.7424 REMOVE & RELAY 24 INCH CONCRETE PIPE	16.000 LF				
0280	603.743 REMOVE & RELAY 30 INCH CONCRETE PIPE	24.000 LF				
0290	603.7442 REMOVE & RELAY 42 INCH CONCRETE PIPE	8.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0310	605.10 6 INCH UNDERDRAIN OUTLET	38.000 LF				
0320	606.178 GUARDRAIL BEAM	1750.000 LF				
0330	606.2401 GUARDRAIL TYPE 3D - DOUBLE RAIL	3862.500 LF				
0340	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	625.000 EA				
0350	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	110.000 EA				
0360	606.356 UNDERDRAIN DELINEATOR POST	40.000 EA				
0370	606.3581 GUARDRAIL, MODIFY EXISTING TO TYPE 3D	737.500 LF				
0380	606.362 GUARDRAIL ADJUSTED	6300.000 LF				
0390	606.363 GUARDRAIL REMOVE AND DISPOSE	700.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	20.000 EA				
0410	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	6.000 EA				
0420	606.79 GUARDRAIL 350 FLARED TERMINAL	16.000 EA				
0430	606.901 CABLE BARRIER, HIGH TENSION, TL-3	17551.500 LF				
0440	606.91 CABLE BARRIER TERMINAL, HIGH TENSION, TL-3	16.000 EA				
0450	608.26 CURB RAMP DETECTABLE WARNING FIELD	35.000 SF				
0460	608.46 REGRADING SIDEWALK	210.000 SY				
0470	608.461 RECONSTRUCT PEDESTRIAN RAMP	2.000 EA				
0480	610.08 PLAIN RIPRAP	20.000 CY				
0490	613.319 EROSION CONTROL BLANKET	3200.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	615.07 LOAM	20.000 CY				
0510	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	241.000 UN				
0520	619.12 MULCH	105.000 UN				
0530	619.1201 MULCH - PLAN QUANTITY	136.000 UN				
0540	619.1401 EROSION CONTROL MIX	175.000 CY				
0550	620.58 EROSION CONTROL GEOTEXTILE	40.000 SY				
0560	627.18 12 " SOLID WHITE PAVEMENT MARKING	7600.000 LF				
0570	627.30 GROOVING FOR PAVEMENT MARKING	122100.000 SF				
0580	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	355000.000 LF				
0590	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	2000.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0600	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1212000.000 LF				
0610	629.05 HAND LABOR, STRAIGHT TIME	120.000 HR				
0620	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	129.000 HR				
0630	631.122 MINI ALL-PURPOSE EXCAVATOR (INCLUDING OPERATOR)	15.000 HR				
0640	631.133 SKID STEER (INCLUDING OPERATOR)	8.000 HR				
0650	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	230.000 HR				
0660	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	30.000 HR				
0670	631.28 BRUSH CHIPPER (INCLUDING OPERATOR)	30.000 HR				
0680	639.18 FIELD OFFICE TYPE A	1.000 EA				
0690	643.87 WEIGH-IN-MOTION SYSTEM	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016784.20

PROJECT(S): IM-1678(420)E
 IM-1829(300)E
 IM-1919(900)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0700	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	200.000 EA				
0710	652.30 FLASHING ARROW BOARD	10.000 EA				
0720	652.33 DRUM	1170.000 EA				
0730	652.34 CONE	2100.000 EA				
0740	652.35 CONSTRUCTION SIGNS	4850.000 SF				
0750	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	153.000 CD				
0760	652.38 FLAGGER	225.000 HR				
0770	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	10.000 EA				
0780	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0790	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					