

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017054.00

PROJECT(S): NH-1705(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
SECTION 0001 PROJECT ITEMS				
0010	202.202 REMOVING PAVEMENT SURFACE	32670.000 SY		
0020	202.203 PAVEMENT BUTT JOINTS	1120.000 SY		
0030	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	3680.000 T		
0040	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	820.000 T		
0050	403.211 HOT MIX ASPHALT (SHIMMING)	50.000 T		
0060	409.15 BITUMINOUS TACK COAT - APPLIED	1650.000 G		
0070	411.09 UNTREATED AGGREGATE SURFACE COURSE	10.000 CY		
0080	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA		
0090	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	42.000 EA		
0100	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	20760.000 LF		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017054.00

PROJECT(S): NH-1705(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1160.000 SF				
0120	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0130	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0140	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0150	631.133 SKID STEER (INCLUDING OPERATOR)	10.000 HR				
0160	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0170	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0180	639.19 FIELD OFFICE TYPE B	1.000 EA				
0190	643.86 TRAFFIC SIGNAL LOOP DETECTORS	15.000 EA				
0200	652.33 DRUM	60.000 EA				
0210	652.34 CONE	100.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017054.00

PROJECT(S): NH-1705(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	652.35 CONSTRUCTION SIGNS	1550.000 SF				
0230	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	56.000 CD				
0240	652.38 FLAGGER	2000.000 HR				
0250	652.381 TRAFFIC OFFICER	100.000 HR				
0260	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA				
0270	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0280	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					