

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017244.00

PROJECT(S): STP-1724(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
SECTION 0001 PROJECT ITEMS				
0010	201.111 CLEARING	LUMP	LUMP	
0020	201.23 REMOVING SINGLE TREE TOP ONLY	7.000 EA		
0030	201.24 REMOVING STUMP	7.000 EA		
0040	202.15 REMOVING MANHOLE OR CATCH BASIN	2.000 EA		
0050	202.202 REMOVING PAVEMENT SURFACE	210.000 SY		
0060	203.20 COMMON EXCAVATION	6155.000 CY		
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	4775.000 CY		
0080	403.1021 TEXTURED ASPHALT PAVEMENT	590.000 SY		
0090	403.207 HOT MIX ASPHALT 19.0 MM HMA	795.000 T		
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	665.000 T		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017244.00

PROJECT(S): STP-1724(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	95.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	670.000 T				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	260.000 G				
0140	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	54.000 LF				
0150	603.159 12 INCH CULVERT PIPE OPTION III	34.000 LF				
0160	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	34.000 LF				
0170	603.169 15 INCH CULVERT PIPE OPTION III	550.000 LF				
0180	604.09 CATCH BASIN TYPE B1	5.000 EA				
0190	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0200	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	1.000 EA				
0210	604.246 CATCH BASIN TYPE F5	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017244.00

PROJECT(S): STP-1724(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0230	605.09 6 INCH UNDERDRAIN TYPE B	778.000 LF				
0240	605.10 6 INCH UNDERDRAIN OUTLET	16.000 LF				
0250	605.11 12 INCH UNDERDRAIN TYPE C	252.000 LF				
0260	605.12 15 INCH UNDERDRAIN TYPE C	200.000 LF				
0270	606.356 UNDERDRAIN DELINEATOR POST	1.000 EA				
0280	609.31 CURB TYPE 3	725.000 LF				
0290	609.34 CURB TYPE 5	42.000 LF				
0300	609.35 CURB TYPE 5 - CIRCULAR	16.000 LF				
0310	610.08 PLAIN RIPRAP	15.000 CY				
0320	615.07 LOAM	610.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017244.00

PROJECT(S): STP-1724(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	50.000 UN				
0340	619.1201 MULCH - PLAN QUANTITY	50.000 UN				
0350	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	4350.000 LF				
0360	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	86.000 SF				
0370	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0380	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	8.000 HR				
0390	639.18 FIELD OFFICE TYPE A	1.000 EA				
0400	652.33 DRUM	34.000 EA				
0410	652.34 CONE	68.000 EA				
0420	652.35 CONSTRUCTION SIGNS	105.000 SF				
0430	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017244.00

PROJECT(S): STP-1724(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.38 FLAGGER	2000.000				
		HR				
0450	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0460	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	15.000				
		SY				
0470	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					