

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
SECTION 0001 PROJECT ITEMS				
0010	201.11 CLEARING	1.000		
		AC		
0020	202.202 REMOVING PAVEMENT SURFACE	95.000		
		SY		
0030	203.2001 COMMON EXCAVATION - PLAN QUANTITY	1105.000		
		CY		
0040	304.09 AGGREGATE BASE COURSE - CRUSHED	100.000		
		CY		
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	675.000		
		CY		
0060	403.1021 TEXTURED ASPHALT PAVEMENT	75.000		
		SY		
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000		
		T		
0080	403.210 HOT MIX ASPHALT 9.5 MM	130.000		
		T		
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	240.000		
		T		
0100	409.15 BITUMINOUS TACK COAT - APPLIED	30.000		
		G		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	1.000 EA				
0120	603.159 12 INCH CULVERT PIPE OPTION III	22.000 LF				
0130	604.09 CATCH BASIN TYPE B1	1.000 EA				
0140	604.16 ALTERING CATCH BASIN TO MANHOLES	3.000 EA				
0150	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0160	606.172 GUARDRAIL TYPE 3B - SINGLE RAIL, 8' POSTS	355.000 LF				
0170	606.22 GUARDRAIL TYPE 3B - OVER 15 FOOT RADIUS	13.000 LF				
0180	606.363 GUARDRAIL REMOVE AND DISPOSE	410.000 LF				
0190	608.26 CURB RAMP DETECTABLE WARNING FIELD	120.000 SF				
0200	608.261 RESET CONCRETE PAVERS	45.000 SY				
0210	609.34 CURB TYPE 5	45.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	609.35 CURB TYPE 5 - CIRCULAR	12.000 LF				
0230	609.38 RESET CURB TYPE 1	945.000 LF				
0240	609.40 RESET CURB TYPE 5	17.000 LF				
0250	610.08 PLAIN RIPRAP	385.000 CY				
0260	615.0701 LOAM - PLAN QUANTITY	40.000 CY				
0270	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	3.000 UN				
0280	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	1.000 UN				
0290	619.1201 MULCH - PLAN QUANTITY	4.000 UN				
0300	626.11 PRECAST CONCRETE JUNCTION BOX	7.000 EA				
0310	626.22 NON-METALLIC CONDUIT	375.000 LF				
0320	626.31 18 INCH FOUNDATION	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	626.32 24 INCH FOUNDATION	5.000 EA				
0340	626.33 30 INCH FOUNDATION	1.000 EA				
0350	626.331 36 INCH FOUNDATION	1.000 EA				
0360	626.35 CONTROLLER CABINET FOUNDATION	2.000 EA				
0370	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2150.000 LF				
0380	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1100.000 SF				
0390	627.77 REMOVING PAVEMENT MARKINGS	330.000 SF				
0400	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				
0410	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.000 HR				
0420	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR				
0430	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	8.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	634.721 RELOCATE LIGHT POLE	LUMP	LUMP			
0450	639.19 FIELD OFFICE TYPE B	1.000 EA				
0460	643.712 PREEMPTIVE SYSTEM	LUMP	LUMP			
0470	643.80 TRAFFIC SIGNALS AT MAINE STREET AND MASON STREET	LUMP	LUMP			
0480	643.80 TRAFFIC SIGNALS AT RTE 1 WB OFF RAMP	LUMP	LUMP			
0490	643.83 VIDEO DETECTION SYSTEM	LUMP	LUMP			
0500	643.91 MAST ARM POLE	3.000 EA				
0510	643.912 REPAINT EXISTING MAST ARMS AND POLES	4.000 EA				
0520	643.92 PEDESTAL POLE	5.000 EA				
0530	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 1.000				
0550	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	SF 90.000				
0560	652.33 DRUM	EA 50.000				
0570	652.34 CONE	EA 50.000				
0580	652.35 CONSTRUCTION SIGNS	SF 300.000				
0590	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0600	652.38 FLAGGER	HR 800.000				
0610	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	EA 1.000				
0620	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0630	659.10 MOBILIZATION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017264.00

PROJECT(S): NH-1726(400)E

CONTRACTOR : _____

LINE	ITEM	APPROX.	UNIT PRICE		BID AMOUNT	
NO	DESCRIPTION	QUANTITY	-----		-----	
		AND UNITS	DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 TOTAL						

TOTAL BID						