

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	107.531 BI-WEEKLY UPDATES	1.000 LS	_____	 _____	_____	 _____
0020	201.11 CLEARING	9.000 AC	_____	 _____	_____	 _____
0030	201.23 REMOVING SINGLE TREE TOP ONLY	114.000 EA	_____	 _____	_____	 _____
0040	201.24 REMOVING STUMP	121.000 EA	_____	 _____	_____	 _____
0050	202.15 REMOVING MANHOLE OR CATCH BASIN	14.000 EA	_____	 _____	_____	 _____
0060	202.19 REMOVING EXISTING BRIDGE - Eddy Flats Br.	LUMP SUM	LUMP SUM		_____	 _____
0070	202.19 REMOVING EXISTING BRIDGE - Shortridge Br.	LUMP SUM	LUMP SUM		_____	 _____
0080	202.202 REMOVING PAVEMENT SURFACE	220.000 SY	_____	 _____	_____	 _____
0090	203.20 COMMON EXCAVATION	72,100.000 CY	_____	 _____	_____	 _____
0100	203.21 ROCK EXCAVATION	700.000 CY	_____	 _____	_____	 _____
0110	203.211 PRESPLITTING ROCK	500.000 LF	_____	 _____	_____	 _____
0120	203.213 DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	800.000 SY	_____	 _____	_____	 _____

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	203.2312 HEALTH AND SAFETY PLAN	LUMP SUM				
0140	203.2333 DISPOSAL TREATMENT OF SPECIAL EXCAVATION	50.000 T				
0150	203.24 COMMON BORROW	20.000 CY				
0160	203.25 GRANULAR BORROW	2,617.000 CY				
0170	203.33 SPECIAL FILL	80.000 CY				
0180	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	156.000 CY				
0190	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	630.000 CY				
0200	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	63,396.000 CY				
0210	307.332 FULL DEPTH RECYCLED PAVEMENT(W EMULSIFIED ASPHALT STABILIZER) 5 IN. DEPTH	62,800.000 SY				
0220	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	8,522.000 T				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	1,050.000 T	_____	 _____	_____	 _____
0240	403.211 HOT MIX ASPHALT (SHIMMING)	6.000 T	_____	 _____	_____	 _____
0250	403.213 HOT MIX ASPHALT 12.5 MM BASE	14,309.000 T	_____	 _____	_____	 _____
0260	409.15 BITUMINOUS TACK COAT - APPLIED	4,776.000 G	_____	 _____	_____	 _____
0270	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	100.000 CY	_____	 _____	_____	 _____
0280	501.231 DYNAMIC LOADING TEST	4.000 EA	_____	 _____	_____	 _____
0290	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	1,625.000 LF	_____	 _____	_____	 _____
0300	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	1,547.000 LF	_____	 _____	_____	 _____
0310	501.90 PILE TIPS	18.000 EA	_____	 _____	_____	 _____
0320	501.91 PILE SPLICES	28.000 EA	_____	 _____	_____	 _____
0330	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	SUM	_____	_____
0350	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP	SUM	_____	_____
0360	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0370	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0380	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	39,100.000 LB	_____	_____	_____	_____
0390	503.13 REINFORCING STEEL, PLACING	39,100.000 LB	_____	_____	_____	_____
0400	503.17 MECHANICAL WELDED SPLICE	134.000 EA	_____	_____	_____	_____
0410	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	32,200.000 LB	_____	_____	_____	_____
0420	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	32,200.000 LB	_____	_____	_____	_____
0430	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0440	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0450	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0460	511.07 COFFERDAM: Abut. #1 - Eddy Flat Br.	LUMP SUM	LUMP	SUM	_____	_____
0470	511.07 COFFERDAM: Abut. #1 - Shortridge Br.	LUMP SUM	LUMP	SUM	_____	_____
0480	511.07 COFFERDAM: Abut. #2 - Eddy Flat Br.	LUMP SUM	LUMP	SUM	_____	_____
0490	511.07 COFFERDAM: Abut. #2 - Shortridge Br.	LUMP SUM	LUMP	SUM	_____	_____
0500	511.07 COFFERDAM: Downstream - Rte.302 Hwy.	LUMP SUM	LUMP	SUM	_____	_____
0510	511.07 COFFERDAM: Downstream - Kimball Brook	LUMP SUM	LUMP	SUM	_____	_____
0520	511.07 COFFERDAM: Upstream - Kimball Brook	LUMP SUM	LUMP	SUM	_____	_____
0530	511.07 COFFERDAM: Upstream - Rte.302 Hwy.	LUMP SUM	LUMP	SUM	_____	_____
0540	514.06 CURING BOX FOR CONCRETE CYLINDERS	2.000 EA	_____	_____	_____	_____
0550	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0560	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	136.000 LF				
0570	524.301 TEMPORARY STRUCTURAL SUPPORT - Shortridge Br.	LUMP SUM	LUMP	SUM		
0580	524.301 TEMPORARY STRUCTURAL SUPPORT Eddy Flats Br.	LUMP SUM	LUMP	SUM		
0590	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM		
0600	526.305 TEMPORARY CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM	LUMP	SUM		
0610	526.34 PERMANENT CONCRETE TRANSITION BARRIER	8.000 EA				
0620	527.34 WORK ZONE CRASH CUSHIONS	12.000 UN				
0630	534.71 PRECAST CONCRETE BOX CULVERT - Hwy.	LUMP SUM	LUMP	SUM		
0640	534.71 PRECAST CONCRETE BOX CULVERT - Kimball Brook Br.	LUMP SUM	LUMP	SUM		
0650	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP	SUM		
0660	603.16 15 INCH CULVERT PIPE OPTION I	694.000 LF				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0670	603.169 15 INCH CULVERT PIPE OPTION III	104.000 LF				
0680	603.17 18 INCH CULVERT PIPE OPTION I	30.000 LF				
0690	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	978.000 LF				
0700	603.179 18 INCH CULVERT PIPE OPTION III	536.000 LF				
0710	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	64.000 LF				
0720	603.199 24 INCH CULVERT PIPE OPTION III	256.000 LF				
0730	603.205 30 INCH REINFORCED CONCRETE PIPE CLASS III	64.000 LF				
0740	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	248.000 LF				
0750	603.239 48 INCH CULVERT PIPE OPTION III	152.000 LF				
0760	603.275 72 INCH REINFORCED CONCRETE PIPE CLASS III	136.000 LF				
0770	603.55 CONCRETE PIPE TIES	52.000 GP				
0780	604.072 CATCH BASIN TYPE A1-C	14.000 EA				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0790	604.092 CATCH BASIN TYPE B1-C	14.000 EA				
0800	604.243 CATCH BASIN TYPE F3-C	1.000 EA				
0810	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0820	605.09 6 INCH UNDERDRAIN TYPE B	11,231.070 LF				
0830	605.10 6 INCH UNDERDRAIN OUTLET	336.000 LF				
0840	605.11 12 INCH UNDERDRAIN TYPE C	990.000 LF				
0850	605.13 18 INCH UNDERDRAIN TYPE C	1,111.000 LF				
0860	605.15 24 INCH UNDERDRAIN TYPE C	221.000 LF				
0870	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	7,133.000 LF				
0880	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	300.000 LF				
0890	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	63.000 LF				
0900	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	21.000 EA				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0910	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA	_____	 _____	_____	 _____
0920	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1	14.000 EA	_____	 _____	_____	 _____
0930	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	14.000 EA	_____	 _____	_____	 _____
0940	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	87.000 EA	_____	 _____	_____	 _____
0950	606.356 UNDERDRAIN DELINEATOR POST	12.000 EA	_____	 _____	_____	 _____
0960	606.47 SINGLE WOOD POST	24.000 EA	_____	 _____	_____	 _____
0970	606.51 MULTIPLE MAILBOX SUPPORT	4.000 EA	_____	 _____	_____	 _____
0980	608.08 REINFORCED CONCRETE SIDEWALK	303.333 SY	_____	 _____	_____	 _____
0990	608.26 CURB RAMP DETECTABLE WARNING FIELD	92.000 SF	_____	 _____	_____	 _____
1000	609.11 VERTICAL CURB TYPE 1	1,298.000 LF	_____	 _____	_____	 _____
1010	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	50.000 LF	_____	 _____	_____	 _____
1020	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	27.000 EA	_____	 _____	_____	 _____

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1030	609.238 TERMINAL CURB TYPE 1 - 8 FOOT	40.000 EA				
1040	609.31 CURB TYPE 3	7,600.000 LF				
1050	609.38 RESET CURB TYPE 1	300.000 LF				
1060	610.08 PLAIN RIPRAP	3,410.000 CY				
1070	610.09 HAND LAID RIPRAP	2.000 CY				
1080	610.18 STONE DITCH PROTECTION	50.000 CY				
1090	610.210 STREAM CHANNEL ROCK	45.000 CY				
1100	613.319 EROSION CONTROL BLANKET	5,737.000 SY				
1110	613.40 TURF REINFORCEMENT MAT - (TRM)	1,200.000 SY				
1120	615.07 LOAM	5,996.000 CY				
1130	618.13 SEEDING METHOD NUMBER 1	57.000 UN				
1140	618.14 SEEDING METHOD NUMBER 2	858.000 UN				
1150	619.12 MULCH	915.000 UN				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1160	619.14 EROSION CONTROL MIX	6,117.000 CY				
1170	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	500.000 SY				
1180	620.58 EROSION CONTROL GEOTEXTILE	3,882.000 SY				
1190	620.66 DRAINAGE GEOCOMPOSITE	172.000 SY				
1200	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	71,620.000 LF				
1210	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	100.000 LF				
1220	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	770.000 SF				
1230	627.77 REMOVING PAVEMENT MARKINGS	2,500.000 SF				
1240	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	140,000.000 LF				
1250	629.05 HAND LABOR, STRAIGHT TIME	290.000 HR				
1260	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	50.000 HR				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 12 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1270	631.11 AIR TOOL (INCLUDING OPERATOR)	50.000 HR				
1280	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	70.000 HR				
1290	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
1300	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
1310	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
1320	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	120.000 HR				
1330	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	50.000 HR				
1340	631.22 FRONT END LOADER (INCLUDING OPERATOR)	50.000 HR				
1350	639.18 FIELD OFFICE TYPE A - Hwy.	1.000 EA				
1360	639.19 FIELD OFFICE TYPE B - Kimball Brook Br.	1.000 EA				
1370	643.72 TEMPORARY TRAFFIC SIGNAL - Hwy Rte.302	LUMP SUM				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 13 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1380	643.72 TEMPORARY TRAFFIC SIGNAL - Bridge	LUMP SUM				
1390	645.103 DEMOUNT GUIDE SIGN	49.000 EA				
1400	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	95.000 EA				
1410	645.113 REINSTALL GUIDE SIGN	31.000 EA				
1420	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	21.000 EA				
1430	645.291 ROADSIDE GUIDE SIGNS TYPE II	81.000 SF				
1440	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	639.000 SF				
1450	652.30 FLASHING ARROW BOARD	2.000 EA				
1460	652.312 TYPE III BARRICADE	14.000 EA				
1470	652.33 DRUM	320.000 EA				
1480	652.34 CONE	520.000 EA				

12/17/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 14 of 15

Proposal ID: 017280.00

Project(s): 017280.00, 017912.00, 021691.00,
023849.00

SECTION: 1 Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1490	652.35 CONSTRUCTION SIGNS	2,170.000 SF	_____	 _____	_____	 _____
1500	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	344.000 CD	_____	 _____	_____	 _____
1510	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Kimball Brook Br.	LUMP SUM		LUMP SUM	_____	 _____
1520	652.38 FLAGGER	19,360.000 HR	_____	 _____	_____	 _____
1530	652.381 TRAFFIC OFFICER	300.000 HR	_____	 _____	_____	 _____
1540	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	12.000 EA	_____	 _____	_____	 _____
1550	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
1560	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
1570	660.21 ON-THE-JOB TRAINING (BID)	2,000.000 HR	_____	 _____	_____	 _____
1580	801.03 TEST PITS	6.000 EA	_____	 _____	_____	 _____
1590	834.322 DRY HYDRANT - INSTALL ONLY	LUMP SUM		LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____

Total Bid: _____