

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017285.00

PROJECT(S): STP-1728(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA				
0020	201.24 REMOVING STUMP	1.000 EA				
0030	202.202 REMOVING PAVEMENT SURFACE	6650.000 SY				
0040	203.20 COMMON EXCAVATION	1250.000 CY				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	850.000 CY				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	650.000 T				
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	55.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	185.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	25.000 G				
0100	411.131 STONE DUST SURFACE COURSE	165.000 SF				4

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017285.00

PROJECT(S): STP-1728(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	17.000 CY				
0120	525.19 GRANITE SEATING BLOCKS	5.000 EA				
0130	525.191 MEMORIAL RELOCATION SPANISH SQUARE	LUMP	LUMP			
0140	603.159 12 INCH CULVERT PIPE OPTION III	135.000 LF				
0150	604.092 CATCH BASIN TYPE B1-C	1.000 EA				
0160	604.16 ALTERING CATCH BASIN TO MANHOLES	2.000 EA				
0170	604.164 REBUILDING CATCH BASIN	3.000 EA				
0180	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	3.000 EA				
0190	604.243 CATCH BASIN TYPE F3-C	1.000 EA				
0200	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0210	604.249 CATCH BASIN TYPE F6-C	1.000 EA				5

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017285.00

PROJECT(S): STP-1728(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	608.08 REINFORCED CONCRETE SIDEWALK	40.000 SY				
0230	608.241 PRECAST CONCRETE PAVERS	1580.000 SF				
0240	608.26 CURB RAMP DETECTABLE WARNING FIELD	280.000 SF				
0250	608.261 RESET CONCRETE PAVERS	70.000 SY				
0260	609.11 VERTICAL CURB TYPE 1	150.000 LF				
0270	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	515.000 LF				
0280	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	21.000 EA				
0290	609.2371 TERMINAL CURB TYPE 1- 7 FT - CIRCULAR	10.000 EA				
0300	609.34 CURB TYPE 5	435.000 LF				
0310	609.35 CURB TYPE 5 - CIRCULAR	35.000 LF				
0320	609.38 RESET CURB TYPE 1	1310.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017285.00

PROJECT(S): STP-1728(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	615.07 LOAM	235.000 CY				
0340	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	6.000 UN				
0350	619.1201 MULCH - PLAN QUANTITY	6.000 UN				
0360	621.279 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP A	1.000 EA				
0370	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	38.000 EA				
0380	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	38.000 EA				
0390	626.11 PRECAST CONCRETE JUNCTION BOX	6.000 EA				
0400	626.21 METALLIC CONDUIT	150.000 LF				
0410	626.22 NON-METALLIC CONDUIT	350.000 LF				
0420	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	4800.000 LF				
0430	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1900.000 SF				7

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017285.00

PROJECT(S): STP-1728(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0450	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	20.000 HR				
0460	631.11 AIR TOOL (INCLUDING OPERATOR)	20.000 HR				
0470	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0480	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0490	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0500	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0510	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR				
0520	639.19 FIELD OFFICE TYPE B	1.000 EA				
0530	643.6003 PEDESTRIAN ACTUATED CROSSWALK SIGNS AND FLASHERS	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017285.00

PROJECT(S): STP-1728(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 15.000				
0550	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 3.000				
0560	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	SF 65.000				
0570	652.33 DRUM	EA 100.000				
0580	652.34 CONE	EA 100.000				
0590	652.35 CONSTRUCTION SIGNS	SF 500.000				
0600	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0610	652.38 FLAGGER	HR 1200.000				
0620	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0630	659.10 MOBILIZATION	LUMP	LUMP			
	TOTAL BID					9