

SCHEDULE OF ITEMS

CONTRACT ID: 017289.00

PROJECT(S): NH-1728(900)E

AC-IB-1921(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	59128.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	30.000 SY				
0030	203.20 COMMON EXCAVATION	1214.000 CY				
0040	203.24 COMMON BORROW	487.000 CY				
0050	203.25 GRANULAR BORROW	25.000 CY				
0060	204.41 REHABILITATION OF EXISTING SHOULDERS, PLAN QUANTITY	11480.000 SY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1217.000 CY				
0080	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	15.000 T				
0090	403.210 HOT MIX ASPHALT 9.5 MM	6310.000 T				
0100	403.211 HOT MIX ASPHALT (SHIMMING)	100.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017289.00

PROJECT(S): NH-1728(900)E

AC-IB-1921(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	594.000				
		T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	3066.000				
		G				
0130	504.07 CONCRETE PIPE TIES	2.000				
		GP				
0140	603.41 24 INCH REINFORCED CONCRETE PIPE CLASS IV	8.000				
		LF				
0150	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	8.000				
		EA				
0160	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	8.000				
		EA				
0170	606.178 GUARDRAIL BEAM	125.000				
		LF				
0180	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	576.000				
		LF				
0190	606.35 GUARDRAIL DELINEATOR POST	25.000				
		EA				
0200	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	34.000				
		EA				
0210	606.356 UNDERDRAIN DELINEATOR POST	2.000				
		EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017289.00

PROJECT(S): NH-1728(900)E

AC-IB-1921(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.365 GUARDRAIL REMOVE, MODIFY, AND RESET TYPE 3B TO 3C	287.000 LF				
0230	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	13.000 EA				
0240	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	15.000 EA				
0250	606.79 GUARDRAIL 350 FLARED TERMINAL	17.000 EA				
0260	609.31 CURB TYPE 3	561.000 LF				
0270	610.08 PLAIN RIPRAP	16.000 CY				
0280	613.319 EROSION CONTROL BLANKET	270.000 SY				
0290	615.07 LOAM	125.000 CY				
0300	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	5.000 UN				
0310	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	7.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017289.00

PROJECT(S): NH-1728(900)E
AC-IB-1921(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	15.000 UN				
0330	619.1201 MULCH - PLAN QUANTITY	27.000 UN				
0340	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	67100.000 LF				
0350	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	235.000 SF				
0360	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0370	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR				
0380	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0390	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	70.000 HR				
0400	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	2.000 HR				
0410	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR				
0420	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017289.00

PROJECT(S): NH-1728(900)E

AC-IB-1921(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	639.18 FIELD OFFICE TYPE A	1.000 EA				
0440	643.60 FLASHING BEACON AT:	LUMP	LUMP			
0450	652.311 TYPE II BARRICADE	3.000 EA				
0460	652.33 DRUM	75.000 EA				
0470	652.34 CONE	130.000 EA				
0480	652.35 CONSTRUCTION SIGNS	1254.000 SF				
0490	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0500	652.38 FLAGGER	3940.000 HR				
0510	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0520	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					