

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017542.00

PROJECT(S): 17542.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	201.23 REMOVING SINGLE TREE TOP ONLY	EA	1.000			
0020	201.24 REMOVING STUMP	EA	1.000			
0030	202.203 PAVEMENT BUTT JOINTS	SY	100.000			
0040	203.20 COMMON EXCAVATION	CY	1060.000			
0050	203.21 ROCK EXCAVATION	CY	70.000			
0060	203.25 GRANULAR BORROW	CY	260.000			
0070	203.35 CRUSHED STONE FILL	CY	30.000			
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY	1000.000			
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T	240.000			
0100	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	T	4.000			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017542.00

PROJECT(S): 17542.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	240.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	60.000 G				
0130	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	10.000 CY				
0140	508.13 SHEET WATERPROOFING MEMBRANE	LUMP	LUMP			
0150	511.07 COFFERDAM:	LUMP	LUMP			
0160	525.328 REINFORCED FIELDSTONE RETAINING WALL	320.000 SF				
0170	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0180	603.16 15 INCH CULVERT PIPE OPTION I	60.000 LF				
0190	603.179 18 INCH CULVERT PIPE OPTION III	48.000 LF				
0200	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	162.500 LF				
0210	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	100.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017542.00

PROJECT(S): 17542.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA				
0230	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0240	609.11 VERTICAL CURB TYPE 1	70.000 LF				
0250	609.31 CURB TYPE 3	60.000 LF				
0260	610.08 PLAIN RIPRAP	80.000 CY				
0270	615.07 LOAM	130.000 CY				
0280	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	14.000 UN				
0290	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	4.000 UN				
0300	619.1201 MULCH - PLAN QUANTITY	18.000 UN				
0310	619.1301 BARK MULCH	2.000 CY				
0320	620.58 EROSION CONTROL GEOTEXTILE	150.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017542.00

PROJECT(S): 17542.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	621.039 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP C	1.000 EA				
0340	621.043 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP A	15.000 EA				
0350	621.18 MEDIUM DECIDUOUS TREES (6 FOOT - 8 FOOT) GROUP C	1.000 EA				
0360	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0370	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0380	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0390	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0400	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0410	652.33 DRUM	10.000 EA				
0420	652.34 CONE	20.000 EA				
0430	652.35 CONSTRUCTION SIGNS	430.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017542.00

PROJECT(S): 17542.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	34.000				
	CD					
0450	652.38 FLAGGER	500.000				
	HR					
0460	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0470	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					