

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017822.00

PROJECT(S): 017822.00(S)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
SECTION 0001 PROJECT ITEMS				
0010	201.11 CLEARING	2.500 AC		
0020	202.08 REMOVING BUILDING NO.: NO. 1	LUMP	LUMP	
0030	202.08 REMOVING BUILDING NO.: NO. 2	LUMP	LUMP	
0040	202.08 REMOVING BUILDING NO.: NO. 3	LUMP	LUMP	
0050	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	4000.000 SY		
0060	203.20 COMMON EXCAVATION	23500.000 CY		
0070	203.21 ROCK EXCAVATION	100000.000 CY		
0080	304.09 AGGREGATE BASE COURSE - CRUSHED	4050.000 CY		
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	9275.000 CY		
0100	403.207 HOT MIX ASPHALT 19.0 MM HMA	165.000 T		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017822.00

PROJECT(S): 017822.00(S)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	130.000 T				
0120	603.179 18 INCH CULVERT PIPE OPTION III	100.000 LF				
0130	603.219 36 INCH CULVERT PIPE OPTION III	75.000 LF				
0140	604.09 CATCH BASIN TYPE B1	1.000 EA				
0150	607.17 CHAIN LINK FENCE - 6 FOOT	1300.000 LF				
0160	610.08 PLAIN RIPRAP	7500.000 CY				
0170	615.07 LOAM	100.000 CY				
0180	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	10.000 UN				
0190	620.54 STABILIZATION GEOTEXTILE	7210.000 SY				
0200	620.56 DRAINAGE GEOTEXTILE	2790.000 SY				
0210	639.19 FIELD OFFICE TYPE B	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017822.00

PROJECT(S): 017822.00(S)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0230	659.10 MOBILIZATION	LUMP	LUMP			
0240	832.071 CONTRACTOR ALLOWANCE UTILITY WORK	LUMP	LUMP		2500	.00
0250	910.301 SPECIAL WORK MISC. UTILITY SITE WORK	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					