

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	810.000 CY				
0030	203.21 ROCK EXCAVATION	10.000 CY				
0040	203.25 GRANULAR BORROW	480.000 CY				
0050	203.35 CRUSHED STONE FILL	215.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	695.000 CY				
0070	403.210 HOT MIX ASPHALT 9.5 MM	207.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	138.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	32.000 G				
0100	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0120	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0130	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP	LUMP			
0140	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0150	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				
0160	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0170	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	275.000 LF				
0180	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0190	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0200	610.08 PLAIN RIPRAP	440.000 CY				
0210	615.07 LOAM	45.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	7.000 UN				
0230	619.1201 MULCH - PLAN QUANTITY	7.000 UN				
0240	620.54 STABILIZATION GEOTEXTILE	950.000 SY				
0250	620.58 EROSION CONTROL GEOTEXTILE	280.000 SY				
0260	620.65 REINFORCEMENT GEOGRID	180.000 SY				
0270	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	750.000 LF				
0280	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0290	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0300	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0310	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0320	639.19 FIELD OFFICE TYPE B	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0340	652.31 TYPE I BARRICADE	1.000 EA				
0350	652.312 TYPE III BARRICADE	4.000 EA				
0360	652.33 DRUM	25.000 EA				
0370	652.34 CONE	20.000 EA				
0380	652.35 CONSTRUCTION SIGNS	250.000 SF				
0390	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	30.000 CD				
0400	652.38 FLAGGER	150.000 HR				
0410	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0420	659.10 MOBILIZATION	LUMP	LUMP			
0430	834.322 DRY HYDRANT - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017867.00

PROJECT(S): STP-1786(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					