

SCHEDULE OF ITEMS

CONTRACT ID: 017872.00

PROJECT(S): BR-1787(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 project items						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	CY	1545.000			
0030	203.24 COMMON BORROW	CY	5.000			
0040	203.25 GRANULAR BORROW	CY	345.000			
0050	203.35 CRUSHED STONE FILL	CY	19.000			
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	CY	480.000			
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY	2000.000			
0080	403.207 HOT MIX ASPHALT 19.0 MM HMA	T	196.000			
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T	183.000			
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	T	183.000			

SCHEDULE OF ITEMS

CONTRACT ID: 017872.00

PROJECT(S): BR-1787(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	G 110.000				
0120	501.231 DYNAMIC LOADING TEST	EA 2.000				
0130	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	LF 1545.000				
0140	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	LF 1545.000				
0150	501.90 PILE TIPS	EA 10.000				
0160	501.91 PILE SPLICES	EA 20.000				
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0190	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP	LUMP			
0200	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0210	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 017872.00

PROJECT(S): BR-1787(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	LB 10300.000				
0230	503.13 REINFORCING STEEL, PLACING	LB 10300.000				
0240	503.14 EPOXY-COATED REINFORCING STEEL, FABRICATED AND DELIVERED	LB 300.000				
0250	503.15 EPOXY-COATED REINFORCING STEEL, PLACING	LB 300.000				
0260	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0270	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0280	511.07 COFFERDAM: ABUTMENT NO. 1	LUMP	LUMP			
0290	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0300	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0310	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0320	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 017872.00

PROJECT(S): BR-1787(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	526.34 PERMANENT CONCRETE TRANSITION BARRIER	EA 4.000				
0340	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP	LUMP			
0350	606.1721 BRIDGE TRANSITION - TYPE 1	EA 4.000				
0360	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 200.000				
0370	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				
0380	606.79 GUARDRAIL 350 FLARED TERMINAL	EA 4.000				
0390	610.08 PLAIN RIPRAP	CY 300.000				
0400	613.319 EROSION CONTROL BLANKET	SY 35.000				
0410	615.07 LOAM	CY 26.000				
0420	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	UN 5.000				
0430	619.1201 MULCH - PLAN QUANTITY	UN 5.000				

SCHEDULE OF ITEMS

CONTRACT ID: 017872.00

PROJECT(S): BR-1787(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	619.1401 EROSION CONTROL MIX	CY 52.000				
0450	620.58 EROSION CONTROL GEOTEXTILE	SY 300.000				
0460	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	LF 2000.000				
0470	629.05 HAND LABOR, STRAIGHT TIME	HR 40.000				
0480	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 40.000				
0490	631.14 GRADER (INCLUDING OPERATOR)	HR 40.000				
0500	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	HR 40.000				
0510	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	HR 40.000				
0520	639.18 FIELD OFFICE TYPE A	EA 1.000				
0530	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0540	652.312 TYPE III BARRICADE	EA 4.000				

SCHEDULE OF ITEMS

CONTRACT ID: 017872.00

PROJECT(S): BR-1787(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	652.33 DRUM	EA 20.000				
0560	652.34 CONE	EA 20.000				
0570	652.35 CONSTRUCTION SIGNS	SF 300.000				
0580	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 30.000				
0590	652.38 FLAGGER	HR 200.000				
0600	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	EA 2.000				
0610	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0620	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					