

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE	ITEM	APPROX.	UNIT PRICE		BID AMOUNT	
NO	DESCRIPTION	QUANTITY	-----		-----	
		AND UNITS	DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	18150.000				
		SY				
0020	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE (745 SY)	LUMP	LUMP			
0030	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	250.000				
		T				
0040	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	1638.000				
		T				
0050	403.2101 9.5 MM POLYMER MODIFIED HMA	41.000				
		T				
0060	403.211 HOT MIX ASPHALT (SHIMMING)	597.000				
		T				
0070	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	348.000				
		T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	1559.000				
		G				
0090	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	40.000				
		LB				
0100	424.3333 LOW MODULUS JOINT SEALER, APPLIED	9200.000				
		LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	429.34 GRID/ FABRIC FABRIC COMPOSITE PAVEMENT INTERLAYER	1315.000 SF				
0120	502.70 BRIDGE DRAINS	8.000 EA				
0130	502.701 BRIDGE DRAIN GRATE MODIFICATION	28.000 EA				
0140	507.0926 FURNISH ALUMINUM BRIDGE RAIL COMPONENTS	LUMP	LUMP			
0150	507.0927 ALUMINUM BRIDGE RAIL, 2 BAR POST REPLACEMENT	8.000 EA				
0160	507.0928 ALUMINUM BRIDGE RAIL, RAIL SECTION REPLACEMENT	40.000 LF				
0170	507.30 ALUMINUM RAIL BAR SPLICE RETROFIT	18.000 EA				
0180	507.31 ALUMINUM BRIDGE RAIL SPLICE INSPECTION	LUMP	LUMP			
0190	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE (5665 SY)	LUMP	LUMP			
0200	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES (160 SY)	LUMP	LUMP			
0210	518.391 REPAIRING GRANITE CURB JOINT AND BEDDING MORTAR	560.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 7.9 IN.	3160.000 SF				
0230	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 7.9 IN.	730.000 SF				
0240	518.52 REPAIR OF UPWARD FACING SURFACES > 7.9 IN.	7.000 CY				
0250	518.60 REPAIR OF VERTICAL SURFACES < 7.9 IN.	62.000 SF				
0260	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	14.000 CY				
0270	520.242 BRIDGE JOINT MODIFICATION TYPE 2	2.000 EA				
0280	520.244 BRIDGE JOINT MODIFICATION TYPE 4	2.000 EA				
0290	520.247 BRIDGE JOINT MODIFICATION TYPE 7	2.000 EA				
0300	526.301 TEMPORARY CONCRETE BARRIER TYPE I (6650 LF)	LUMP	LUMP			
0310	526.34 PERMANENT CONCRETE TRANSITION BARRIER	6.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0330	604.167 ALTER CATCH BASIN GRATE TO CASCADE	13.000 EA				
0340	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA				
0350	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	16.000 EA				
0360	606.1721 BRIDGE TRANSITION - TYPE 1	6.000 EA				
0370	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	75.000 LF				
0380	606.363 GUARDRAIL REMOVE AND DISPOSE	188.000 LF				
0390	610.08 PLAIN RIPRAP	50.000 CY				
0400	615.07 LOAM	20.000 CY				
0410	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1.000 UN				
0420	619.1201 MULCH - PLAN QUANTITY	1.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	620.58 EROSION CONTROL GEOTEXTILE	100.000 SY				
0440	627.18 12 " SOLID WHITE PAVEMENT MARKING	950.000 LF				
0450	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	31650.000 LF				
0460	627.77 REMOVING PAVEMENT MARKINGS	3500.000 SF				
0470	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	33050.000 LF				
0480	629.05 HAND LABOR, STRAIGHT TIME	70.000 HR				
0490	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	40.000 HR				
0500	631.11 AIR TOOL (INCLUDING OPERATOR)	40.000 HR				
0510	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	28.000 HR				
0520	631.133 SKID STEER (INCLUDING OPERATOR)	8.000 HR				
0530	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	28.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	16.000 HR				
0550	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	16.000 HR				
0560	639.18 FIELD OFFICE TYPE A	1.000 EA				
0570	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0580	644.30 GLAREFOILS	200.000 EA				
0590	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	50.000 EA				
0600	652.30 FLASHING ARROW BOARD	6.000 EA				
0610	652.312 TYPE III BARRICADE	10.000 EA				
0620	652.33 DRUM	750.000 EA				
0630	652.34 CONE	100.000 EA				
0640	652.35 CONSTRUCTION SIGNS	1620.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017929.00

PROJECT(S): IM-1792(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	652.351 CONSTRUCTION SIGNS - SUPPLIED BY MAINEDOT	2100.000 SF				
0660	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	185.000 CD				
0670	652.38 FLAGGER	60.000 HR				
0680	652.381 TRAFFIC OFFICER	240.000 HR				
0690	652.382 TRAFFIC MONITOR	185.000 CD				
0700	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	7.000 EA				
0710	652.43 PORTABLE CHANGEABLE MESSAGE SIGN - RETAINED BY DEPARTMENT	2.000 EA				
0720	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0730	659.10 MOBILIZATION	LUMP	LUMP			
0740	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
	SECTION 0001 TOTAL					
	TOTAL BID					