

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00,
023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	11.000 AC	_____	 _____	_____	 _____
0020	201.23 REMOVING SINGLE TREE TOP ONLY	50.000 EA	_____	 _____	_____	 _____
0030	201.24 REMOVING STUMP	50.000 EA	_____	 _____	_____	 _____
0040	202.15 REMOVING MANHOLE OR CATCH BASIN	8.000 EA	_____	 _____	_____	 _____
0050	202.19 REMOVING EXISTING BRIDGE	LUMP SUM		 LUMP SUM	_____	 _____
0060	202.202 REMOVING PAVEMENT SURFACE	2,690.000 SY	_____	 _____	_____	 _____
0070	203.20 COMMON EXCAVATION	108,900.000 CY	_____	 _____	_____	 _____
0080	203.21 ROCK EXCAVATION	17,050.000 CY	_____	 _____	_____	 _____
0090	203.211 PRESPLITTING ROCK	9,800.000 LF	_____	 _____	_____	 _____
0100	203.213 DRILLING AND BLASTING OF SOLID ROCK SUBGRADE	3,400.000 SY	_____	 _____	_____	 _____
0110	203.25 GRANULAR BORROW	6,950.000 CY	_____	 _____	_____	 _____
0120	203.33 SPECIAL FILL	190.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	203.35 CRUSHED STONE FILL	180.000 CY	_____	 _____	_____	 _____
0140	204.20 ADD SHOULDER AGGREGATE TO EXISTING SHOULDER, PLAN QUANTITY	120.000 SY	_____	 _____	_____	 _____
0150	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	100.000 CY	_____	 _____	_____	 _____
0160	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	250.000 CY	_____	 _____	_____	 _____
0170	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	2,530.000 CY	_____	 _____	_____	 _____
0180	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	54.000 CY	_____	 _____	_____	 _____
0190	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	93,550.000 CY	_____	 _____	_____	 _____
0200	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	8,000.000 T	_____	 _____	_____	 _____
0210	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	2,290.000 T	_____	 _____	_____	 _____
0220	403.211 HOT MIX ASPHALT (SHIMMING)	50.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	403.213 HOT MIX ASPHALT 12.5 MM BASE	18,120.000 T	_____	 _____	_____	 _____
0240	409.15 BITUMINOUS TACK COAT - APPLIED	2,951.000 G	_____	 _____	_____	 _____
0250	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	100.000 CY	_____	 _____	_____	 _____
0260	461.131 TEMPORARY PAVEMENT	604.000 T	_____	 _____	_____	 _____
0270	501.502 ROCK SOCKETED H-PILES	147.000 LF	_____	 _____	_____	 _____
0280	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	147.000 LF	_____	 _____	_____	 _____
0290	501.804 DRILLING EQUIPMENT MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
0300	501.91 PILE SPLICES	7.000 EA	_____	 _____	_____	 _____
0310	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS WEYMOUTH	380.000 CY	_____	 _____	_____	 _____
0320	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS WING	460.000 CY	_____	 _____	_____	 _____
0330	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	390.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP	SUM	_____	_____
0350	502.291 SAW CUT GROOVING	LUMP SUM	LUMP	SUM	_____	_____
0360	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0370	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0380	502.565 CONCRETE FILL	20.000 CY	_____	_____	_____	_____
0390	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	79,900.000 LB	_____	_____	_____	_____
0400	503.13 REINFORCING STEEL, PLACING	79,900.000 LB	_____	_____	_____	_____
0410	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	64,100.000 LB	_____	_____	_____	_____
0420	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	64,100.000 LB	_____	_____	_____	_____
0430	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED WEYMOUTH	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00,
023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0440	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED WING	LUMP SUM	LUMP	SUM	_____	_____
0450	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____
0460	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0470	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0480	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0490	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 13'-7", WEYMOUTH	LUMP SUM	LUMP	SUM	_____	_____
0500	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 13'-7", WING	LUMP SUM	LUMP	SUM	_____	_____
0510	511.07 COFFERDAM: ABUT NO.1, WEYMOUTH	LUMP SUM	LUMP	SUM	_____	_____
0520	511.07 COFFERDAM: ABUT NO.1, WING	LUMP SUM	LUMP	SUM	_____	_____
0530	511.07 COFFERDAM: ABUT NO.2, WEYMOUTH	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0540	511.07 COFFERDAM: ABUT NO.2, WING	LUMP SUM	LUMP	SUM	_____	_____
0550	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0560	514.06 CURING BOX FOR CONCRETE CYLINDERS	2.000 EA	_____	_____	_____	_____
0570	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0580	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	17.000 SF	_____	_____	_____	_____
0590	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	194.000 LF	_____	_____	_____	_____
0600	523.52 BEARING INSTALLATION	15.000 EA	_____	_____	_____	_____
0610	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	5.000 EA	_____	_____	_____	_____
0620	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	10.000 EA	_____	_____	_____	_____
0630	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0640	526.34 PERMANENT CONCRETE TRANSITION BARRIER	8.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0650	527.34 WORK ZONE CRASH CUSHIONS	12.000 UN	_____	 _____	_____	 _____
0660	603.16 15 INCH CULVERT PIPE OPTION I	468.000 LF	_____	 _____	_____	 _____
0670	603.17 18 INCH CULVERT PIPE OPTION I	216.000 LF	_____	 _____	_____	 _____
0680	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	124.000 LF	_____	 _____	_____	 _____
0690	603.179 18 INCH CULVERT PIPE OPTION III	264.000 LF	_____	 _____	_____	 _____
0700	603.19 24 INCH CULVERT PIPE OPTION I	34.000 LF	_____	 _____	_____	 _____
0710	603.199 24 INCH CULVERT PIPE OPTION III	124.000 LF	_____	 _____	_____	 _____
0720	603.20 30 INCH CULVERT PIPE OPTION I	48.000 LF	_____	 _____	_____	 _____
0730	603.205 30 INCH REINFORCED CONCRETE PIPE CLASS III	382.000 LF	_____	 _____	_____	 _____
0740	603.209 30 INCH CULVERT PIPE OPTION III	256.000 LF	_____	 _____	_____	 _____
0750	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	292.000 LF	_____	 _____	_____	 _____
0760	603.219 36 INCH CULVERT PIPE OPTION III	164.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00,
023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0770	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	72.000 LF	_____	 _____	_____	 _____
0780	603.235 48 INCH REINFORCED CONCRETE PIPE CLASS III	312.000 LF	_____	 _____	_____	 _____
0790	603.245 54 INCH REINFORCED CONCRETE PIPE CLASS III	100.000 LF	_____	 _____	_____	 _____
0800	603.275 72 INCH REINFORCED CONCRETE PIPE CLASS III	104.000 LF	_____	 _____	_____	 _____
0810	603.55 CONCRETE PIPE TIES	88.000 GP	_____	 _____	_____	 _____
0820	603.78 18 INCH INLET GRATE UNIT	1.000 EA	_____	 _____	_____	 _____
0830	604.092 CATCH BASIN TYPE B1-C	8.000 EA	_____	 _____	_____	 _____
0840	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA	_____	 _____	_____	 _____
0850	605.09 6 INCH UNDERDRAIN TYPE B	6,610.000 LF	_____	 _____	_____	 _____
0860	605.10 6 INCH UNDERDRAIN OUTLET	420.000 LF	_____	 _____	_____	 _____
0870	605.13 18 INCH UNDERDRAIN TYPE C	680.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00,
023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0880	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	10,642.000 LF	_____	_____	_____	_____
0890	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	175.000 LF	_____	_____	_____	_____
0900	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	176.000 LF	_____	_____	_____	_____
0910	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	20.000 EA	_____	_____	_____	_____
0920	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1	8.000 EA	_____	_____	_____	_____
0930	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	_____	_____	_____
0940	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	_____	_____	_____
0950	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	58.000 EA	_____	_____	_____	_____
0960	606.356 UNDERDRAIN DELINEATOR POST	37.000 EA	_____	_____	_____	_____
0970	606.47 SINGLE WOOD POST	17.000 EA	_____	_____	_____	_____
0980	606.51 MULTIPLE MAILBOX SUPPORT	1.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00,
023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0990	606.66 TERMINAL END THRIE BEAM	1.000 EA	_____	 _____	_____	 _____
1000	606.71 GUARDRAIL THRIE BEAM - 15 FOOT RADIUS AND LESS	12.500 LF	_____	 _____	_____	 _____
1010	609.31 CURB TYPE 3	2,660.000 LF	_____	 _____	_____	 _____
1020	610.08 PLAIN RIPRAP	5,601.000 CY	_____	 _____	_____	 _____
1030	610.16 HEAVY RIPRAP	2,120.000 CY	_____	 _____	_____	 _____
1040	610.163 SPECIAL RIPRAP	30.000 CY	_____	 _____	_____	 _____
1050	610.18 STONE DITCH PROTECTION	700.000 CY	_____	 _____	_____	 _____
1060	613.319 EROSION CONTROL BLANKET	14,350.000 SY	_____	 _____	_____	 _____
1070	613.40 TURF REINFORCEMENT MAT - (TRM)	6,400.000 SY	_____	 _____	_____	 _____
1080	615.07 LOAM	7,340.000 CY	_____	 _____	_____	 _____
1090	615.081 COMPOST BLANKET	550.000 CY	_____	 _____	_____	 _____
1100	618.13 SEEDING METHOD NUMBER 1	97.000 UN	_____	 _____	_____	 _____
1110	618.14 SEEDING METHOD NUMBER 2	1,048.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1120	618.146 SEEDING HYDROMULCH MEDIUM	90.000 UN	_____	_____	_____	_____
1130	619.12 MULCH	1,145.000 UN	_____	_____	_____	_____
1140	619.14 EROSION CONTROL MIX	770.000 CY	_____	_____	_____	_____
1150	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	100.000 SY	_____	_____	_____	_____
1160	620.56 DRAINAGE GEOTEXTILE	570.000 SY	_____	_____	_____	_____
1170	620.58 EROSION CONTROL GEOTEXTILE	8,725.000 SY	_____	_____	_____	_____
1180	620.66 DRAINAGE GEOCOMPOSITE	80.000 SY	_____	_____	_____	_____
1190	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	76,232.000 LF	_____	_____	_____	_____
1200	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	160.000 SF	_____	_____	_____	_____
1210	627.77 REMOVING PAVEMENT MARKINGS	1,100.000 SF	_____	_____	_____	_____
1220	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	150,300.000 LF	_____	_____	_____	_____
1230	629.05 HAND LABOR, STRAIGHT TIME	110.000 HR	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1250	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
1260	631.13 BULLDOZER (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
1270	631.14 GRADER (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
1280	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
1290	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	120.000 HR	_____	 _____	_____	 _____
1300	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	90.000 HR	_____	 _____	_____	 _____
1310	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	50.000 HR	_____	 _____	_____	 _____
1320	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
1330	643.72 TEMPORARY TRAFFIC SIGNAL WEYMOUTH	LUMP SUM	_____	 LUMP SUM	_____	 _____
1340	643.72 TEMPORARY TRAFFIC SIGNAL WING	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00,
023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1350	645.103 DEMOUNT GUIDE SIGN	1.000 EA	_____	 _____	_____	 _____
1360	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	35.000 EA	_____	 _____	_____	 _____
1370	645.113 REINSTALL GUIDE SIGN	15.000 EA	_____	 _____	_____	 _____
1380	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	4.000 EA	_____	 _____	_____	 _____
1390	645.291 ROADSIDE GUIDE SIGNS TYPE II	60.000 SF	_____	 _____	_____	 _____
1400	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	410.000 SF	_____	 _____	_____	 _____
1410	645.60 ACTUATED DYNAMIC SIGNS	LUMP SUM		 LUMP SUM	_____	 _____
1420	652.30 FLASHING ARROW BOARD	2.000 EA	_____	 _____	_____	 _____
1430	652.312 TYPE III BARRICADE	8.000 EA	_____	 _____	_____	 _____
1440	652.33 DRUM	300.000 EA	_____	 _____	_____	 _____
1450	652.34 CONE	500.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018247.00

Project(s): 018247.00, 022615.00, 022616.00, 023100.00, 023102.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1460	652.35 CONSTRUCTION SIGNS	1,200.000 SF	_____	 _____	_____	 _____
1470	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Highway	494.000 CD	_____	 _____	_____	 _____
1480	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Weymouth Br.	250.000 CD	_____	 _____	_____	 _____
1490	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Wing Br.	250.000 CD	_____	 _____	_____	 _____
1500	652.38 FLAGGER	18,200.000 HR	_____	 _____	_____	 _____
1510	652.381 TRAFFIC OFFICER	350.000 HR	_____	 _____	_____	 _____
1520	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	6.000 EA	_____	 _____	_____	 _____
1530	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
1540	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
1550	660.21 ON-THE-JOB TRAINING (BID)	2,400.000 HR	_____	 _____	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____