

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	4.000 AC	_____	 _____	_____	 _____
0020	201.23 REMOVING SINGLE TREE TOP ONLY	52.000 EA	_____	 _____	_____	 _____
0030	201.24 REMOVING STUMP	65.000 EA	_____	 _____	_____	 _____
0040	202.203 PAVEMENT BUTT JOINTS	540.000 SY	_____	 _____	_____	 _____
0050	203.20 COMMON EXCAVATION	43,500.000 CY	_____	 _____	_____	 _____
0060	203.2318 DISPOSAL OF SPECIAL WASTE	30.000 T	_____	 _____	_____	 _____
0070	203.25 GRANULAR BORROW	250.000 CY	_____	 _____	_____	 _____
0080	203.33 SPECIAL FILL	350.000 CY	_____	 _____	_____	 _____
0090	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	100.000 CY	_____	 _____	_____	 _____
0100	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	195.000 CY	_____	 _____	_____	 _____
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	27,100.000 CY	_____	 _____	_____	 _____
0120	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	2,600.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	350.000 T	_____	 _____	_____	 _____
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	5,900.000 T	_____	 _____	_____	 _____
0150	409.15 BITUMINOUS TACK COAT - APPLIED	1,550.000 G	_____	 _____	_____	 _____
0160	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	145.000 CY	_____	 _____	_____	 _____
0170	502.565 CONCRETE FILL	10.000 CY	_____	 _____	_____	 _____
0180	511.07 COFFERDAM: GREAT BROOK DOWNSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____
0190	511.07 COFFERDAM: GREAT BROOK UPSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____
0200	511.07 COFFERDAM: SPRING BROOK DOWNSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____
0210	511.07 COFFERDAM: SPRING BROOK UPSTREAM	LUMP SUM	_____	 LUMP SUM	_____	 _____
0220	511.07 COFFERDAM: Sta. 155+38, Lt (Inlet)	LUMP SUM	_____	 LUMP SUM	_____	 _____
0230	511.07 COFFERDAM: Sta. 155+38, Rt (Outlet)	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	511.07 COFFERDAM: Sta. 87+66, Lt (Inlet)	LUMP SUM	LUMP	SUM	_____	_____
0250	511.07 COFFERDAM: Sta. 87+66, Rt.(outlet)	LUMP SUM	LUMP	SUM	_____	_____
0260	524.301 TEMPORARY STRUCTURAL SUPPORT - Great Brook	LUMP SUM	LUMP	SUM	_____	_____
0270	524.301 TEMPORARY STRUCTURAL SUPPORT - Spring Brook	LUMP SUM	LUMP	SUM	_____	_____
0280	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0290	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0300	531.51 BRIDGE STRUCTURE - DETAIL BUILD - SPRING BROOK	LUMP SUM	LUMP	SUM	_____	_____
0310	531.51 BRIDGE STRUCTURE - DETAIL BUILD GREAT BROOK	LUMP SUM	LUMP	SUM	_____	_____
0320	603.159 12 INCH CULVERT PIPE OPTION III Sta. 155+38, Rt (Outlet)	74.000 LF	_____	_____	_____	_____
0330	603.17 18 INCH CULVERT PIPE OPTION I	704.000 LF	_____	_____	_____	_____
0340	603.179 18 INCH CULVERT PIPE OPTION III	337.000 LF	_____	_____	_____	_____
0350	603.19 24 INCH CULVERT PIPE OPTION I	188.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	208.000 LF	_____	 _____	_____	 _____
0370	603.20 30 INCH CULVERT PIPE OPTION I	160.000 LF	_____	 _____	_____	 _____
0380	603.205 30 INCH REINFORCED CONCRETE PIPE CLASS III	192.000 LF	_____	 _____	_____	 _____
0390	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	88.000 LF	_____	 _____	_____	 _____
0400	603.219 36 INCH CULVERT PIPE OPTION III	204.000 LF	_____	 _____	_____	 _____
0410	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	80.000 LF	_____	 _____	_____	 _____
0420	603.229 42 INCH CULVERT PIPE OPTION III	74.000 LF	_____	 _____	_____	 _____
0430	603.235 48 INCH REINFORCED CONCRETE PIPE CLASS III	100.000 LF	_____	 _____	_____	 _____
0440	603.255 60 INCH REINFORCED CONCRETE PIPE CLASS III	76.000 LF	_____	 _____	_____	 _____
0450	603.55 CONCRETE PIPE TIES	40.000 GP	_____	 _____	_____	 _____
0460	604.09 CATCH BASIN TYPE B1	4.000 EA	_____	 _____	_____	 _____
0470	604.092 CATCH BASIN TYPE B1-C	10.375 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	604.096 60 INCH CATCH BASIN TYPE B1-C	1.000 EA	_____	 _____	_____	 _____
0490	604.244 CATCH BASIN TYPE F4	6.000 EA	_____	 _____	_____	 _____
0500	605.09 6 INCH UNDERDRAIN TYPE B	2,106.000 LF	_____	 _____	_____	 _____
0510	605.10 6 INCH UNDERDRAIN OUTLET	262.000 LF	_____	 _____	_____	 _____
0520	605.11 12 INCH UNDERDRAIN TYPE C	822.000 LF	_____	 _____	_____	 _____
0530	605.13 18 INCH UNDERDRAIN TYPE C	616.000 LF	_____	 _____	_____	 _____
0540	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	2,818.750 LF	_____	 _____	_____	 _____
0550	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	175.000 LF	_____	 _____	_____	 _____
0560	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA	_____	 _____	_____	 _____
0570	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	2.000 EA	_____	 _____	_____	 _____
0580	606.1308 BURIED-IN-SLOPE GUARDRAIL END, MID-WAY SPLICE	1.000 EA	_____	 _____	_____	 _____
0590	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	7.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0600	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	28.000 EA	_____	 _____	_____	 _____
0610	606.356 UNDERDRAIN DELINEATOR POST	14.000 EA	_____	 _____	_____	 _____
0620	609.31 CURB TYPE 3	1,548.000 LF	_____	 _____	_____	 _____
0630	610.08 PLAIN RIPRAP	2,300.000 CY	_____	 _____	_____	 _____
0640	610.16 HEAVY RIPRAP	878.000 CY	_____	 _____	_____	 _____
0650	610.18 STONE DITCH PROTECTION	420.000 CY	_____	 _____	_____	 _____
0660	610.210 STREAM CHANNEL ROCK	400.000 CY	_____	 _____	_____	 _____
0670	610.212 STREAMBED ROCK FEATURES	320.000 CY	_____	 _____	_____	 _____
0680	613.319 EROSION CONTROL BLANKET	2,520.000 SY	_____	 _____	_____	 _____
0690	613.40 TURF REINFORCEMENT MAT - (TRM)	290.000 SY	_____	 _____	_____	 _____
0700	615.07 LOAM	2,250.000 CY	_____	 _____	_____	 _____
0710	618.13 SEEDING METHOD NUMBER 1	20.000 UN	_____	 _____	_____	 _____
0720	618.14 SEEDING METHOD NUMBER 2	350.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0730	619.12 MULCH	370.000 UN	_____	 _____	_____	 _____
0740	620.58 EROSION CONTROL GEOTEXTILE	4,713.000 SY	_____	 _____	_____	 _____
0750	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	74,250.000 LF	_____	 _____	_____	 _____
0760	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	80.000 SF	_____	 _____	_____	 _____
0770	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	8,250.000 LF	_____	 _____	_____	 _____
0780	629.05 HAND LABOR, STRAIGHT TIME	65.000 HR	_____	 _____	_____	 _____
0790	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	440.000 HR	_____	 _____	_____	 _____
0800	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR	_____	 _____	_____	 _____
0810	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0820	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0830	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0840	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0850	643.72 TEMPORARY TRAFFIC SIGNAL - Great Brook	LUMP SUM	LUMP SUM		_____	 _____
0860	643.72 TEMPORARY TRAFFIC SIGNAL - Spring Brook	LUMP SUM	LUMP SUM		_____	 _____
0870	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	19.000 EA	_____	 _____	_____	 _____
0880	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	19.000 EA	_____	 _____	_____	 _____
0890	652.31 TYPE I BARRICADE	25.000 EA	_____	 _____	_____	 _____
0900	652.311 TYPE II BARRICADE	25.000 EA	_____	 _____	_____	 _____
0910	652.312 TYPE III BARRICADE	18.000 EA	_____	 _____	_____	 _____
0920	652.33 DRUM	120.000 EA	_____	 _____	_____	 _____
0930	652.34 CONE	200.000 EA	_____	 _____	_____	 _____
0940	652.35 CONSTRUCTION SIGNS	1,300.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018283.00

Project(s): 018283.00, 022608.00, 022610.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0950	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES WIN. 018283.00 - Highway	400.000 CD	_____	 _____	_____	 _____
0960	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Bridges	LUMP SUM	LUMP SUM		_____	 _____
0970	652.38 FLAGGER	8,240.000 HR	_____	 _____	_____	 _____
0980	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	8.000 EA	_____	 _____	_____	 _____
0990	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
1000	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
1010	660.21 ON-THE-JOB TRAINING (BID)	2,000.000 HR	_____	 _____	_____	 _____
1020	801.141 4" PVC SANITARY SEWER (SDR-35)	125.000 LF	_____	 _____	_____	 _____
1030	801.16 6 INCH PVC SANITARY SEWER (SDR-35)	50.000 LF	_____	 _____	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____