

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	107.51 PROSECUTION OF WORK - INITIAL SCHEDULE	LUMP SUM	LUMP	SUM	_____	_____
0020	107.531 BI-WEEKLY UPDATES	1.000 LS	_____	_____	_____	_____
0030	201.11 CLEARING	3.000 AC	_____	_____	_____	_____
0040	201.23 REMOVING SINGLE TREE TOP ONLY	5.000 EA	_____	_____	_____	_____
0050	201.24 REMOVING STUMP	5.000 EA	_____	_____	_____	_____
0060	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	179.000 CY	_____	_____	_____	_____
0070	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	10.000 EA	_____	_____	_____	_____
0080	202.19 REMOVING EXISTING BRIDGE 959 CY	LUMP SUM	LUMP	SUM	_____	_____
0090	202.202 REMOVING PAVEMENT SURFACE	24,010.000 SY	_____	_____	_____	_____
0100	202.21 REMOVING EXISTING SUBSTRUCTURE	265.000 CY	_____	_____	_____	_____
0110	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE BRIDGE 5823 (1540 SY)	LUMP SUM	LUMP	SUM	_____	_____
0120	203.20 COMMON EXCAVATION	27,400.000 CY	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	203.24 COMMON BORROW	31,700.000 CY	_____	 _____	_____	 _____
0140	203.25 GRANULAR BORROW	13,630.000 CY	_____	 _____	_____	 _____
0150	203.4338 LIGHTWEIGHT FILL FOAMED GLASS AGGREGATE	19,600.000 CY	_____	 _____	_____	 _____
0160	203.4340 ELASTIC INCLUSION	136.000 SY	_____	 _____	_____	 _____
0170	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	2,490.000 CY	_____	 _____	_____	 _____
0180	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	26,600.000 CY	_____	 _____	_____	 _____
0190	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	5,500.000 T	_____	 _____	_____	 _____
0200	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	420.000 T	_____	 _____	_____	 _____
0210	403.2111 9.5 MM POLYMER MODIFIED HMA (SHIM)	720.000 T	_____	 _____	_____	 _____
0220	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	10,370.000 T	_____	 _____	_____	 _____
0230	409.15 BITUMINOUS TACK COAT - APPLIED	4,960.000 G	_____	 _____	_____	 _____
0240	461.131 TEMPORARY PAVEMENT	2,500.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	501.231 DYNAMIC LOADING TEST	10.000 EA	_____	 _____	_____	 _____
0260	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	4,950.000 LF	_____	 _____	_____	 _____
0270	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	2,920.000 LF	_____	 _____	_____	 _____
0280	501.502 ROCK SOCKETED H-PILES	1,460.000 LF	_____	 _____	_____	 _____
0290	501.804 DRILLING EQUIPMENT MOBILIZATION BRIDGE 5823	LUMP SUM		LUMP SUM	_____	 _____
0300	501.804 DRILLING EQUIPMENT MOBILIZATION BRIDGE 6787	LUMP SUM		LUMP SUM	_____	 _____
0310	501.90 PILE TIPS	86.000 EA	_____	 _____	_____	 _____
0320	501.91 PILE SPLICES	10.000 EA	_____	 _____	_____	 _____
0330	501.92 PILE DRIVING EQUIPMENT MOBILIZATION BRIDGE 5823	LUMP SUM		LUMP SUM	_____	 _____
0340	501.92 PILE DRIVING EQUIPMENT MOBILIZATION BRIDGE 6787	LUMP SUM		LUMP SUM	_____	 _____
0350	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS BRIDGE 5823	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____
0370	502.239 STRUCTURAL CONCRETE PIERS BRIDGE 5823	LUMP SUM	LUMP	SUM	_____	_____
0380	502.239 STRUCTURAL CONCRETE PIERS BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____
0390	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES BRIDGE 5823	LUMP SUM	LUMP	SUM	_____	_____
0400	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____
0410	502.31 STRUCTURAL CONCRETE APPROACH SLABS BRIDGE 5823	LUMP SUM	LUMP	SUM	_____	_____
0420	502.31 STRUCTURAL CONCRETE APPROACH SLABS BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____
0430	502.453 STRUCTURAL CONCRETE MOMENT SLAB	LUMP SUM	LUMP	SUM	_____	_____
0440	502.454 STRUCTURAL CONCRETE SLEEPER SLAB BRIDGE 5823	LUMP SUM	LUMP	SUM	_____	_____
0450	502.454 STRUCTURAL CONCRETE SLEEPER SLAB BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS BRIDGE 5823	LUMP SUM	LUMP	SUM	_____	_____
0470	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____
0480	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: A MODIFIED	4.000 EA	_____	_____	_____	_____
0490	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: E	5.000 EA	_____	_____	_____	_____
0500	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: F	8.000 EA	_____	_____	_____	_____
0510	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	250,300.000 LB	_____	_____	_____	_____
0520	503.13 REINFORCING STEEL, PLACING	250,300.000 LB	_____	_____	_____	_____
0530	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	331,800.000 LB	_____	_____	_____	_____
0540	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	331,800.000 LB	_____	_____	_____	_____
0550	504.70 STRUCTURAL STEEL FABRICATED AND DELIVERED	LUMP SUM	LUMP	SUM	_____	_____
0560	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____
0580	504.73 REMOVING, MODIFYING, AND RESETTING EXISTING STRUCTURAL STEEL	LUMP SUM	LUMP	SUM	_____	_____
0590	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0600	506.144 FIELD PAINTING NEW AND EXISTING STRUCTURAL STEEL	LUMP SUM	LUMP	SUM	_____	_____
0610	506.17 SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	LUMP SUM	LUMP	SUM	_____	_____
0620	506.18 CONTAINMENT AND POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0630	506.191 DISPOSAL OF SPECIAL WASTE OR HAZARDOUS WASTE MATERIAL	LUMP SUM	LUMP	SUM	_____	_____
0640	506.9104 THERMAL SPRAY COATING - SHOP APPLIED	LUMP SUM	LUMP	SUM	_____	_____
0650	507.0821 STEEL BRIDGE RAILING, 3 BAR BRIDGE 5823	LUMP SUM	LUMP	SUM	_____	_____
0660	507.0821 STEEL BRIDGE RAILING, 3 BAR BRIDGE 6787	LUMP SUM	LUMP	SUM	_____	_____
0670	507.0822 STEEL APPROACH RAILING, 3-BAR	1.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	507.0822 STEEL APPROACH RAILING, 3-BAR MODIFIED	7.000 EA	_____	 _____	_____	 _____
0690	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE BRIDGE 5823	LUMP SUM	LUMP	 SUM	_____	 _____
0700	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE BRIDGE 6787	LUMP SUM	LUMP	 SUM	_____	 _____
0710	512.081 FRENCH DRAINS BRIDGE 5823	LUMP SUM	LUMP	 SUM	_____	 _____
0720	512.081 FRENCH DRAINS BRIDGE 6787	LUMP SUM	LUMP	 SUM	_____	 _____
0730	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES BRIDGE 5823	LUMP SUM	LUMP	 SUM	_____	 _____
0740	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES BRIDGE 6787	LUMP SUM	LUMP	 SUM	_____	 _____
0750	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	670.000 SF	_____	 _____	_____	 _____
0760	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	220.000 SF	_____	 _____	_____	 _____
0770	522.06 MODULAR EXPANSION DEVICE	4.000 EA	_____	 _____	_____	 _____
0780	523.52 BEARING INSTALLATION	84.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0790	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	84.000 EA	_____	 _____	_____	 _____
0800	524.301 TEMPORARY STRUCTURAL SUPPORT APPROACHES	LUMP SUM	LUMP	 SUM	_____	 _____
0810	524.301 TEMPORARY STRUCTURAL SUPPORT SUPERSTRUCTURE	LUMP SUM	LUMP	 SUM	_____	 _____
0820	524.40 PROTECTIVE SHIELD BRIDGE 5823 (780 SY)	LUMP SUM	LUMP	 SUM	_____	 _____
0830	524.40 PROTECTIVE SHIELD BRIDGE 6787 (1600 SY)	LUMP SUM	LUMP	 SUM	_____	 _____
0840	526.302 PORTABLE CONCRETE BARRIER	2,800.000 LF	_____	 _____	_____	 _____
0850	526.322 PERMANENT CONCRETE BARRIER TYPE III MODIFIED	756.000 LF	_____	 _____	_____	 _____
0860	526.502 PRECAST CONCRETE MEDIAN BARRIER	LUMP SUM	LUMP	 SUM	_____	 _____
0870	527.305 QUADGUARD CRASH CUSHION	1.000 UN	_____	 _____	_____	 _____
0880	527.34 WORK ZONE CRASH CUSHIONS	10.000 UN	_____	 _____	_____	 _____
0890	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	187,400.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0900	530.31 GFRP, REINFORCEMENT BARS, PLACING	187,400.000 LF	_____	 _____	_____	 _____
0910	603.04 4" PVC DRAIN SERVICE	4.000 LF	_____	 _____	_____	 _____
0920	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	430.000 LF	_____	 _____	_____	 _____
0930	603.159 12 INCH CULVERT PIPE OPTION III	680.000 LF	_____	 _____	_____	 _____
0940	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	120.000 LF	_____	 _____	_____	 _____
0950	603.169 15 INCH CULVERT PIPE OPTION III	20.000 LF	_____	 _____	_____	 _____
0960	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	230.000 LF	_____	 _____	_____	 _____
0970	603.179 18 INCH CULVERT PIPE OPTION III	400.000 LF	_____	 _____	_____	 _____
0980	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	420.000 LF	_____	 _____	_____	 _____
0990	603.55 CONCRETE PIPE TIES	9.000 GP	_____	 _____	_____	 _____
1000	603.93 DIRECTIONAL BORE STA 1005+35	170.000 LF	_____	 _____	_____	 _____
1010	604.072 CATCH BASIN TYPE A1-C	11.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1020	604.09 CATCH BASIN TYPE B1	3.000 EA	_____	 _____	_____	 _____
1030	604.092 CATCH BASIN TYPE B1-C	35.000 EA	_____	 _____	_____	 _____
1040	604.247 CATCH BASIN TYPE F5-C	10.000 EA	_____	 _____	_____	 _____
1050	604.249 CATCH BASIN TYPE F6-C	1.000 EA	_____	 _____	_____	 _____
1060	605.09 6 INCH UNDERDRAIN TYPE B	2,000.000 LF	_____	 _____	_____	 _____
1070	605.11 12 INCH UNDERDRAIN TYPE C	2,100.000 LF	_____	 _____	_____	 _____
1080	605.12 15 INCH UNDERDRAIN TYPE C	350.000 LF	_____	 _____	_____	 _____
1090	605.13 18 INCH UNDERDRAIN TYPE C	78.000 LF	_____	 _____	_____	 _____
1100	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	5,100.000 LF	_____	 _____	_____	 _____
1110	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	190.000 LF	_____	 _____	_____	 _____
1120	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA	_____	 _____	_____	 _____
1130	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1A	8.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1140	606.1721 BRIDGE TRANSITION - TYPE 1	8.000 EA	_____	 _____	_____	 _____
1150	606.259 ANCHORAGE ASSEMBLY	4.000 EA	_____	 _____	_____	 _____
1160	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	12.000 EA	_____	 _____	_____	 _____
1170	606.356 UNDERDRAIN DELINEATOR POST	19.000 EA	_____	 _____	_____	 _____
1180	607.09 WOVEN WIRE FENCE - METAL POSTS	180.000 LF	_____	 _____	_____	 _____
1190	607.16 CHAIN LINK FENCE - 4 FOOT	1,900.000 LF	_____	 _____	_____	 _____
1200	607.183 CHAIN LINK SNOW FENCE 33 INCH BRIDGE 5823	LUMP SUM	LUMP SUM		_____	 _____
1210	607.183 CHAIN LINK SNOW FENCE 33 INCH BRIDGE 6787	LUMP SUM	LUMP SUM		_____	 _____
1220	607.33 BRACING ASSEMBLY TYPE II - METAL POSTS	2.000 EA	_____	 _____	_____	 _____
1230	608.07 PLAIN CONCRETE SIDEWALK	44.000 SY	_____	 _____	_____	 _____
1240	608.26 CURB RAMP DETECTABLE WARNING FIELD	420.000 SF	_____	 _____	_____	 _____
1250	609.11 VERTICAL CURB TYPE 1	2,500.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1260	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	120.000 LF	_____	 _____	_____	 _____
1270	609.221 TERMINAL CURB TYPE 1	160.000 LF	_____	 _____	_____	 _____
1280	609.222 TERMINAL CURB TYPE 1 - CIRCULAR	88.000 LF	_____	 _____	_____	 _____
1290	609.312 SPECIAL CURB WHEEL STOP	77.000 LF	_____	 _____	_____	 _____
1300	609.34 CURB TYPE 5	5,400.000 LF	_____	 _____	_____	 _____
1310	609.35 CURB TYPE 5 - CIRCULAR	150.000 LF	_____	 _____	_____	 _____
1320	610.08 PLAIN RIPRAP	1,602.000 CY	_____	 _____	_____	 _____
1330	610.16 HEAVY RIPRAP	440.000 CY	_____	 _____	_____	 _____
1340	613.319 EROSION CONTROL BLANKET	2,190.000 SY	_____	 _____	_____	 _____
1350	615.07 LOAM	6,400.000 CY	_____	 _____	_____	 _____
1360	615.081 COMPOST BLANKET	110.000 CY	_____	 _____	_____	 _____
1370	615.27 UNDERDRAIN SOIL FILTER 5 EACH	LUMP SUM		 LUMP SUM	_____	 _____
1380	617.35 COMPOST	40.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1390	618.13 SEEDING METHOD NUMBER 1	58.000 UN	_____	 _____	_____	 _____
1400	618.14 SEEDING METHOD NUMBER 2	370.000 UN	_____	 _____	_____	 _____
1410	618.143 SPECIAL SEED MIX: A LOW GROWTH MEADOW MIX	85.000 UN	_____	 _____	_____	 _____
1420	618.146 HGM BIOTIC SOIL HYDROMULCH MEDIA	21.000 UN	_____	 _____	_____	 _____
1430	619.12 MULCH	520.000 UN	_____	 _____	_____	 _____
1440	619.13 BARK MULCH	40.000 CY	_____	 _____	_____	 _____
1450	620.58 EROSION CONTROL GEOTEXTILE	2,950.000 SY	_____	 _____	_____	 _____
1460	621.031 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP A	40.000 EA	_____	 _____	_____	 _____
1470	621.401 EVERGREENS (2 FOOT - 2.50 FOOT) GROUP A	30.000 EA	_____	 _____	_____	 _____
1480	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	80.000 EA	_____	 _____	_____	 _____
1490	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	50.000 EA	_____	 _____	_____	 _____
1500	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	60.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1510	626.11 PRECAST CONCRETE JUNCTION BOX	121.000 EA	_____	 _____	_____	 _____
1520	626.21 METALLIC CONDUIT	1,000.000 LF	_____	 _____	_____	 _____
1530	626.22 NON-METALLIC CONDUIT 2-INCH, LIGHTING	11,000.000 LF	_____	 _____	_____	 _____
1540	626.22 NON-METALLIC CONDUIT 3-INCH, SIGNALS	3,400.000 LF	_____	 _____	_____	 _____
1550	626.221 NON-METALLIC CONDUIT CONCRETE ENCASED	455.000 LF	_____	 _____	_____	 _____
1560	626.251 NON-METALLIC UNDER PAVEMENT CONDUIT (SCHEDULE 80 OR GREATER RATING)	1,500.000 LF	_____	 _____	_____	 _____
1570	626.35 CONTROLLER CABINET FOUNDATION	4.000 EA	_____	 _____	_____	 _____
1580	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	28.000 EA	_____	 _____	_____	 _____
1590	626.421 24 INCH DIAMETER FOUNDATION	168.000 LF	_____	 _____	_____	 _____
1600	626.46 48 INCH DIAMETER FOUNDATION	158.000 LF	_____	 _____	_____	 _____
1610	626.48 60 INCH DIAMETER FOUNDATION	45.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1620	626.49 GREATER THAN 60-INCH DIAMETER FOUNDATION 72 INCH	20.000 LF	_____	_____	_____	_____
1630	627.311 8 INCH WHITE PAVEMENT MARKING LINE	2,300.000 LF	_____	_____	_____	_____
1640	627.407 REFLECTORIZED PLASTIC WHITE OR YELLOW PAVEMENT MARKING	60.000 SF	_____	_____	_____	_____
1650	627.511 TEMPORARY PAVEMENT LINE TAPE, YELLOW OR WHITE	1,775.000 SF	_____	_____	_____	_____
1660	627.512 REMOVABLE BLACK LINE MASKING TAPE	2,500.000 SF	_____	_____	_____	_____
1670	627.55 12" TEMPORARY PAVEMENT TAPE, WHITE	250.000 LF	_____	_____	_____	_____
1680	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	28,000.000 LF	_____	_____	_____	_____
1690	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	15,500.000 LF	_____	_____	_____	_____
1700	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	5,600.000 SF	_____	_____	_____	_____
1710	627.752 TEMPORARY WHITE OR YELLOW PAVEMENT & CURB MARKING	1,125.000 SF	_____	_____	_____	_____
1720	627.77 REMOVING PAVEMENT MARKINGS	5,200.000 SF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1730	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	96,000.000 LF	_____	 _____	_____	 _____
1740	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	39,000.000 LF	_____	 _____	_____	 _____
1750	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	 _____	_____	 _____
1760	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR	_____	 _____	_____	 _____
1770	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	200.000 HR	_____	 _____	_____	 _____
1780	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
1790	634.160 HIGHWAY LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____
1800	634.2042 LED LUMINARIES	7.000 EA	_____	 _____	_____	 _____
1810	634.206 LIGHT STANDARD FOR POST TOP LUMINAIRE	58.000 EA	_____	 _____	_____	 _____
1820	634.25 SERVICE POLE COMPLETE WITH CABINET AND CONTROLS	2.000 EA	_____	 _____	_____	 _____
1830	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1840	643.21 NON-INVASIVE DETECTION - STOP LINE: HOGAN RD & I-95 SOUTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
1850	643.21 NON-INVASIVE DETECTION - STOP LINE: HOGAN RD & HASKELL RD / SYLVAN RD	LUMP SUM	LUMP	SUM	_____	_____
1860	643.21 NON-INVASIVE DETECTION - STOP LINE: HOGAN RD & I-95 NORTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
1870	643.21 NON-INVASIVE DETECTION - STOP LINE: HOGAN RD & SPRINGER DR / BANGOR MALL BLVD	LUMP SUM	LUMP	SUM	_____	_____
1880	643.22 NON-INVASIVE DETECTION - ADVANCE: HOGAN RD & I-95 SOUTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
1890	643.22 NON-INVASIVE DETECTION - ADVANCE: HOGAN RD & HASKELL RD / SYLVAN RD	LUMP SUM	LUMP	SUM	_____	_____
1900	643.22 NON-INVASIVE DETECTION - ADVANCE: HOGAN RD & I-95 NORTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
1910	643.22 NON-INVASIVE DETECTION - ADVANCE: HOGAN RD & SPRINGER DR / BANGOR MALL BLVD	LUMP SUM	LUMP	SUM	_____	_____
1920	643.621 RECTANGULAR RAPID FLASHING BEACON ASSEMBLY	2.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1930	643.71 TRAFFIC SIGNAL MODIFICATION HOGAN RD & MT HOPE AVE	LUMP SUM	LUMP	SUM	_____	_____
1940	643.71 TRAFFIC SIGNAL MODIFICATION HOGAN RD & EMCC / DRIVEWAY	LUMP SUM	LUMP	SUM	_____	_____
1950	643.71 TRAFFIC SIGNAL MODIFICATION HOGAN RD & HASKELL RD / SYLVAN RD	LUMP SUM	LUMP	SUM	_____	_____
1960	643.71 TRAFFIC SIGNAL MODIFICATION HOGAN RD & SPRINGER DR / BANGOR MALL RD	LUMP SUM	LUMP	SUM	_____	_____
1970	643.711 TRAFFIC SIGNAL MODIFICATION (TEMPORARY)	LUMP SUM	LUMP	SUM	_____	_____
1980	643.72 TEMPORARY TRAFFIC SIGNAL HOGAN RD & I-95 NORTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
1990	643.72 TEMPORARY TRAFFIC SIGNAL HOGAN RD & I-95 SOUTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
2000	643.80 TRAFFIC SIGNALS AT HOGAN RD & I-95 NORTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
2010	643.80 TRAFFIC SIGNALS AT HOGAN RD & I-95 SOUTHBOUND RAMPS	LUMP SUM	LUMP	SUM	_____	_____
2020	643.81 TRAFFIC SIGNAL CONTROL SYSTEM	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2030	643.90 INTERCONNECT WIRE	LUMP SUM				
2040	643.91 MAST ARM POLE W/15' ARM	2.000 EA				
2050	643.91 MAST ARM POLE W/35' ARM	1.000 EA				
2060	643.91 MAST ARM POLE W/40' ARM	1.000 EA				
2070	643.91 MAST ARM POLE W/55' ARM	1.000 EA				
2080	643.92 PEDESTAL POLE	20.000 EA				
2090	643.93 STRAIN POLE	4.000 EA				
2100	643.94 DUAL PURPOSE POLE W/30' ARM	1.000 EA				
2110	643.94 DUAL PURPOSE POLE W/45' ARM	1.000 EA				
2120	643.94 DUAL PURPOSE POLE W/50' ARM	1.000 EA				
2130	643.94 DUAL PURPOSE POLE W/55' ARM	1.000 EA				
2140	643.94 DUAL PURPOSE POLE W/60' ARM	3.000 EA				
2150	645.103 DEMOUNT GUIDE SIGN	5.000 EA				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2160	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	79.000 EA	_____	 _____	_____	 _____
2170	645.109 REMOVE AND SALVAGE HIGHWAY SIGNS	5.000 EA	_____	 _____	_____	 _____
2180	645.1095 REMOVE OVERHEAD SPAN WIRE SYSTEM WITH SIGNS STA 14+60	LUMP SUM		LUMP SUM	_____	 _____
2190	645.1095 REMOVE OVERHEAD SPAN WIRE SYSTEM WITH SIGNS STA 220+10	LUMP SUM		LUMP SUM	_____	 _____
2200	645.1096 REMOVE MAST ARM POLE WITH SIGNS STA 21+05	LUMP SUM		LUMP SUM	_____	 _____
2210	645.1096 REMOVE MAST ARM POLE WITH SIGNS STA 27+15	LUMP SUM		LUMP SUM	_____	 _____
2220	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	6.000 EA	_____	 _____	_____	 _____
2230	645.12 OVERHEAD GUIDE SIGN: STA 219+25	LUMP SUM		LUMP SUM	_____	 _____
2240	645.121 OVERHEAD LANE USE SIGN ASSEMBLY	2.000 EA	_____	 _____	_____	 _____
2250	645.15 CANTILEVER GUIDE SIGN STA 17+40	LUMP SUM		LUMP SUM	_____	 _____
2260	645.15 CANTILEVER GUIDE SIGN STA 900+15	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2270	645.251 ROADSIDE GUIDE SIGNS, TYPE I	815.000 SF	_____	 _____	_____	 _____
2280	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	400.000 SF	_____	 _____	_____	 _____
2290	652.35 CONSTRUCTION SIGNS	1,730.000 SF	_____	 _____	_____	 _____
2300	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES 1400 CD	LUMP SUM	LUMP SUM		_____	 _____
2310	652.38 FLAGGER	9,750.000 HR	_____	 _____	_____	 _____
2320	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	8.000 EA	_____	 _____	_____	 _____
2330	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP SUM		_____	 _____
2340	654.351 CONNECTED ROADSIDE UNIT (RSU)	4.000 EA	_____	 _____	_____	 _____
2350	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
2360	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	560.000 SY	_____	 _____	_____	 _____
2370	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018595.11

Project(s): 018595.11

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
2380	660.21 ON-THE-JOB TRAINING (BID)	3,000.000 HR	_____	 _____	_____	 _____
Section: 1			Total:		_____	
			Total Bid:		_____	