

4/12/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 018786.20

Project(s): 018786.20

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	2,750.000 SY	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	5,700.000 CY	_____	 _____	_____	 _____
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	4,600.000 CY	_____	 _____	_____	 _____
0040	403.213 HOT MIX ASPHALT 12.5 MM BASE	30.000 T	_____	 _____	_____	 _____
0050	409.15 BITUMINOUS TACK COAT - APPLIED	10.000 G	_____	 _____	_____	 _____
0060	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP SUM		_____	 _____
0070	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP SUM		_____	 _____
0080	602.30 FLOWABLE CONCRETE FILL	12.000 CY	_____	 _____	_____	 _____
0090	603.16 15 INCH CULVERT PIPE OPTION I	510.000 LF	_____	 _____	_____	 _____
0100	603.179 18 INCH CULVERT PIPE OPTION III	89.000 LF	_____	 _____	_____	 _____
0110	603.199 24 INCH CULVERT PIPE OPTION III	144.000 LF	_____	 _____	_____	 _____
0120	603.239 48 INCH CULVERT PIPE OPTION III	86.000 LF	_____	 _____	_____	 _____
0130	604.092 CATCH BASIN TYPE B1-C	6.000 EA	_____	 _____	_____	 _____

4/12/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 018786.20

Project(s): 018786.20

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0140	605.09 6 INCH UNDERDRAIN TYPE B	1,233.000 LF				
0150	605.10 6 INCH UNDERDRAIN OUTLET	37.000 LF				
0160	605.11 12 INCH UNDERDRAIN TYPE C	196.000 LF				
0170	605.15 24 INCH UNDERDRAIN TYPE C	164.000 LF				
0180	610.08 PLAIN RIPRAP	30.000 CY				
0190	610.18 STONE DITCH PROTECTION	110.000 CY				
0200	613.319 EROSION CONTROL BLANKET	1,040.000 SY				
0210	618.14 SEEDING METHOD NUMBER 2	10.000 UN				
0220	619.12 MULCH	10.000 UN				
0230	620.58 EROSION CONTROL GEOTEXTILE	560.000 SY				
0240	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0250	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0260	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				

4/12/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 018786.20

Project(s): 018786.20

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0270	639.21 FIELD OFFICE TYPE D	1.000 EA	_____	_____	_____	_____
0280	652.33 DRUM	40.000 EA	_____	_____	_____	_____
0290	652.34 CONE	60.000 EA	_____	_____	_____	_____
0300	652.35 CONSTRUCTION SIGNS	600.000 SF	_____	_____	_____	_____
0310	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	70.000 CD	_____	_____	_____	_____
0320	652.38 FLAGGER	1,420.000 HR	_____	_____	_____	_____
0330	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0340	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0350	801.03 TEST PITS	1.000 EA	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____