

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018834.00

Project(s): 018834.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	280.000 CY	_____	 _____	_____	 _____
0020	203.24 COMMON BORROW	150.000 CY	_____	 _____	_____	 _____
0030	203.25 GRANULAR BORROW	120.000 CY	_____	 _____	_____	 _____
0040	203.33 SPECIAL FILL	50.000 CY	_____	 _____	_____	 _____
0050	203.55 CULVERT BEDDING STONE	100.000 CY	_____	 _____	_____	 _____
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY	_____	 _____	_____	 _____
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	220.000 CY	_____	 _____	_____	 _____
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	51.000 T	_____	 _____	_____	 _____
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	53.000 T	_____	 _____	_____	 _____
0100	409.15 BITUMINOUS TACK COAT - APPLIED	14.000 G	_____	 _____	_____	 _____
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM		 LUMP SUM	_____	 _____
0120	511.07 COFFERDAM: UPSTREAM	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018834.00

Project(s): 018834.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM				
0140	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0150	603.299 96" CULVERT PIPE OPTION III	116.000 LF				
0160	606.363 GUARDRAIL REMOVE AND DISPOSE	500.000 LF				
0170	610.08 PLAIN RIPRAP	60.000 CY				
0180	610.210 STREAM CHANNEL ROCK	30.000 CY				
0190	610.212 STREAMBED ROCK FEATURES	10.000 CY				
0200	613.319 EROSION CONTROL BLANKET	80.000 SY				
0210	615.10 DIRTY BORROW	80.000 CY				
0220	618.14 SEEDING METHOD NUMBER 2	15.000 UN				
0230	619.12 MULCH	15.000 UN				
0240	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	330.000 SY				
0250	620.58 EROSION CONTROL GEOTEXTILE	130.000 SY				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018834.00

Project(s): 018834.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0260	620.65 REINFORCEMENT GEOGRID	140.000 SY	_____	 _____	_____	 _____
0270	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	660.000 LF	_____	 _____	_____	 _____
0280	629.05 HAND LABOR, STRAIGHT TIME	60.000 HR	_____	 _____	_____	 _____
0290	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0300	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0310	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0320	643.72 TEMPORARY TRAFFIC SIGNAL at Port Rd.	LUMP SUM	LUMP SUM		_____	 _____
0330	652.33 DRUM	10.000 EA	_____	 _____	_____	 _____
0340	652.34 CONE	75.000 EA	_____	 _____	_____	 _____
0350	652.35 CONSTRUCTION SIGNS	230.000 SF	_____	 _____	_____	 _____
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	30.000 CD	_____	 _____	_____	 _____
0370	652.38 FLAGGER	150.000 HR	_____	 _____	_____	 _____

6/3/2020

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 4

Proposal ID: 018834.00

Project(s): 018834.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0390	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0400	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____