

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018892.00

Project(s): 018892.00, 022508.00, 022509.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	9.000 EA	_____	 _____	_____	 _____
0020	201.24 REMOVING STUMP	9.000 EA	_____	 _____	_____	 _____
0030	202.202 REMOVING PAVEMENT SURFACE	4,200.000 SY	_____	 _____	_____	 _____
0040	202.203 PAVEMENT BUTT JOINTS	1,160.000 SY	_____	 _____	_____	 _____
0050	203.20 COMMON EXCAVATION	3,140.000 CY	_____	 _____	_____	 _____
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,180.000 CY	_____	 _____	_____	 _____
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	130.000 T	_____	 _____	_____	 _____
0080	403.2101 9.5 MM POLYMER MODIFIED HMA	1,210.000 T	_____	 _____	_____	 _____
0090	403.211 HOT MIX ASPHALT (SHIMMING)	90.000 T	_____	 _____	_____	 _____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	2,290.000 T	_____	 _____	_____	 _____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	1,010.000 G	_____	 _____	_____	 _____
0120	603.16 15 INCH CULVERT PIPE OPTION I	430.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018892.00

Project(s): 018892.00, 022508.00, 022509.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	730.000 LF	_____	 _____	_____	 _____
0140	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	 _____	_____	 _____
0150	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	 _____	_____	 _____
0160	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	 _____	_____	 _____
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	5.000 EA	_____	 _____	_____	 _____
0180	606.47 SINGLE WOOD POST	6.000 EA	_____	 _____	_____	 _____
0190	609.31 CURB TYPE 3	910.000 LF	_____	 _____	_____	 _____
0200	610.08 PLAIN RIPRAP	54.000 CY	_____	 _____	_____	 _____
0210	613.319 EROSION CONTROL BLANKET	387.000 SY	_____	 _____	_____	 _____
0220	615.07 LOAM	276.000 CY	_____	 _____	_____	 _____
0230	618.13 SEEDING METHOD NUMBER 1	10.000 UN	_____	 _____	_____	 _____
0240	618.14 SEEDING METHOD NUMBER 2	27.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018892.00

Project(s): 018892.00, 022508.00, 022509.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	619.12 MULCH	37.000 UN	_____	 _____	_____	 _____
0260	620.58 EROSION CONTROL GEOTEXTILE	190.000 SY	_____	 _____	_____	 _____
0270	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	13,600.000 LF	_____	 _____	_____	 _____
0280	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	750.000 SF	_____	 _____	_____	 _____
0290	627.77 REMOVING PAVEMENT MARKINGS	1,450.000 SF	_____	 _____	_____	 _____
0300	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	13,600.000 LF	_____	 _____	_____	 _____
0310	629.05 HAND LABOR, STRAIGHT TIME	30.000 HR	_____	 _____	_____	 _____
0320	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0330	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0340	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
0350	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	15.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018892.00

Project(s): 018892.00, 022508.00, 022509.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	639.19 FIELD OFFICE TYPE B	0.990 EA	_____	 _____	_____	 _____
0370	652.33 DRUM	190.000 EA	_____	 _____	_____	 _____
0380	652.34 CONE	190.000 EA	_____	 _____	_____	 _____
0390	652.35 CONSTRUCTION SIGNS	960.000 SF	_____	 _____	_____	 _____
0400	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	183.000 CD	_____	 _____	_____	 _____
0410	652.38 FLAGGER	3,600.000 HR	_____	 _____	_____	 _____
0420	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0430	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0440	812.162 ADJUSTING SEWER MANHOLE TO GRADE	5.000 EA	_____	 _____	_____	 _____
0450	812.163 MODIFY SEWER MH, ADJUST FRAME & COVER	3.000 EA	_____	 _____	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____