

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018949.00

Project(s): 018949.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.121 REMOVING EXISTING CONCRETE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	1,425.000 SY	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	855.000 CY	_____	_____	_____	_____
0040	203.24 COMMON BORROW	60.000 CY	_____	_____	_____	_____
0050	203.25 GRANULAR BORROW	400.000 CY	_____	_____	_____	_____
0060	203.33 SPECIAL FILL	100.000 CY	_____	_____	_____	_____
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	110.000 CY	_____	_____	_____	_____
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	700.000 CY	_____	_____	_____	_____
0090	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	215.000 T	_____	_____	_____	_____
0100	403.211 HOT MIX ASPHALT (SHIMMING)	10.000 T	_____	_____	_____	_____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	170.000 T	_____	_____	_____	_____
0120	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	100.000 T	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018949.00

Project(s): 018949.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	409.15 BITUMINOUS TACK COAT - APPLIED	171.000 G	_____	 _____	_____	 _____
0140	461.131 TEMPORARY PAVEMENT	60.000 T	_____	 _____	_____	 _____
0150	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	 SUM	_____	 _____
0160	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP	 SUM	_____	 _____
0170	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP	 SUM	_____	 _____
0180	513.22 CRUSHED STONE SLOPE PROTECTION	125.000 SY	_____	 _____	_____	 _____
0190	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	 SUM	_____	 _____
0200	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	 SUM	_____	 _____
0210	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	 SUM	_____	 _____
0220	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	 _____	_____	 _____
0230	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP	 SUM	_____	 _____
0240	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	516.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018949.00

Project(s): 018949.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	25.000 LF	_____	 _____	_____	 _____
0260	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	 _____	_____	 _____
0270	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	 _____	_____	 _____
0280	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0290	610.08 PLAIN RIPRAP	230.000 CY	_____	 _____	_____	 _____
0300	610.210 STREAM CHANNEL ROCK	140.000 CY	_____	 _____	_____	 _____
0310	613.319 EROSION CONTROL BLANKET	150.000 SY	_____	 _____	_____	 _____
0320	615.07 LOAM	36.000 CY	_____	 _____	_____	 _____
0330	618.14 SEEDING METHOD NUMBER 2	6.000 UN	_____	 _____	_____	 _____
0340	619.12 MULCH	6.000 UN	_____	 _____	_____	 _____
0350	619.14 EROSION CONTROL MIX	71.000 CY	_____	 _____	_____	 _____
0360	620.58 EROSION CONTROL GEOTEXTILE	315.000 SY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018949.00

Project(s): 018949.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,500.000 LF	_____	 _____	_____	 _____
0380	627.77 REMOVING PAVEMENT MARKINGS	100.000 SF	_____	 _____	_____	 _____
0390	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	100.000 LF	_____	 _____	_____	 _____
0400	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0410	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0420	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0430	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0440	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		 LUMP SUM	_____	 _____
0450	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0460	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0470	652.34 CONE	75.000 EA	_____	 _____	_____	 _____
0480	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018949.00

Project(s): 018949.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0490	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP	SUM	_____	_____
0500	652.38 FLAGGER	480.000 HR	_____	_____	_____	_____
0510	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0520	652.47 TEMPORARY PORTABLE RUMBLE STRIP	2.000 GP	_____	_____	_____	_____
0530	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0540	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____