

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	240.000 SY	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	1,100.000 CY	_____	_____	_____	_____
0040	203.24 COMMON BORROW	1,450.000 CY	_____	_____	_____	_____
0050	203.25 GRANULAR BORROW	430.000 CY	_____	_____	_____	_____
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	370.000 CY	_____	_____	_____	_____
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,100.000 CY	_____	_____	_____	_____
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	270.000 T	_____	_____	_____	_____
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	24.000 T	_____	_____	_____	_____
0100	403.211 HOT MIX ASPHALT (SHIMMING)	7.000 T	_____	_____	_____	_____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	420.000 T	_____	_____	_____	_____
0120	409.15 BITUMINOUS TACK COAT - APPLIED	110.000 G	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	411.09 UNTREATED AGGREGATE SURFACE COURSE	30.000 CY	_____	 _____	_____	 _____
0140	501.231 DYNAMIC LOADING TEST	2.000 EA	_____	 _____	_____	 _____
0150	501.251 PILE CASING	10.000 EA	_____	 _____	_____	 _____
0160	501.52 STEEL H-BEAM PILES 102 LBS/FT, DELIVERED	375.000 LF	_____	 _____	_____	 _____
0170	501.521 STEEL H-BEAM PILES 102 LBS/FT, IN PLACE	375.000 LF	_____	 _____	_____	 _____
0180	501.90 PILE TIPS	10.000 EA	_____	 _____	_____	 _____
0190	501.91 PILE SPLICES	15.000 EA	_____	 _____	_____	 _____
0200	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0210	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0220	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM	_____	 _____
0230	502.291 SAW CUT GROOVING	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0250	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0260	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	14,800.000 LB	_____	_____	_____	_____
0270	503.13 REINFORCING STEEL, PLACING	14,800.000 LB	_____	_____	_____	_____
0280	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	10,000.000 LB	_____	_____	_____	_____
0290	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	10,000.000 LB	_____	_____	_____	_____
0300	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	SUM	_____	_____
0310	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____
0320	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0330	506.9104 THERMAL SPRAY COATING - SHOP APPLIED	LUMP SUM	LUMP	SUM	_____	_____
0340	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP	SUM	_____	_____
0360	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0370	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	_____	_____	_____
0380	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0390	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	46.000 LF	_____	_____	_____	_____
0400	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0410	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	_____	_____	_____
0420	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	20,400.000 LF	_____	_____	_____	_____
0430	530.31 GFRP, REINFORCEMENT BARS, PLACING	20,400.000 LF	_____	_____	_____	_____
0440	603.16 15 INCH CULVERT PIPE OPTION I	130.000 LF	_____	_____	_____	_____
0450	605.09 6 INCH UNDERDRAIN TYPE B	180.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	605.10 6 INCH UNDERDRAIN OUTLET	30.000 LF	_____	 _____	_____	 _____
0470	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0480	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	525.000 LF	_____	 _____	_____	 _____
0490	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0500	606.47 SINGLE WOOD POST	1.000 EA	_____	 _____	_____	 _____
0510	606.50 SINGLE STEEL PIPE POST	1.000 EA	_____	 _____	_____	 _____
0520	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	4.000 EA	_____	 _____	_____	 _____
0530	610.08 PLAIN RIPRAP	1,200.000 CY	_____	 _____	_____	 _____
0540	613.319 EROSION CONTROL BLANKET	370.000 SY	_____	 _____	_____	 _____
0550	615.07 LOAM	300.000 CY	_____	 _____	_____	 _____
0560	618.13 SEEDING METHOD NUMBER 1	10.000 UN	_____	 _____	_____	 _____
0570	618.14 SEEDING METHOD NUMBER 2	8.000 UN	_____	 _____	_____	 _____
0580	618.141 SEEDING METHOD NUMBER 3	13.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	619.12 MULCH	31.000 UN	_____	 _____	_____	 _____
0600	619.14 EROSION CONTROL MIX	50.000 CY	_____	 _____	_____	 _____
0610	620.58 EROSION CONTROL GEOTEXTILE	1,450.000 SY	_____	 _____	_____	 _____
0620	620.65 REINFORCEMENT GEOGRID	1,650.000 SY	_____	 _____	_____	 _____
0630	620.661 DRAINAGE GEOCOMPOSITE INSTALLATION	74.000 SY	_____	 _____	_____	 _____
0640	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,250.000 LF	_____	 _____	_____	 _____
0650	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	 _____	_____	 _____
0660	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0670	631.14 GRADER (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0680	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	25.000 HR	_____	 _____	_____	 _____
0690	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0700	637.071 DUST CONTROL	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018954.00

Project(s): 018954.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0720	652.312 TYPE III BARRICADE	8.000 EA	_____	 _____	_____	 _____
0730	652.33 DRUM	40.000 EA	_____	 _____	_____	 _____
0740	652.34 CONE	40.000 EA	_____	 _____	_____	 _____
0750	652.35 CONSTRUCTION SIGNS	310.000 SF	_____	 _____	_____	 _____
0760	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		LUMP SUM	_____	 _____
0770	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0780	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____