

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 1 COMMON ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	70.000 SY				
0030	203.20 COMMON EXCAVATION	360.000 CY				
0040	203.24 COMMON BORROW	10.000 CY				
0050	203.25 GRANULAR BORROW	400.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	670.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	520.000 CY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	88.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	83.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	33.000 G				
0110	501.231 DYNAMIC LOADING TEST	2.000 EA				
0120	501.251 PILE CASING	4.000 EA				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 1 COMMON ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	540.000 LF	_____	 _____	_____	 _____
0140	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	540.000 LF	_____	 _____	_____	 _____
0150	501.90 PILE TIPS	8.000 EA	_____	 _____	_____	 _____
0160	501.91 PILE SPLICES	8.000 EA	_____	 _____	_____	 _____
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0190	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM	_____	 _____
0200	502.291 SAW CUT GROOVING	LUMP SUM		LUMP SUM	_____	 _____
0210	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0220	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____
0230	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	11,310.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 1 COMMON ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.13 REINFORCING STEEL, PLACING	11,310.000 LB	_____	 _____	_____	 _____
0250	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	5,720.000 LB	_____	 _____	_____	 _____
0260	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	5,720.000 LB	_____	 _____	_____	 _____
0270	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	 SUM	_____	 _____
0280	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	 SUM	_____	 _____
0290	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	 SUM	_____	 _____
0340	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	 SUM	_____	 _____
0350	511.07 COFFERDAM: ABUTMENT NO. 1	LUMP SUM	LUMP	 SUM	_____	 _____
0360	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP SUM	LUMP	 SUM	_____	 _____
0370	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	 _____	_____	 _____
0380	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	 SUM	_____	 _____
0390	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	 SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 1 COMMON ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0400	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	 _____	_____	 _____
0410	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	19,300.000 LF	_____	 _____	_____	 _____
0420	530.31 GFRP, REINFORCEMENT BARS, PLACING	19,300.000 LF	_____	 _____	_____	 _____
0430	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0440	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	713.000 LF	_____	 _____	_____	 _____
0450	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	_____	 _____	_____	 _____
0460	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	3.000 EA	_____	 _____	_____	 _____
0470	610.16 HEAVY RIPRAP	2,500.000 CY	_____	 _____	_____	 _____
0480	610.18 STONE DITCH PROTECTION	5.000 CY	_____	 _____	_____	 _____
0490	613.319 EROSION CONTROL BLANKET	310.000 SY	_____	 _____	_____	 _____
0500	615.07 LOAM	20.000 CY	_____	 _____	_____	 _____
0510	618.14 SEEDING METHOD NUMBER 2	3.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 1 COMMON ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0520	619.12 MULCH	3.000 UN	_____	 _____	_____	 _____
0530	619.14 EROSION CONTROL MIX	40.000 CY	_____	 _____	_____	 _____
0540	620.58 EROSION CONTROL GEOTEXTILE	2,620.000 SY	_____	 _____	_____	 _____
0550	620.661 DRAINAGE GEOCOMPOSITE INSTALLATION	62.000 SY	_____	 _____	_____	 _____
0560	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,800.000 LF	_____	 _____	_____	 _____
0570	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0580	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0590	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000 HR	_____	 _____	_____	 _____
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0610	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0620	652.312 TYPE III BARRICADE	8.000 EA	_____	 _____	_____	 _____
0630	652.33 DRUM	10.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 1 COMMON ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0640	652.34 CONE	20.000 EA	_____	 _____	_____	 _____
0650	652.35 CONSTRUCTION SIGNS	300.000 SF	_____	 _____	_____	 _____
0660	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES (120 CD)	LUMP SUM	LUMP SUM		_____	 _____
0670	652.38 FLAGGER	240.000 HR	_____	 _____	_____	 _____
0680	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0690	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
<b>Section: 1</b>			<b>Total:</b>		_____	 _____

SECTION: 2 GALVANIZING

Alt Set ID: AL Alt Mbr ID: 1

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0300	506.9103 GALVANIZING (75,600 LB)	LUMP SUM	LUMP SUM		_____	 _____
<b>Section: 2</b>			<b>Total:</b>		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018955.00

Project(s): 018955.00

SECTION: 3 THERMAL SPRAY

Alt Set ID: AL

Alt Mbr ID: 2

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0320	506.9104 THERMAL SPRAY COATING - SHOP APPLIED (75,600 LB)	LUMP SUM	LUMP	SUM	_____	_____
<b>Section: 3</b>			<b>Total:</b>		_____	_____

SECTION: 4 GALVANIZING & THERMAL SPRAY

Alt Set ID: AL

Alt Mbr ID: 3

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0310	506.9103 GALVANIZING (5,903 LB)	LUMP SUM	LUMP	SUM	_____	_____
0330	506.9104 THERMAL SPRAY COATING - SHOP APPLIED (69,700 LB)	LUMP SUM	LUMP	SUM	_____	_____
<b>Section: 4</b>			<b>Total:</b>		_____	_____
			<b>Total Bid:</b>		_____	_____