

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.15 REMOVING MANHOLE OR CATCH BASIN	2.000 EA	_____	 _____	_____	 _____
0020	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0030	202.202 REMOVING PAVEMENT SURFACE	100.000 SY	_____	 _____	_____	 _____
0040	203.20 COMMON EXCAVATION	500.000 CY	_____	 _____	_____	 _____
0050	203.2312 HEALTH AND SAFETY PLAN	LUMP SUM	LUMP SUM		_____	 _____
0060	203.2341 DISPOSAL OF CONTAMINATED SOIL	210.000 T	_____	 _____	_____	 _____
0070	203.24 COMMON BORROW	150.000 CY	_____	 _____	_____	 _____
0080	203.25 GRANULAR BORROW	500.000 CY	_____	 _____	_____	 _____
0090	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 CY	_____	 _____	_____	 _____
0100	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1,400.000 CY	_____	 _____	_____	 _____
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	480.000 CY	_____	 _____	_____	 _____
0120	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	103.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	30.000 T	_____	 _____	_____	 _____
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	160.000 T	_____	 _____	_____	 _____
0150	409.15 BITUMINOUS TACK COAT - APPLIED	50.000 G	_____	 _____	_____	 _____
0160	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM		_____	 _____
0170	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	340.000 CY	_____	 _____	_____	 _____
0180	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0190	502.291 SAW CUT GROOVING	LUMP SUM	LUMP SUM		_____	 _____
0200	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM		_____	 _____
0210	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	17,700.000 LB	_____	 _____	_____	 _____
0220	503.13 REINFORCING STEEL, PLACING	17,700.000 LB	_____	 _____	_____	 _____
0230	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	10,700.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	10,700.000 LB	_____	 _____	_____	 _____
0250	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	 SUM	_____	 _____
0260	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP SUM	LUMP	 SUM	_____	 _____
0270	511.07 COFFERDAM: ABUT NO.1	LUMP SUM	LUMP	 SUM	_____	 _____
0280	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	 SUM	_____	 _____
0290	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	 _____	_____	 _____
0300	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	 SUM	_____	 _____
0310	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	 SUM	_____	 _____
0320	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	 _____	_____	 _____
0330	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	23,400.000 LF	_____	 _____	_____	 _____
0340	530.31 GFRP, REINFORCEMENT BARS, PLACING	23,400.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	535.61 PRESTRESSED STRUCTURAL CONCRETE I-GIRDERS	LUMP SUM				
0360	603.179 18 INCH CULVERT PIPE OPTION III	136.000 LF				
0370	604.092 CATCH BASIN TYPE B1-C	2.000 EA				
0380	604.2402 BEHIND CURB CATCH BASIN	2.000 EA				
0390	604.262 CATCH BASIN TYPE B5-C	2.000 EA				
0400	605.09 6 INCH UNDERDRAIN TYPE B	150.000 LF				
0410	605.11 12 INCH UNDERDRAIN TYPE C	170.000 LF				
0420	605.12 15 INCH UNDERDRAIN TYPE C	130.000 LF				
0430	606.1721 BRIDGE TRANSITION - TYPE 1	3.000 EA				
0440	606.1721 BRIDGE TRANSITION - TYPE 1 Modified	1.000 EA				
0450	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	37.500 LF				
0460	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	606.2591 ANCHORAGE ASSEMBLY FOR DRIVEWAY RADIUS	1.000 EA	_____	 _____	_____	 _____
0480	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	 _____	_____	 _____
0490	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	_____	 _____	_____	 _____
0500	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	2.000 EA	_____	 _____	_____	 _____
0510	607.24 REMOVE AND RESET FENCE	30.000 LF	_____	 _____	_____	 _____
0520	608.26 CURB RAMP DETECTABLE WARNING FIELD	10.000 SF	_____	 _____	_____	 _____
0530	609.31 CURB TYPE 3	500.000 LF	_____	 _____	_____	 _____
0540	610.08 PLAIN RIPRAP	190.000 CY	_____	 _____	_____	 _____
0550	610.18 STONE DITCH PROTECTION	4.000 CY	_____	 _____	_____	 _____
0560	613.319 EROSION CONTROL BLANKET	41.000 SY	_____	 _____	_____	 _____
0570	615.07 LOAM	34.000 CY	_____	 _____	_____	 _____
0580	618.14 SEEDING METHOD NUMBER 2	4.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	618.141 SEEDING METHOD NUMBER 3	3.000 UN	_____	 _____	_____	 _____
0600	619.12 MULCH	7.000 UN	_____	 _____	_____	 _____
0610	619.14 EROSION CONTROL MIX	34.000 CY	_____	 _____	_____	 _____
0620	620.58 EROSION CONTROL GEOTEXTILE	290.000 SY	_____	 _____	_____	 _____
0630	620.661 DRAINAGE GEOCOMPOSITE INSTALLATION	130.000 SY	_____	 _____	_____	 _____
0640	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	550.000 LF	_____	 _____	_____	 _____
0650	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	 _____	_____	 _____
0660	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0670	631.14 GRADER (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0680	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0690	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	631.231 CRANE, 45 TON CAPACITY (INCLUDING OPERATOR) for gas line work only	100.000 HR	_____	 _____	_____	 _____
0710	637.071 DUST CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0720	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0730	652.312 TYPE III BARRICADE	8.000 EA	_____	 _____	_____	 _____
0740	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0750	652.34 CONE	25.000 EA	_____	 _____	_____	 _____
0760	652.35 CONSTRUCTION SIGNS	240.000 SF	_____	 _____	_____	 _____
0770	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0780	652.38 FLAGGER	240.000 HR	_____	 _____	_____	 _____
0790	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0800	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
0810	822.363 12 INCH CLASS 52 DUCTILE IRON PIPE	400.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 018970.00

Project(s): 018970.00

SECTION: 1 Main Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0820	827.33 TRENCH INSULATION	100.000 LF	_____	 _____	_____	 _____
0830	827.362 GAS MAIN TRENCHING	400.000 LF	_____	 _____	_____	 _____
0840	830.10 WATER MAIN BRIDGE CROSSING	LUMP SUM		LUMP SUM	_____	 _____
0850	830.16 GAS MAIN BRIDGE CROSSING HANGER SYSTEM	LUMP SUM		LUMP SUM	_____	 _____
0860	890.01 SPECIAL WORK #1 WATER CONNECTION	LUMP SUM		LUMP SUM	_____	 _____
0870	890.021 SPECIAL WORK #2 WATER CONNECTION	LUMP SUM		LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____