

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	10.000 EA	_____	_____	_____	_____
0020	201.24 REMOVING STUMP	11.000 EA	_____	_____	_____	_____
0030	202.08 REMOVING BUILDING NO.: 1	LUMP SUM	LUMP SUM	_____	_____	_____
0040	202.08 REMOVING BUILDING NO.: 2	LUMP SUM	LUMP SUM	_____	_____	_____
0050	202.202 REMOVING PAVEMENT SURFACE	16,300.000 SY	_____	_____	_____	_____
0060	203.20 COMMON EXCAVATION	12,800.000 CY	_____	_____	_____	_____
0070	203.21 ROCK EXCAVATION	1,800.000 CY	_____	_____	_____	_____
0080	203.25 GRANULAR BORROW	150.000 CY	_____	_____	_____	_____
0090	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	150.000 CY	_____	_____	_____	_____
0100	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	350.000 CY	_____	_____	_____	_____
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	10,150.000 CY	_____	_____	_____	_____
0120	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	2,310.000 T	_____	_____	_____	_____

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	470.000 T	_____	_____	_____	_____
0140	403.211 HOT MIX ASPHALT (SHIMMING)	380.000 T	_____	_____	_____	_____
0150	403.213 HOT MIX ASPHALT 12.5 MM BASE	2,220.000 T	_____	_____	_____	_____
0160	409.15 BITUMINOUS TACK COAT - APPLIED	1,314.821 G	_____	_____	_____	_____
0170	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	3.000 CY	_____	_____	_____	_____
0180	603.159 12 INCH CULVERT PIPE OPTION III	8.000 LF	_____	_____	_____	_____
0190	603.16 15 INCH CULVERT PIPE OPTION I	312.000 LF	_____	_____	_____	_____
0200	603.169 15 INCH CULVERT PIPE OPTION III	82.000 LF	_____	_____	_____	_____
0210	603.17 18 INCH CULVERT PIPE OPTION I	120.000 LF	_____	_____	_____	_____
0220	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	92.000 LF	_____	_____	_____	_____
0230	603.179 18 INCH CULVERT PIPE OPTION III	104.000 LF	_____	_____	_____	_____
0240	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	80.000 LF	_____	_____	_____	_____

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	603.199 24 INCH CULVERT PIPE OPTION III	218.000 LF				
0260	603.55 CONCRETE PIPE TIES	8.000 GP				
0270	603.7418 REMOVE & RELAY 18 INCH CONCRETE PIPE	136.000 LF				
0280	604.092 CATCH BASIN TYPE B1-C	7.000 EA				
0290	604.093 60 INCH CATCH BASIN TYPE B1	1.000 EA				
0300	604.244 CATCH BASIN TYPE F4	1.000 EA				
0310	605.09 6 INCH UNDERDRAIN TYPE B	1,140.000 LF				
0320	605.10 6 INCH UNDERDRAIN OUTLET	20.000 LF				
0330	605.11 12 INCH UNDERDRAIN TYPE C	270.000 LF				
0340	605.12 15 INCH UNDERDRAIN TYPE C	170.000 LF				
0350	605.15 24 INCH UNDERDRAIN TYPE C	400.000 LF				
0360	606.178 GUARDRAIL BEAM	50.000 LF				
0370	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	37.500 LF				

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF	_____	 _____	_____	 _____
0390	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	_____	 _____	_____	 _____
0400	606.356 UNDERDRAIN DELINEATOR POST	2.000 EA	_____	 _____	_____	 _____
0410	606.366 GUARDRAIL, REMOVE & RESET TYPE 3C	300.000 LF	_____	 _____	_____	 _____
0420	606.47 SINGLE WOOD POST	11.000 EA	_____	 _____	_____	 _____
0430	606.51 MULTIPLE MAILBOX SUPPORT	3.000 EA	_____	 _____	_____	 _____
0440	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	1.000 EA	_____	 _____	_____	 _____
0450	607.15 DRIVE GATEWAY 16 FOOT - METAL	2.000 EA	_____	 _____	_____	 _____
0460	607.242 REMOVE AND RESET GATEWAY	2.000 EA	_____	 _____	_____	 _____
0470	607.243 REMOVE CHAIN LINK FENCE	8.000 LF	_____	 _____	_____	 _____
0480	607.25 REMOVE AND RESET CHAIN LINK FENCE	265.000 LF	_____	 _____	_____	 _____
0490	609.11 VERTICAL CURB TYPE 1	380.000 LF	_____	 _____	_____	 _____

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0500	609.1101 SPECIAL GRANITE CURB - 48"	16.000 LF				
0510	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	90.000 LF				
0520	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	7.000 EA				
0530	609.31 CURB TYPE 3	2,030.000 LF				
0540	610.08 PLAIN RIPRAP	110.000 CY				
0550	610.18 STONE DITCH PROTECTION	30.000 CY				
0560	613.319 EROSION CONTROL BLANKET	1,480.000 SY				
0570	615.07 LOAM	1,050.000 CY				
0580	618.13 SEEDING METHOD NUMBER 1	38.000 UN				
0590	618.14 SEEDING METHOD NUMBER 2	94.000 UN				
0600	619.12 MULCH	133.000 UN				
0610	620.58 EROSION CONTROL GEOTEXTILE	220.000 SY				
0620	621.031 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP A	12.000 EA				

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0630	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	19,100.000 LF	_____	_____	_____	_____
0640	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	760.000 SF	_____	_____	_____	_____
0650	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	30,700.000 LF	_____	_____	_____	_____
0660	629.05 HAND LABOR, STRAIGHT TIME	90.000 HR	_____	_____	_____	_____
0670	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	110.000 HR	_____	_____	_____	_____
0680	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	140.000 HR	_____	_____	_____	_____
0690	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	15.000 HR	_____	_____	_____	_____
0700	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0710	631.22 FRONT END LOADER (INCLUDING OPERATOR)	60.000 HR	_____	_____	_____	_____
0720	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	15.000 HR	_____	_____	_____	_____
0730	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	_____	_____	_____

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0740	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	26.000 EA	_____	 _____	_____	 _____
0750	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	25.000 EA	_____	 _____	_____	 _____
0760	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	14.000 SF	_____	 _____	_____	 _____
0770	652.33 DRUM	310.000 EA	_____	 _____	_____	 _____
0780	652.34 CONE	325.000 EA	_____	 _____	_____	 _____
0790	652.35 CONSTRUCTION SIGNS	1,296.000 SF	_____	 _____	_____	 _____
0800	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	157.000 CD	_____	 _____	_____	 _____
0810	652.38 FLAGGER	8,125.000 HR	_____	 _____	_____	 _____
0820	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	 _____	_____	 _____
0830	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____

12/3/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 8

Proposal ID: 019002.00

Project(s): 019002.00, 019107.00, 023775.02

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0840	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	160.000 SY	_____	_____	_____	_____
0850	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0860	801.16 6 INCH PVC SANITARY SEWER (SDR- 35)	50.000 LF	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____