

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 019080.00

PROJECT(S): AC-NH-1908(000)E
 NH-1910(100)
 AC-NH-1912(300)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	133300.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	590.000 SY				
0030	202.205 RUMBLE STRIPS - SHOULDER	840.000 LF				
0040	203.242 DIRTY BORROW	280.000 CY				
0050	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	7700.000 T				
0060	403.2101 9.5 MM POLYMER MODIFIED HMA	3830.000 T				
0070	403.211 HOT MIX ASPHALT (SHIMMING)	150.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	3300.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	8110.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 019080.00

PROJECT(S): AC-NH-1908(000)E
 NH-1910(100)
 AC-NH-1912(300)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	410.151 EMULSIFIED ASPHALT SEALCOAT, APPLIED	54450.000 SY				
0110	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	14500.000 LB				
0120	604.167 ALTER CATCH BASIN GRATE TO CASCADE	2.000 EA				
0130	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	10.000 EA				
0140	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	53.000 EA				
0150	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	30.000 UN				
0160	619.12 MULCH	30.000 UN				
0170	627.18 12 " SOLID WHITE PAVEMENT MARKING	3400.000 LF				
0180	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	119590.000 LF				
0190	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	7090.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 019080.00

PROJECT(S): AC-NH-1908(000)E
 NH-1910(100)
 AC-NH-1912(300)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	3090.000 SF				
0210	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0220	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR				
0230	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0240	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0250	639.19 FIELD OFFICE TYPE B	1.000 EA				
0260	643.86 TRAFFIC SIGNAL LOOP DETECTORS	12.000 EA				
0270	652.30 FLASHING ARROW BOARD	5.000 EA				
0280	652.33 DRUM	120.000 EA				
0290	652.34 CONE	350.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 019080.00

PROJECT(S): AC-NH-1908(000)E
 NH-1910(100)
 AC-NH-1912(300)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	652.35 CONSTRUCTION SIGNS	SF 4710.000				
0310	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 118.000				
0320	652.38 FLAGGER	HR 4200.000				
0330	652.381 TRAFFIC OFFICER	HR 200.000				
0340	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	EA 10.000				
0350	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0360	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					.

SECTION 0002 TRAFFIC ITEMS

0370	643.83 VIDEO DETECTION SYSTEM INTERSECTION OF BYPASS DRIVE (ROUTE 24)	LUMP	LUMP			
------	---	------	------	--	--	--

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 019080.00

PROJECT(S): AC-NH-1908(000)E
NH-1910(100)
AC-NH-1912(300)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0380	643.83 VIDEO DETECTION SYSTEM INTERSECTION OF COMMUNITY WAY AND VILLAGE DRIVE	LUMP	LUMP			
	SECTION 0002 TOTAL					
	TOTAL BID					