

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019178.10

Project(s): 019178.10

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	600.000 SY	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	822.000 CY	_____	 _____	_____	 _____
0030	203.2318 DISPOSAL OF SPECIAL WASTE	160.000 T	_____	 _____	_____	 _____
0040	203.24 COMMON BORROW	10.000 CY	_____	 _____	_____	 _____
0050	203.25 GRANULAR BORROW	578.000 CY	_____	 _____	_____	 _____
0060	203.33 SPECIAL FILL	66.000 CY	_____	 _____	_____	 _____
0070	203.55 CULVERT BEDDING STONE	167.000 CY	_____	 _____	_____	 _____
0080	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	89.000 CY	_____	 _____	_____	 _____
0090	304.14 AGGREGATE BASE COURSE - TYPE A	700.000 CY	_____	 _____	_____	 _____
0100	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	131.000 T	_____	 _____	_____	 _____
0110	403.211 HOT MIX ASPHALT (SHIMMING)	12.000 T	_____	 _____	_____	 _____
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	208.000 T	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019178.10

Project(s): 019178.10

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	99.000 T	_____	 _____	_____	 _____
0140	409.15 BITUMINOUS TACK COAT - APPLIED	139.000 G	_____	 _____	_____	 _____
0150	461.131 TEMPORARY PAVEMENT	40.000 T	_____	 _____	_____	 _____
0160	502.565 CONCRETE FILL	62.000 CY	_____	 _____	_____	 _____
0170	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM		_____	 _____
0180	511.07 COFFERDAM: Downstream	LUMP SUM	LUMP SUM		_____	 _____
0190	511.07 COFFERDAM: Upstream	LUMP SUM	LUMP SUM		_____	 _____
0200	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM		_____	 _____
0210	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP SUM		_____	 _____
0220	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM		_____	 _____
0230	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	 _____	_____	 _____
0240	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019178.10

Project(s): 019178.10

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	413.000 LF	_____	 _____	_____	 _____
0260	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	 _____	_____	 _____
0270	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA	_____	 _____	_____	 _____
0280	607.10 BARBED WIRE FENCE - WOOD POSTS	85.000 LF	_____	 _____	_____	 _____
0290	610.08 PLAIN RIPRAP	120.000 CY	_____	 _____	_____	 _____
0300	610.210 STREAM CHANNEL ROCK	400.000 CY	_____	 _____	_____	 _____
0310	613.319 EROSION CONTROL BLANKET	112.000 SY	_____	 _____	_____	 _____
0320	615.07 LOAM	52.000 CY	_____	 _____	_____	 _____
0330	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	 _____	_____	 _____
0340	619.12 MULCH	9.000 UN	_____	 _____	_____	 _____
0350	619.14 EROSION CONTROL MIX	104.000 CY	_____	 _____	_____	 _____
0360	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	559.000 SY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019178.10

Project(s): 019178.10

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	620.58 EROSION CONTROL GEOTEXTILE	525.000 SY	_____	 _____	_____	 _____
0380	620.65 REINFORCEMENT GEOGRID	235.000 SY	_____	 _____	_____	 _____
0390	627.18 12 " SOLID WHITE PAVEMENT MARKING	24.000 LF	_____	 _____	_____	 _____
0400	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	900.000 LF	_____	 _____	_____	 _____
0410	627.77 REMOVING PAVEMENT MARKINGS	400.000 SF	_____	 _____	_____	 _____
0420	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,200.000 LF	_____	 _____	_____	 _____
0430	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	 _____	_____	 _____
0440	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0450	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0460	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0470	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0480	652.312 TYPE III BARRICADE	2.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019178.10

Project(s): 019178.10

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0490	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0500	652.34 CONE	100.000 EA	_____	 _____	_____	 _____
0510	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	 _____	_____	 _____
0520	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0530	652.38 FLAGGER	500.000 HR	_____	 _____	_____	 _____
0540	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0550	652.47 TEMPORARY PORTABLE RUMBLE STRIP	2.000 GP	_____	 _____	_____	 _____
0560	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0570	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____