

SCHEDULE OF ITEMS

CONTRACT ID: 019264.00

PROJECT(S): 019264.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 ITEMS						
0010	203.20 COMMON EXCAVATION	CY 1019.000				
0020	203.24 COMMON BORROW	CY 358.000				
0030	203.25 GRANULAR BORROW	CY 187.000				
0040	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	CY 50.000				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 924.000				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T 228.000				
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	T 228.000				
0080	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0090	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0100	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 019264.00

PROJECT(S): 019264.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0120	603.17 18 INCH CULVERT PIPE OPTION I	LF 30.000				
0130	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 125.000				
0140	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	LF 12.500				
0150	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	LF 12.500				
0160	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 7.000				
0170	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	EA 3.000				
0180	606.79 GUARDRAIL 350 FLARED TERMINAL	EA 3.000				
0190	610.16 HEAVY RIPRAP	CY 100.000				
0200	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	UN 5.000				
0210	619.12 MULCH	UN 5.000				

SCHEDULE OF ITEMS

CONTRACT ID: 019264.00

PROJECT(S): 019264.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	620.58 EROSION CONTROL GEOTEXTILE	92.000 SY				
0230	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	1.000 HR				
0240	652.312 TYPE III BARRICADE	5.000 EA				
0250	652.33 DRUM	8.000 EA				
0260	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	14.000 CD				
0270	652.38 FLAGGER	120.000 HR				
0280	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA				
0290	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0300	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					

SECTION 0002 OPTIONAL RICHMOND UTILITIES DISTRICT

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 120202

REVISED:

CONTRACT ID: 019264.00

PROJECT(S): 019264.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	801.011 BYPASS PUMPING SYSTEM	LUMP	LUMP			
0320	801.18 12 INCH PVC SANITARY SEWER (SDR-35)	LF 80.000				
0330	822.35 10 INCH CLASS 52 DUCTILE IRON PIPE	LF 80.000				
	SECTION 0002 TOTAL					
	TOTAL BID					