

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA	_____	 _____	_____	 _____
0020	201.24 REMOVING STUMP	1.000 EA	_____	 _____	_____	 _____
0030	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM	LUMP SUM		_____	 _____
0040	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	16.000 CY	_____	 _____	_____	 _____
0050	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0060	202.202 REMOVING PAVEMENT SURFACE	1,545.000 SY	_____	 _____	_____	 _____
0070	203.20 COMMON EXCAVATION	2,365.000 CY	_____	 _____	_____	 _____
0080	203.2318 DISPOSAL OF SPECIAL WASTE	885.000 T	_____	 _____	_____	 _____
0090	203.25 GRANULAR BORROW	790.000 CY	_____	 _____	_____	 _____
0100	203.35 CRUSHED STONE FILL	64.000 CY	_____	 _____	_____	 _____
0110	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	790.000 CY	_____	 _____	_____	 _____
0120	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	11.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,180.000 CY	_____	 _____	_____	 _____
0140	304.15 AGGREGATE BASE COURSE - TYPE B	280.000 CY	_____	 _____	_____	 _____
0150	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	398.000 T	_____	 _____	_____	 _____
0160	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	117.000 T	_____	 _____	_____	 _____
0170	403.211 HOT MIX ASPHALT (SHIMMING)	10.000 T	_____	 _____	_____	 _____
0180	403.213 HOT MIX ASPHALT 12.5 MM BASE	490.000 T	_____	 _____	_____	 _____
0190	409.15 BITUMINOUS TACK COAT - APPLIED	190.000 G	_____	 _____	_____	 _____
0200	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	7.000 CY	_____	 _____	_____	 _____
0210	461.131 TEMPORARY PAVEMENT	100.000 T	_____	 _____	_____	 _____
0220	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	55.000 CY	_____	 _____	_____	 _____
0230	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	_____	 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLABS CLARK	LUMP SUM	LUMP	SUM	_____	_____
0250	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS CLARK	LUMP SUM	LUMP	SUM	_____	_____
0260	502.565 CONCRETE FILL	100.000 CY	_____	_____	_____	_____
0270	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	20,665.000 LB	_____	_____	_____	_____
0280	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	20,665.000 LB	_____	_____	_____	_____
0290	507.0821 STEEL BRIDGE RAILING, 3 BAR CLARK	LUMP SUM	LUMP	SUM	_____	_____
0300	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP SUM	LUMP	SUM	_____	_____
0310	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0320	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0330	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 19.5 FT	LUMP SUM	LUMP	SUM	_____	_____
0340	511.07 COFFERDAM: ABUT NO.1 CLARK	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	511.07 COFFERDAM: ABUT NO.1 MARSH	LUMP SUM	LUMP	SUM	_____	_____
0360	511.07 COFFERDAM: ABUT NO.2 CLARK	LUMP SUM	LUMP	SUM	_____	_____
0370	511.07 COFFERDAM: ABUT NO.2 MARSH	LUMP SUM	LUMP	SUM	_____	_____
0380	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0390	514.06 CURING BOX FOR CONCRETE CYLINDERS	2.000 EA	_____	_____	_____	_____
0400	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0410	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0420	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0430	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP SUM	LUMP	SUM	_____	_____
0440	601.21 GABIONS, GALVANIZED	34.000 CY	_____	_____	_____	_____
0450	603.15 12 INCH CULVERT PIPE OPTION I	50.000 LF	_____	_____	_____	_____
0460	603.159 12 INCH CULVERT PIPE OPTION III	53.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	603.16 15 INCH CULVERT PIPE OPTION I	50.000 LF	_____	 _____	_____	 _____
0480	603.17 18 INCH CULVERT PIPE OPTION I	50.000 LF	_____	 _____	_____	 _____
0490	604.072 CATCH BASIN TYPE A1-C	2.000 EA	_____	 _____	_____	 _____
0500	604.09 CATCH BASIN TYPE B1	1.000 EA	_____	 _____	_____	 _____
0510	604.242 CATCH BASIN TYPE F3	2.000 EA	_____	 _____	_____	 _____
0520	604.262 CATCH BASIN TYPE B5-C	1.000 EA	_____	 _____	_____	 _____
0530	605.09 6 INCH UNDERDRAIN TYPE B	270.000 LF	_____	 _____	_____	 _____
0540	605.12 15 INCH UNDERDRAIN TYPE C	215.000 LF	_____	 _____	_____	 _____
0550	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	900.000 LF	_____	 _____	_____	 _____
0560	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	8.000 EA	_____	 _____	_____	 _____
0570	606.1721 BRIDGE TRANSITION - TYPE 1	8.000 EA	_____	 _____	_____	 _____
0580	606.1728 W-BEAM TO 3-BAR BRIDGE RAIL TRANSITION	6.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	606.1729 W-BEAM TO 4-BAR BRIDGE RAIL TRANSITION	2.000 EA	_____	 _____	_____	 _____
0600	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	16.000 EA	_____	 _____	_____	 _____
0610	608.26 CURB RAMP DETECTABLE WARNING FIELD	70.000 SF	_____	 _____	_____	 _____
0620	609.11 VERTICAL CURB TYPE 1	635.000 LF	_____	 _____	_____	 _____
0630	609.238 TERMINAL CURB TYPE 1 - 8 FOOT	5.000 EA	_____	 _____	_____	 _____
0640	609.31 CURB TYPE 3	87.000 LF	_____	 _____	_____	 _____
0650	609.38 RESET CURB TYPE 1	53.000 LF	_____	 _____	_____	 _____
0660	610.08 PLAIN RIPRAP	860.000 CY	_____	 _____	_____	 _____
0670	610.09 HAND LAID RIPRAP	20.000 CY	_____	 _____	_____	 _____
0680	610.16 HEAVY RIPRAP	230.000 CY	_____	 _____	_____	 _____
0690	615.07 LOAM	127.000 CY	_____	 _____	_____	 _____
0700	618.13 SEEDING METHOD NUMBER 1	7.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	 _____	_____	 _____
0720	619.12 MULCH	15.000 UN	_____	 _____	_____	 _____
0730	619.14 EROSION CONTROL MIX	55.000 CY	_____	 _____	_____	 _____
0740	620.58 EROSION CONTROL GEOTEXTILE	1,650.000 SY	_____	 _____	_____	 _____
0750	626.22 NON-METALLIC CONDUIT	25.000 LF	_____	 _____	_____	 _____
0760	627.18 12 " SOLID WHITE PAVEMENT MARKING	40.000 LF	_____	 _____	_____	 _____
0770	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3,795.000 LF	_____	 _____	_____	 _____
0780	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	280.000 SF	_____	 _____	_____	 _____
0790	627.77 REMOVING PAVEMENT MARKINGS	210.000 SF	_____	 _____	_____	 _____
0800	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	5,050.000 LF	_____	 _____	_____	 _____
0810	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR	_____	 _____	_____	 _____
0820	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0830	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0840	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0850	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0870	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0880	643.62 RECTANGULAR RAPID FLASHING BEACON	2.000 EA	_____	 _____	_____	 _____
0890	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		 LUMP SUM	_____	 _____
0900	643.83 VIDEO DETECTION SYSTEM	LUMP SUM		 LUMP SUM	_____	 _____
0910	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	1.000 EA	_____	 _____	_____	 _____
0920	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	3.000 EA	_____	 _____	_____	 _____
0930	652.312 TYPE III BARRICADE	6.000 EA	_____	 _____	_____	 _____
0940	652.33 DRUM	60.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019305.00

Project(s): 019305.00, 019305.10, 021702.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0950	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0960	652.35 CONSTRUCTION SIGNS	720.000 SF	_____	 _____	_____	 _____
0970	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0980	652.38 FLAGGER	1,595.000 HR	_____	 _____	_____	 _____
0990	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	5.000 EA	_____	 _____	_____	 _____
1000	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
1010	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
1020	674.10 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1,400.000 SF	_____	 _____	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____