

SCHEDULE OF ITEMS

DATE: 121212

REVISED:

CONTRACT ID: 019310.00

PROJECT(S): 019310.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 project Items

0010	201.23 REMOVING SINGLE TREE TOP ONLY	EA 2.000				
0020	203.20 COMMON EXCAVATION	CY 340.000				
0030	203.24 COMMON BORROW	CY 20.000				
0040	203.25 GRANULAR BORROW	CY 160.000				
0050	203.33 SPECIAL FILL	CY 40.000				
0060	203.35 CRUSHED STONE FILL	CY 110.000				
0070	205.51 WIDENING OF EXISTING SHOULDER - PLAN QUANTITY	SY 340.000				
0080	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	CY 70.000				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 295.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

SCHEDULE OF ITEMS

DATE: 121212

REVISED:

CONTRACT ID: 019310.00

PROJECT(S): 019310.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.102 HOT MIX ASPHALT PAVEMENT - SPECIAL AREAS	10.000 T				
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	35.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	93.000 T				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	22.000 G				
0140	508.13 SHEET WATERPROOFING MEMBRANE	LUMP	LUMP			
0150	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0160	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0170	513.22 CRUSHED STONE SLOPE PROTECTION	15.000 SY				
0180	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0190	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0200	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 3

SCHEDULE OF ITEMS

DATE: 121212

REVISED:

CONTRACT ID: 019310.00

PROJECT(S): 019310.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	1162.500 LF				
0220	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0230	606.363 GUARDRAIL REMOVE AND DISPOSE	1320.000 LF				
0240	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0250	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0260	610.08 PLAIN RIPRAP	190.000 CY				
0270	613.329 EXTENDED USE EROSION CONTROL BLANKETS	50.000 SY				
0280	615.07 LOAM	10.000 CY				
0290	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1.000 UN				
0300	619.1201 MULCH - PLAN QUANTITY	1.000 UN				
0310	619.1401 EROSION CONTROL MIX	60.000 CY				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 121212

REVISED:

CONTRACT ID: 019310.00

PROJECT(S): 019310.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	620.58 EROSION CONTROL GEOTEXTILE	SY 635.000				
0330	620.65 REINFORCEMENT GEOGRID	SY 170.000				
0340	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	LF 300.000				
0350	629.05 HAND LABOR, STRAIGHT TIME	HR 10.000				
0360	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 20.000				
0370	631.131 SMALL BULLDOZER-GRADER (INCLUDING OPERATOR)	HR 10.000				
0380	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	HR 10.000				
0390	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	HR 10.000				
0400	639.19 FIELD OFFICE TYPE B	EA 1.000				
0410	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0420	652.312 TYPE III BARRICADE	EA 4.000				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 5

SCHEDULE OF ITEMS

DATE: 121212

REVISED:

CONTRACT ID: 019310.00

PROJECT(S): 019310.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	652.33 DRUM	EA 30.000				
0440	652.34 CONE	EA 25.000				
0450	652.35 CONSTRUCTION SIGNS	SF 186.000				
0460	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 75.000				
0470	652.38 FLAGGER	HR 100.000				
0480	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0490	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					