

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.15 REMOVING MANHOLE OR CATCH BASIN	2.000 EA	_____	 _____	_____	 _____
0020	202.202 REMOVING PAVEMENT SURFACE	1,580.000 SY	_____	 _____	_____	 _____
0030	203.20 COMMON EXCAVATION	1,400.000 CY	_____	 _____	_____	 _____
0040	203.24 COMMON BORROW	200.000 CY	_____	 _____	_____	 _____
0050	203.25 GRANULAR BORROW	50.000 CY	_____	 _____	_____	 _____
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY	_____	 _____	_____	 _____
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,300.000 CY	_____	 _____	_____	 _____
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	180.000 T	_____	 _____	_____	 _____
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	280.000 T	_____	 _____	_____	 _____
0100	403.211 HOT MIX ASPHALT (SHIMMING)	20.000 T	_____	 _____	_____	 _____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	150.000 T	_____	 _____	_____	 _____
0120	409.15 BITUMINOUS TACK COAT - APPLIED	100.000 G	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	 _____	_____	 _____
0140	603.159 12 INCH CULVERT PIPE OPTION III	210.000 LF	_____	 _____	_____	 _____
0150	603.179 18 INCH CULVERT PIPE OPTION III	270.000 LF	_____	 _____	_____	 _____
0160	603.199 24 INCH CULVERT PIPE OPTION III	8.000 LF	_____	 _____	_____	 _____
0170	604.16 ALTERING CATCH BASIN TO MANHOLES	1.000 EA	_____	 _____	_____	 _____
0180	604.164 REBUILDING CATCH BASIN	1.000 EA	_____	 _____	_____	 _____
0190	604.2403 SPECIAL BASIN	2.000 EA	_____	 _____	_____	 _____
0200	604.243 CATCH BASIN TYPE F3-C	2.000 EA	_____	 _____	_____	 _____
0210	604.245 CATCH BASIN TYPE F4-C	2.000 EA	_____	 _____	_____	 _____
0220	604.248 CATCH BASIN TYPE F6	2.000 EA	_____	 _____	_____	 _____
0230	604.26 CATCH BASIN TYPE B5	2.000 EA	_____	 _____	_____	 _____
0240	604.262 CATCH BASIN TYPE B5-C	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	288.000 LF	_____	 _____	_____	 _____
0260	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	 _____	_____	 _____
0270	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	 _____	_____	 _____
0280	606.178 GUARDRAIL BEAM	25.000 LF	_____	 _____	_____	 _____
0290	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA	_____	 _____	_____	 _____
0300	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	10.000 EA	_____	 _____	_____	 _____
0310	606.48 SINGLE GALVANIZED STEEL POST	4.000 EA	_____	 _____	_____	 _____
0320	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA	_____	 _____	_____	 _____
0330	607.22 CEDAR RAIL FENCE	72.000 LF	_____	 _____	_____	 _____
0340	607.24 REMOVE AND RESET FENCE	96.000 LF	_____	 _____	_____	 _____
0350	608.26 CURB RAMP DETECTABLE WARNING FIELD	161.000 SF	_____	 _____	_____	 _____
0360	609.11 VERTICAL CURB TYPE 1	790.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	15.000 LF	_____	 _____	_____	 _____
0380	609.23 TERMINAL CURB TYPE 1	18.000 EA	_____	 _____	_____	 _____
0390	609.232 TERMINAL CURB TYPE I - CIRCULAR	12.000 EA	_____	 _____	_____	 _____
0400	609.31 CURB TYPE 3	390.000 LF	_____	 _____	_____	 _____
0410	609.34 CURB TYPE 5	40.000 LF	_____	 _____	_____	 _____
0420	610.08 PLAIN RIPRAP	14.000 CY	_____	 _____	_____	 _____
0430	610.09 HAND LAID RIPRAP	5.000 CY	_____	 _____	_____	 _____
0440	613.319 EROSION CONTROL BLANKET	130.000 SY	_____	 _____	_____	 _____
0450	615.07 LOAM	180.000 CY	_____	 _____	_____	 _____
0460	615.10 DIRTY BORROW	150.000 CY	_____	 _____	_____	 _____
0470	618.13 SEEDING METHOD NUMBER 1	15.000 UN	_____	 _____	_____	 _____
0480	618.14 SEEDING METHOD NUMBER 2	24.000 UN	_____	 _____	_____	 _____
0490	619.12 MULCH	39.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0500	620.58 EROSION CONTROL GEOTEXTILE	40.000 SY	_____	 _____	_____	 _____
0510	626.11 PRECAST CONCRETE JUNCTION BOX	5.000 EA	_____	 _____	_____	 _____
0520	626.21 METALLIC CONDUIT	70.000 LF	_____	 _____	_____	 _____
0530	626.22 NON-METALLIC CONDUIT	3,000.000 LF	_____	 _____	_____	 _____
0540	626.32 24 INCH FOUNDATION	9.000 EA	_____	 _____	_____	 _____
0550	626.332 30 INCH DIAMATER GREATER THAN 8 FEET LONG & 36 INCH DIAMETER, 42 INCH DIAMETER FOUNDATION	4.000 CY	_____	 _____	_____	 _____
0560	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	5.000 EA	_____	 _____	_____	 _____
0570	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,700.000 LF	_____	 _____	_____	 _____
0580	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1,230.000 SF	_____	 _____	_____	 _____
0590	627.77 REMOVING PAVEMENT MARKINGS	200.000 SF	_____	 _____	_____	 _____
0600	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,000.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0610	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0620	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0630	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0640	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
0650	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
0660	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0670	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
0680	634.16 HIGHWAY LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____
0690	634.2042 LED LUMINARIES	6.000 EA	_____	 _____	_____	 _____
0700	634.210 CONVENTIONAL LIGHT STANDARD	1.000 EA	_____	 _____	_____	 _____
0710	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0720	643.71 TRAFFIC SIGNAL MODIFICATION	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0730	643.92 PEDESTAL POLE	4.000 EA	_____	 _____	_____	 _____
0740	645.103 DEMOUNT GUIDE SIGN	3.000 EA	_____	 _____	_____	 _____
0750	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	20.000 EA	_____	 _____	_____	 _____
0760	645.113 REINSTALL GUIDE SIGN	3.000 EA	_____	 _____	_____	 _____
0770	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	20.000 EA	_____	 _____	_____	 _____
0780	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	120.000 SF	_____	 _____	_____	 _____
0790	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	13.000 SF	_____	 _____	_____	 _____
0800	645.512 LED BLANK-OUT SIGN, OVERHEAD MOUNT	1.000 EA	_____	 _____	_____	 _____
0810	652.33 DRUM	115.000 EA	_____	 _____	_____	 _____
0820	652.34 CONE	115.000 EA	_____	 _____	_____	 _____
0830	652.35 CONSTRUCTION SIGNS	800.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 019402.00

Project(s): 019402.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0840	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	90.000 CD	_____	 _____	_____	 _____
0850	652.38 FLAGGER	2,250.000 HR	_____	 _____	_____	 _____
0860	652.381 TRAFFIC OFFICER	40.000 HR	_____	 _____	_____	 _____
0870	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	3.000 EA	_____	 _____	_____	 _____
0880	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0890	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____