

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020814.00

Project(s): 020814.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	270.000 SY	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	2,420.000 CY	_____	_____	_____	_____
0040	203.24 COMMON BORROW	50.000 CY	_____	_____	_____	_____
0050	203.25 GRANULAR BORROW	480.000 CY	_____	_____	_____	_____
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	570.000 CY	_____	_____	_____	_____
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	480.000 CY	_____	_____	_____	_____
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	97.000 T	_____	_____	_____	_____
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	85.000 T	_____	_____	_____	_____
0100	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	103.000 T	_____	_____	_____	_____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	71.000 G	_____	_____	_____	_____
0120	501.239 DYNAMIC LOADING TESTS - PROVIDING FOR	4.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020814.00

Project(s): 020814.00

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	1,910.000 LF	_____	 _____	_____	 _____
0140	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	1,870.000 LF	_____	 _____	_____	 _____
0150	501.90 PILE TIPS	10.000 EA	_____	 _____	_____	 _____
0160	501.91 PILE SPLICES	40.000 EA	_____	 _____	_____	 _____
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		 LUMP SUM	_____	 _____
0190	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		 LUMP SUM	_____	 _____
0200	502.492 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	6.000 CY	_____	 _____	_____	 _____
0210	503.17 MECHANICAL WELDED SPLICE	54.000 EA	_____	 _____	_____	 _____
0220	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	24,300.000 LB	_____	 _____	_____	 _____
0230	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	24,300.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020814.00

Project(s): 020814.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0250	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0260	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0270	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	_____	_____	_____
0280	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0290	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	102.000 LF	_____	_____	_____	_____
0300	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	SUM	_____	_____
0310	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0320	526.305 TEMPORARY CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM	LUMP	SUM	_____	_____
0330	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	_____	_____	_____
0340	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020814.00

Project(s): 020814.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	534.7601 PRECAST APPROACH SLAB	LUMP SUM	LUMP	SUM	_____	_____
0360	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP	SUM	_____	_____
0370	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	238.000 LF	_____	_____	_____	_____
0380	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF	_____	_____	_____	_____
0390	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	_____	_____	_____
0400	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1	4.000 EA	_____	_____	_____	_____
0410	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	_____	_____	_____
0420	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	_____	_____	_____	_____
0430	610.08 PLAIN RIPRAP	460.000 CY	_____	_____	_____	_____
0440	610.18 STONE DITCH PROTECTION	25.000 CY	_____	_____	_____	_____
0450	613.319 EROSION CONTROL BLANKET	58.000 SY	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020814.00

Project(s): 020814.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	615.07 LOAM	15.000 CY	_____	 _____	_____	 _____
0470	618.141 SEEDING METHOD NUMBER 3	3.000 UN	_____	 _____	_____	 _____
0480	619.12 MULCH	3.000 UN	_____	 _____	_____	 _____
0490	619.14 EROSION CONTROL MIX	30.000 CY	_____	 _____	_____	 _____
0500	620.58 EROSION CONTROL GEOTEXTILE	790.000 SY	_____	 _____	_____	 _____
0510	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,100.000 LF	_____	 _____	_____	 _____
0520	627.77 REMOVING PAVEMENT MARKINGS	500.000 SF	_____	 _____	_____	 _____
0530	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	2,680.000 LF	_____	 _____	_____	 _____
0540	629.05 HAND LABOR, STRAIGHT TIME	35.000 HR	_____	 _____	_____	 _____
0550	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0560	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0570	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 020814.00

Project(s): 020814.00

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0590	637.071 DUST CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0600	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0610	643.72 TEMPORARY TRAFFIC SIGNAL ROUTE 1 & CAPELL BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0620	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0630	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0640	652.34 CONE	20.000 EA	_____	 _____	_____	 _____
0650	652.35 CONSTRUCTION SIGNS	204.000 SF	_____	 _____	_____	 _____
0660	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0670	652.38 FLAGGER	240.000 HR	_____	 _____	_____	 _____
0680	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0690	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____

