

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021657.00

Project(s): 021657.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	1,400.000 SY	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	1,170.000 CY	_____	_____	_____	_____
0040	203.2318 DISPOSAL OF SPECIAL WASTE	100.000 T	_____	_____	_____	_____
0050	203.24 COMMON BORROW	120.000 CY	_____	_____	_____	_____
0060	203.25 GRANULAR BORROW	290.000 CY	_____	_____	_____	_____
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	617.000 CY	_____	_____	_____	_____
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1,150.000 CY	_____	_____	_____	_____
0090	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	190.000 T	_____	_____	_____	_____
0100	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T	_____	_____	_____	_____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	50.000 T	_____	_____	_____	_____
0120	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	170.000 T	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021657.00

Project(s): 021657.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	409.15 BITUMINOUS TACK COAT - APPLIED	150.000 G	_____	 _____	_____	 _____
0140	461.131 TEMPORARY PAVEMENT	90.000 T	_____	 _____	_____	 _____
0150	501.231 DYNAMIC LOADING TEST	2.000 EA	_____	 _____	_____	 _____
0160	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	310.000 LF	_____	 _____	_____	 _____
0170	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	300.000 LF	_____	 _____	_____	 _____
0180	501.90 PILE TIPS	8.000 EA	_____	 _____	_____	 _____
0190	501.91 PILE SPLICES	12.000 EA	_____	 _____	_____	 _____
0200	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
0210	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		 LUMP SUM	_____	 _____
0220	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		 LUMP SUM	_____	 _____
0230	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021657.00

Project(s): 021657.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	502.492 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	4.000 CY	_____	 _____	_____	 _____
0250	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	18,700.000 LB	_____	 _____	_____	 _____
0260	503.13 REINFORCING STEEL, PLACING	18,700.000 LB	_____	 _____	_____	 _____
0270	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	2,000.000 LB	_____	 _____	_____	 _____
0280	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	2,000.000 LB	_____	 _____	_____	 _____
0290	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		 LUMP SUM	_____	 _____
0300	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		 LUMP SUM	_____	 _____
0310	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP SUM		 LUMP SUM	_____	 _____
0320	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM		 LUMP SUM	_____	 _____
0330	511.07 COFFERDAM: UPSTREAM	LUMP SUM		 LUMP SUM	_____	 _____
0340	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021657.00

Project(s): 021657.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		LUMP SUM	_____	_____
0360	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	70.000 LF	_____	_____	_____	_____
0370	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM	_____	_____
0380	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0390	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM		LUMP SUM	_____	_____
0400	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	3.000 EA	_____	_____	_____	_____
0410	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	162.500 LF	_____	_____	_____	_____
0420	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA	_____	_____	_____	_____
0430	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0450	607.421 SCREENING FENCE	200.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021657.00

Project(s): 021657.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	610.08 PLAIN RIPRAP	413.000 CY	_____	 _____	_____	 _____
0470	613.319 EROSION CONTROL BLANKET	65.000 SY	_____	 _____	_____	 _____
0480	615.07 LOAM	30.000 CY	_____	 _____	_____	 _____
0490	618.14 SEEDING METHOD NUMBER 2	1.000 UN	_____	 _____	_____	 _____
0500	619.12 MULCH	1.000 UN	_____	 _____	_____	 _____
0510	619.14 EROSION CONTROL MIX	30.000 CY	_____	 _____	_____	 _____
0520	620.58 EROSION CONTROL GEOTEXTILE	639.000 SY	_____	 _____	_____	 _____
0530	620.66 DRAINAGE GEOCOMPOSITE	84.000 SY	_____	 _____	_____	 _____
0540	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,040.000 LF	_____	 _____	_____	 _____
0550	627.77 REMOVING PAVEMENT MARKINGS	340.000 SF	_____	 _____	_____	 _____
0560	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,000.000 LF	_____	 _____	_____	 _____
0570	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021657.00

Project(s): 021657.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0590	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0600	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0610	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0620	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0630	652.33 DRUM	27.000 EA	_____	 _____	_____	 _____
0640	652.34 CONE	27.000 EA	_____	 _____	_____	 _____
0650	652.35 CONSTRUCTION SIGNS	300.000 SF	_____	 _____	_____	 _____
0660	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0670	652.38 FLAGGER	320.000 HR	_____	 _____	_____	 _____
0680	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0690	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

12/4/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

---

Proposal ID: 021657.00

Project(s): 021657.00

Section: 1

Total:

\_\_\_\_\_!\_\_\_\_\_

Total Bid:

\_\_\_\_\_!\_\_\_\_\_