

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description  | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|--|--------------------------------|------------|-------|------------|-------|
|                      |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0010                 | 202.19<br>REMOVING EXISTING BRIDGE                                 | LUMP SUM                       | LUMP SUM   |       | _____      | _____ |
| 0020                 | 202.202<br>REMOVING PAVEMENT SURFACE                               | 73.000<br>SY                   | _____      | _____ | _____      | _____ |
| 0030                 | 203.20<br>COMMON EXCAVATION  | 1,750.000<br>CY                | _____      | _____ | _____      | _____ |
| 0040                 | 203.24<br>COMMON BORROW  | 1,250.000<br>CY                | _____      | _____ | _____      | _____ |
| 0050                 | 203.25<br>GRANULAR BORROW  | 3,240.000<br>CY                | _____      | _____ | _____      | _____ |
| 0060                 | 206.082<br>STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES          | 150.000<br>CY                  | _____      | _____ | _____      | _____ |
| 0070                 | 304.10<br>AGGREGATE SUBBASE COURSE - GRAVEL                        | 1,600.000<br>CY                | _____      | _____ | _____      | _____ |
| 0080                 | 403.208<br>HOT MIX ASPHALT 12.5 MM HMA SURFACE                     | 254.000<br>T                   | _____      | _____ | _____      | _____ |
| 0090                 | 403.209<br>HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS) | 8.000<br>T                     | _____      | _____ | _____      | _____ |
| 0100                 | 403.213<br>HOT MIX ASPHALT 12.5 MM BASE                            | 394.000<br>T                   | _____      | _____ | _____      | _____ |
| 0110                 | 409.15<br>BITUMINOUS TACK COAT - APPLIED                           | 102.000<br>G                   | _____      | _____ | _____      | _____ |
| 0120                 | 501.231<br>DYNAMIC LOADING TEST                                    | 2.000<br>EA                    | _____      | _____ | _____      | _____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0130                 | 501.54<br>STEEL H-BEAM PILES 117 LBS/FT, DELIVERED                        | 245.000<br>LF                  | _____      | <br>_____ | _____      | <br>_____ |
| 0140                 | 501.541<br>STEEL H-BEAM PILES 117 LBS/FT, IN PLACE                        | 208.000<br>LF                  | _____      | <br>_____ | _____      | <br>_____ |
| 0150                 | 501.90<br>PILE TIPS   | 8.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0160                 | 501.91<br>PILE SPLICES  | 8.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0170                 | 501.92<br>PILE DRIVING EQUIPMENT MOBILIZATION                             | LUMP SUM                       |            | LUMP SUM  | _____      | <br>_____ |
| 0180                 | 502.219<br>STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS             | LUMP SUM                       |            | LUMP SUM  | _____      | <br>_____ |
| 0190                 | 502.26<br>STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES | LUMP SUM                       |            | LUMP SUM  | _____      | <br>_____ |
| 0200                 | 502.31<br>STRUCTURAL CONCRETE APPROACH SLABS                              | LUMP SUM                       |            | LUMP SUM  | _____      | <br>_____ |
| 0210                 | 502.49<br>STRUCTURAL CONCRETE CURBS AND SIDEWALKS                         | LUMP SUM                       |            | LUMP SUM  | _____      | <br>_____ |
| 0220                 | 503.12<br>REINFORCING STEEL, FABRICATED AND DELIVERED                     | 16,900.000<br>LB               | _____      | <br>_____ | _____      | <br>_____ |
| 0230                 | 503.13<br>REINFORCING STEEL, PLACING                                      | 16,900.000<br>LB               | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0240                 | 503.26<br>STAINLESS STEEL REINFORCEMENT<br>- FABRICATED & DELIVERED | 12,700.000<br>LB               | _____      | <br>_____ | _____      | <br>_____ |
| 0250                 | 503.27<br>STAINLESS STEEL REINFORCEMENT<br>- PLACING                | 12,700.000<br>LB               | _____      | <br>_____ | _____      | <br>_____ |
| 0260                 | 504.702<br>STRUCTURAL STEEL FABRICATED<br>AND DELIVERED, WELDED     | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0270                 | 504.71<br>STRUCTURAL STEEL ERECTION                                 | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0280                 | 505.08<br>SHEAR CONNECTORS  | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0290                 | 506.9104<br>THERMAL SPRAY COATING - SHOP<br>APPLIED                 | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0300                 | 507.0821<br>STEEL BRIDGE RAILING, 3 BAR                             | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0310                 | 508.14<br>HIGH PERFORMANCE<br>WATERPROOFING MEMBRANE                | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0320                 | 511.07<br>COFFERDAM: ABUT NO.1                                      | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0330                 | 511.07<br>COFFERDAM: ABUT NO.2                                      | LUMP SUM                       | LUMP       | <br>SUM   | _____      | <br>_____ |
| 0340                 | 514.06<br>CURING BOX FOR CONCRETE<br>CYLINDERS                      | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description  | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|--|--------------------------------|------------|-------|------------|-------|
|                      |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0350                 | 515.21<br>PROTECTIVE COATING FOR CONCRETE SURFACES         | LUMP SUM                       |            |       |            |       |
| 0360                 | 520.232<br>EXPANSION DEVICE - ASPHALTIC PLUG JOINT         | 60.000<br>LF                   |            |       |            |       |
| 0370                 | 524.301<br>TEMPORARY STRUCTURAL SUPPORT                    | LUMP SUM                       |            |       |            |       |
| 0380                 | 526.301<br>TEMPORARY CONCRETE BARRIER TYPE I               | LUMP SUM                       |            |       |            |       |
| 0390                 | 526.34<br>PERMANENT CONCRETE TRANSITION BARRIER            | 4.000<br>EA                    |            |       |            |       |
| 0400                 | 527.34<br>WORK ZONE CRASH CUSHIONS                         | 2.000<br>UN                    |            |       |            |       |
| 0410                 | 530.30<br>GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED | 31,400.000<br>LF               |            |       |            |       |
| 0420                 | 530.31<br>GFRP, REINFORCEMENT BARS, PLACING                | 31,400.000<br>LF               |            |       |            |       |
| 0430                 | 603.199<br>24 INCH CULVERT PIPE OPTION III                 | 132.000<br>LF                  |            |       |            |       |
| 0440                 | 606.1301<br>31" W-BM GR, MID-WAY SPLICE-SGL FACED          | 238.000<br>LF                  |            |       |            |       |
| 0450                 | 606.1303<br>31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS   | 13.000<br>LF                   |            |       |            |       |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0460                 | 606.1304<br>31" W-BM GR, MID-WAY SPLICE-OVER<br>15' RAD     | 75.000<br>LF                   | _____      | <br>_____ | _____      | <br>_____ |
| 0470                 | 606.1305<br>31" W-BM GR, MID-WAY SPLICE<br>FLARED TERMINAL  | 2.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0480                 | 606.1307<br>BRIDGE TRANSITION<br>(ASYMMETRICAL) - TYPE 1    | 4.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0490                 | 606.265<br>TERMINAL END - SINGLE RAIL -<br>GALVANIZED STEEL | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0500                 | 606.353<br>REFLECTORIZED FLEXIBLE<br>GUARDRAIL MARKER       | 8.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0510                 | 606.78<br>LOW VOLUME GUARDRAIL END -<br>TYPE 3              | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0520                 | 609.31<br>CURB TYPE 3                                       | 70.000<br>LF                   | _____      | <br>_____ | _____      | <br>_____ |
| 0530                 | 610.08<br>PLAIN RIPRAP                                      | 1,000.000<br>CY                | _____      | <br>_____ | _____      | <br>_____ |
| 0540                 | 610.18<br>STONE DITCH PROTECTION                            | 32.000<br>CY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0550                 | 613.319<br>EROSION CONTROL BLANKET                          | 61.000<br>SY                   | _____      | <br>_____ | _____      | <br>_____ |
| 0560                 | 615.07<br>LOAM  | 190.000<br>CY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0570                 | 618.14<br>SEEDING METHOD NUMBER 2                           | 30.000<br>UN                   | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0580                 | 619.12<br>MULCH   | 30.000<br>UN                   | _____      | <br>_____ | _____      | <br>_____ |
| 0590                 | 619.14<br>EROSION CONTROL MIX   | 190.000<br>CY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0600                 | 620.58<br>EROSION CONTROL GEOTEXTILE  | 1,550.000<br>SY                | _____      | <br>_____ | _____      | <br>_____ |
| 0610                 | 620.661<br>DRAINAGE GEOCOMPOSITE<br>INSTALLATION                                | 120.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0620                 | 627.733<br>4" WHITE OR YELLOW PAINTED<br>PAVEMENT MARKING LINE                  | 2,500.000<br>LF                | _____      | <br>_____ | _____      | <br>_____ |
| 0630                 | 627.77<br>REMOVING PAVEMENT MARKINGS  | 250.000<br>SF                  | _____      | <br>_____ | _____      | <br>_____ |
| 0640                 | 627.78<br>TEMPORARY 4 INCH PAINTED<br>PAVEMENT MARKING LINE, WHITE<br>OR YELLOW | 1,200.000<br>LF                | _____      | <br>_____ | _____      | <br>_____ |
| 0650                 | 629.05<br>HAND LABOR, STRAIGHT TIME   | 20.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0660                 | 631.12<br>ALL PURPOSE EXCAVATOR<br>(INCLUDING OPERATOR)                         | 20.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0670                 | 631.14<br>GRADER (INCLUDING OPERATOR)   | 20.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0680                 | 631.172<br>TRUCK - LARGE (INCLUDING<br>OPERATOR)                                | 20.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0690                 | 639.18<br>FIELD OFFICE TYPE A   | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021658.00

Project(s): 021658.00

SECTION: 1 project items

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description  | Approximate Quantity and Units | Unit Price |       | Bid Amount |       |
|----------------------|--|--------------------------------|------------|-------|------------|-------|
|                      |  |                                | Dollars    | Cents | Dollars    | Cents |
| 0700                 | 643.72<br>TEMPORARY TRAFFIC SIGNAL                           | LUMP SUM                       | LUMP SUM   |       | _____      | _____ |
| 0710                 | 652.312<br>TYPE III BARRICADE                                | 4.000<br>EA                    | _____      | _____ | _____      | _____ |
| 0720                 | 652.33<br>DRUM   | 30.000<br>EA                   | _____      | _____ | _____      | _____ |
| 0730                 | 652.34<br>CONE   | 30.000<br>EA                   | _____      | _____ | _____      | _____ |
| 0740                 | 652.35<br>CONSTRUCTION SIGNS                                 | 250.000<br>SF                  | _____      | _____ | _____      | _____ |
| 0750                 | 652.361<br>MAINTENANCE OF TRAFFIC CONTROL DEVICES            | LUMP SUM                       | LUMP SUM   |       | _____      | _____ |
| 0760                 | 652.38<br>FLAGGER  | 360.000<br>HR                  | _____      | _____ | _____      | _____ |
| 0770                 | 656.75<br>TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL | LUMP SUM                       | LUMP SUM   |       | _____      | _____ |
| 0780                 | 659.10<br>MOBILIZATION                                       | LUMP SUM                       | LUMP SUM   |       | _____      | _____ |
| Section: 1           |  |                                | Total:     |       | _____      | _____ |
|                      |  |                                | Total Bid: |       | _____      | _____ |