

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021677.00

Project(s): 021677.00

SECTION: 1 Project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	320.000 SY	_____	_____	_____	_____
0030	203.20 COMMON EXCAVATION	500.000 CY	_____	_____	_____	_____
0040	203.2318 DISPOSAL OF SPECIAL WASTE	700.000 T	_____	_____	_____	_____
0050	203.24 COMMON BORROW	430.000 CY	_____	_____	_____	_____
0060	203.25 GRANULAR BORROW	250.000 CY	_____	_____	_____	_____
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	50.000 CY	_____	_____	_____	_____
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	920.000 CY	_____	_____	_____	_____
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	200.000 T	_____	_____	_____	_____
0100	403.211 HOT MIX ASPHALT (SHIMMING)	10.000 T	_____	_____	_____	_____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	270.000 T	_____	_____	_____	_____
0120	409.15 BITUMINOUS TACK COAT - APPLIED	77.000 G	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021677.00

Project(s): 021677.00

SECTION: 1 Project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.231 DYNAMIC LOADING TEST	2.000 EA	_____	 _____	_____	 _____
0140	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	430.000 LF	_____	 _____	_____	 _____
0150	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	390.000 LF	_____	 _____	_____	 _____
0160	501.90 PILE TIPS	10.000 EA	_____	 _____	_____	 _____
0170	501.91 PILE SPLICES	20.000 EA	_____	 _____	_____	 _____
0180	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0190	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0200	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM		LUMP SUM	_____	 _____
0210	502.291 SAW CUT GROOVING	LUMP SUM		LUMP SUM	_____	 _____
0220	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0230	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021677.00

Project(s): 021677.00

SECTION: 1 Project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	3,600.000 LB	_____	 _____	_____	 _____
0250	503.13 REINFORCING STEEL, PLACING	3,600.000 LB	_____	 _____	_____	 _____
0260	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	28,400.000 LB	_____	 _____	_____	 _____
0270	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	28,400.000 LB	_____	 _____	_____	 _____
0280	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		LUMP SUM	_____	 _____
0290	511.07 COFFERDAM: ABUT NO.1	LUMP SUM		LUMP SUM	_____	 _____
0300	511.07 COFFERDAM: ABUT NO.2	LUMP SUM		LUMP SUM	_____	 _____
0310	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA	_____	 _____	_____	 _____
0320	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		LUMP SUM	_____	 _____
0330	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM	_____	 _____
0340	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021677.00

Project(s): 021677.00

SECTION: 1 Project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP SUM		_____	_____
0360	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	763.000 LF	_____	_____	_____	_____
0370	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF	_____	_____	_____	_____
0380	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0390	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1	4.000 EA	_____	_____	_____	_____
0400	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA	_____	_____	_____	_____
0410	610.16 HEAVY RIPRAP	2,500.000 CY	_____	_____	_____	_____
0420	610.18 STONE DITCH PROTECTION	10.000 CY	_____	_____	_____	_____
0430	613.319 EROSION CONTROL BLANKET	160.000 SY	_____	_____	_____	_____
0440	615.07 LOAM	13.000 CY	_____	_____	_____	_____
0450	618.14 SEEDING METHOD NUMBER 2	3.000 UN	_____	_____	_____	_____
0460	619.12 MULCH	3.000 UN	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021677.00

Project(s): 021677.00

SECTION: 1 Project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	619.14 EROSION CONTROL MIX	26.000 CY	_____	 _____	_____	 _____
0480	620.58 EROSION CONTROL GEOTEXTILE	1,170.000 SY	_____	 _____	_____	 _____
0490	620.66 DRAINAGE GEOCOMPOSITE	48.000 SY	_____	 _____	_____	 _____
0500	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,900.000 LF	_____	 _____	_____	 _____
0510	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	11.000 SF	_____	 _____	_____	 _____
0520	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0530	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0540	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0550	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0560	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0570	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0580	652.312 TYPE III BARRICADE	6.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021677.00

Project(s): 021677.00

SECTION: 1 Project items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	652.33 DRUM	50.000 EA	_____	 _____	_____	 _____
0600	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0610	652.35 CONSTRUCTION SIGNS	600.000 SF	_____	 _____	_____	 _____
0620	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0630	652.38 FLAGGER	160.000 HR	_____	 _____	_____	 _____
0640	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0650	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____