

11/17/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	410.000 SY				
0030	203.20 COMMON EXCAVATION	1,360.000 CY				
0040	203.24 COMMON BORROW	50.000 CY				
0050	203.25 GRANULAR BORROW	360.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	600.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	860.000 CY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	129.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	4.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	157.000 T				
0110	409.15 BITUMINOUS TACK COAT - APPLIED	77.000 G				
0120	461.131 TEMPORARY PAVEMENT	130.000 T				

11/17/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	200.000 LF	_____	_____	_____	_____
0140	501.502 ROCK SOCKETED H-PILES	200.000 LF	_____	_____	_____	_____
0150	501.804 DRILLING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0160	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	SUM	_____	_____
0170	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP	SUM	_____	_____
0180	502.291 SAW CUT GROOVING	LUMP SUM	LUMP	SUM	_____	_____
0190	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0200	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0210	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	16,200.000 LB	_____	_____	_____	_____
0220	503.13 REINFORCING STEEL, PLACING	16,200.000 LB	_____	_____	_____	_____
0230	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	11,000.000 LB	_____	_____	_____	_____

11/17/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	11,000.000 LB				
0250	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		LUMP SUM		
0260	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA				
0270	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 18 FT	LUMP SUM		LUMP SUM		
0280	511.07 COFFERDAM: ABUT NO.1	LUMP SUM		LUMP SUM		
0290	511.07 COFFERDAM: ABUT NO.2	LUMP SUM		LUMP SUM		
0300	512.081 FRENCH DRAINS	LUMP SUM		LUMP SUM		
0310	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		LUMP SUM		
0320	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM		
0330	527.34 WORK ZONE CRASH CUSHIONS	6.000 UN				
0340	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	14,720.000 LF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	530.31 GFRP, REINFORCEMENT BARS, PLACING	14,720.000 LF	_____	_____	_____	_____
0360	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP SUM	_____	_____	_____
0370	603.15 12 INCH CULVERT PIPE OPTION I	18.000 LF	_____	_____	_____	_____
0380	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	154.000 LF	_____	_____	_____	_____
0390	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	13.000 LF	_____	_____	_____	_____
0400	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0410	606.1721 BRIDGE TRANSITION - TYPE 1	3.000 EA	_____	_____	_____	_____
0420	606.1721 BRIDGE TRANSITION - TYPE 1 MODIFIED	1.000 EA	_____	_____	_____	_____
0430	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA	_____	_____	_____	_____
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0450	607.242 REMOVE AND RESET GATEWAY	1.000 EA	_____	_____	_____	_____

11/17/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	607.294 BARRIER BOULDERS	3.000 EA				
0470	610.16 HEAVY RIPRAP	580.000 CY				
0480	610.18 STONE DITCH PROTECTION	5.000 CY				
0490	610.214 VOID-FILLED HEAVY RIPRAP	700.000 CY				
0500	613.319 EROSION CONTROL BLANKET	160.000 SY				
0510	615.07 LOAM	84.000 CY				
0520	618.14 SEEDING METHOD NUMBER 2	9.000 UN				
0530	619.12 MULCH	9.000 UN				
0540	619.14 EROSION CONTROL MIX	110.000 CY				
0550	620.58 EROSION CONTROL GEOTEXTILE	1,610.000 SY				
0560	620.60 SEPARATION GEOTEXTILE	400.000 SY				
0570	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,575.000 LF				
0580	627.77 REMOVING PAVEMENT MARKINGS	300.000 SF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	900.000 LF				
0600	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0610	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0620	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0630	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0640	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0650	639.19 FIELD OFFICE TYPE B	1.000 EA				
0660	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM				
0670	652.312 TYPE III BARRICADE	4.000 EA				
0680	652.33 DRUM	25.000 EA				
0690	652.34 CONE	50.000 EA				
0700	652.35 CONSTRUCTION SIGNS	400.000 SF				

11/17/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

Proposal ID: 021687.00

Project(s): 021687.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		LUMP SUM		
0720	652.38 FLAGGER	100.000 HR				
0730	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM		
0740	659.10 MOBILIZATION (10% OR LESS)	LUMP SUM		LUMP SUM		
Section: 1			Total:			
			Total Bid:			