

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021696.00

Project(s): 021696.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	860.000 SY	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	2,800.000 CY	_____	 _____	_____	 _____
0030	203.25 GRANULAR BORROW	2,260.000 CY	_____	 _____	_____	 _____
0040	203.33 SPECIAL FILL	680.000 CY	_____	 _____	_____	 _____
0050	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY	_____	 _____	_____	 _____
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,150.000 CY	_____	 _____	_____	 _____
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	310.000 T	_____	 _____	_____	 _____
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	400.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	130.000 G	_____	 _____	_____	 _____
0100	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM	 _____	_____	 _____
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP SUM	 _____	_____	 _____
0120	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP SUM	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021696.00

Project(s): 021696.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0140	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0150	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM	LUMP	SUM	_____	_____
0160	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,038.000 LF	_____	_____	_____	_____
0170	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0180	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	1.000 EA	_____	_____	_____	_____
0190	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0200	610.08 PLAIN RIPRAP	500.000 CY	_____	_____	_____	_____
0210	610.18 STONE DITCH PROTECTION	10.000 CY	_____	_____	_____	_____
0220	610.210 STREAM CHANNEL ROCK	475.000 CY	_____	_____	_____	_____
0230	610.212 STREAMBED ROCK FEATURES	70.000 CY	_____	_____	_____	_____
0240	613.319 EROSION CONTROL BLANKET	37.000 SY	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021696.00

Project(s): 021696.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	615.07 LOAM	170.000 CY	_____	 _____	_____	 _____
0260	618.14 SEEDING METHOD NUMBER 2	30.000 UN	_____	 _____	_____	 _____
0270	619.12 MULCH	30.000 UN	_____	 _____	_____	 _____
0280	619.14 EROSION CONTROL MIX	25.000 CY	_____	 _____	_____	 _____
0290	620.58 EROSION CONTROL GEOTEXTILE	700.000 SY	_____	 _____	_____	 _____
0300	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3,136.000 LF	_____	 _____	_____	 _____
0310	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0320	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0330	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0340	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0350	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0360	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021696.00

Project(s): 021696.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.34 CONE	20.000 EA	_____	 _____	_____	 _____
0380	652.35 CONSTRUCTION SIGNS	263.000 SF	_____	 _____	_____	 _____
0390	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		LUMP SUM	_____	 _____
0400	652.38 FLAGGER	240.000 HR	_____	 _____	_____	 _____
0410	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0420	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0430	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____