

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021755.00

Project(s): 021755.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	167.000 SY	_____	 _____	_____	 _____
0020	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE	LUMP SUM	LUMP SUM		_____	 _____
0030	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	14.000 T	_____	 _____	_____	 _____
0040	403.211 HOT MIX ASPHALT (SHIMMING)	5.000 T	_____	 _____	_____	 _____
0050	403.213 HOT MIX ASPHALT 12.5 MM BASE	20.000 T	_____	 _____	_____	 _____
0060	409.15 BITUMINOUS TACK COAT - APPLIED	6.000 G	_____	 _____	_____	 _____
0070	502.248 UNDERWATER GROUT BAGS	7.000 CY	_____	 _____	_____	 _____
0080	502.29 STRUCTURAL CONCRETE WEARING SURFACE ON BRIDGES	LUMP SUM	LUMP SUM		_____	 _____
0090	502.291 SAW CUT GROOVING	LUMP SUM	LUMP SUM		_____	 _____
0100	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	150.000 LB	_____	 _____	_____	 _____
0110	503.13 REINFORCING STEEL, PLACING	225.000 LB	_____	 _____	_____	 _____
0120	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP SUM		_____	 _____

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 021755.00

Project(s): 021755.00

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM		LUMP SUM		
0140	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0150	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		LUMP SUM		
0160	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	150.000 SF				
0170	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 8 IN.	75.000 SF				
0180	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	194.000 SF				
0190	518.61 REPAIR OF VERTICAL SURFACES >= 8 IN.	4.000 CY				
0200	520.241 BRIDGE JOINT MODIFICATION TYPE 1	1.000 EA				
0210	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM		
0220	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				
0230	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA				

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 021755.00

Project(s): 021755.00

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA	_____	 _____	_____	 _____
0250	615.07 LOAM	6.000 CY	_____	 _____	_____	 _____
0260	618.141 SEEDING METHOD NUMBER 3	1.000 UN	_____	 _____	_____	 _____
0270	619.12 MULCH	1.000 UN	_____	 _____	_____	 _____
0280	619.14 EROSION CONTROL MIX	12.000 CY	_____	 _____	_____	 _____
0290	627.51 6" TEMPORARY PAVEMENT TAPE, YELLOW OR WHITE	50.000 LF	_____	 _____	_____	 _____
0300	627.55 12" TEMPORARY PAVEMENT TAPE, WHITE	50.000 LF	_____	 _____	_____	 _____
0310	627.57 12" REMOVABLE BLACK LINE MASKING TAPE	50.000 LF	_____	 _____	_____	 _____
0320	627.811 TEMPORARY BI-DIRECTIONAL YELLOW DELINEATORS	50.000 EA	_____	 _____	_____	 _____
0330	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0340	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021755.00

Project(s): 021755.00

SECTION: 1 PROJECT ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0360	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0370	652.312 TYPE III BARRICADE	2.000 EA	_____	 _____	_____	 _____
0380	652.33 DRUM	30.000 EA	_____	 _____	_____	 _____
0390	652.34 CONE	30.000 EA	_____	 _____	_____	 _____
0400	652.35 CONSTRUCTION SIGNS	100.000 SF	_____	 _____	_____	 _____
0410	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0420	652.38 FLAGGER	60.000 HR	_____	 _____	_____	 _____
0430	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0440	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____