

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021830.00

Project(s): 021830.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	760.000 CY	_____	 _____	_____	 _____
0020	203.25 GRANULAR BORROW	160.000 CY	_____	 _____	_____	 _____
0030	203.33 SPECIAL FILL	70.000 CY	_____	 _____	_____	 _____
0040	203.55 CULVERT BEDDING STONE	90.000 CY	_____	 _____	_____	 _____
0050	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	45.000 CY	_____	 _____	_____	 _____
0060	304.16 AGGREGATE BASE COURSE - TYPE C	1,000.000 CY	_____	 _____	_____	 _____
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	85.000 T	_____	 _____	_____	 _____
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	130.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	30.000 G	_____	 _____	_____	 _____
0100	511.07 COFFERDAM: Downstream	LUMP SUM	_____	 LUMP SUM	_____	 _____
0110	511.07 COFFERDAM: Upstream	LUMP SUM	_____	 LUMP SUM	_____	 _____
0120	603.4076 112" X 75" POLYMER COATED PIPE ARCH	98.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021830.00

Project(s): 021830.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	610.08 PLAIN RIPRAP	30.000 CY	_____	 _____	_____	 _____
0140	610.210 STREAM CHANNEL ROCK	20.000 CY	_____	 _____	_____	 _____
0150	610.212 STREAMBED ROCK FEATURES	2.000 CY	_____	 _____	_____	 _____
0160	615.10 DIRTY BORROW	60.000 CY	_____	 _____	_____	 _____
0170	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	 _____	_____	 _____
0180	619.12 MULCH	9.000 UN	_____	 _____	_____	 _____
0190	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	350.000 SY	_____	 _____	_____	 _____
0200	620.58 EROSION CONTROL GEOTEXTILE	60.000 SY	_____	 _____	_____	 _____
0210	620.65 REINFORCEMENT GEOGRID	135.000 SY	_____	 _____	_____	 _____
0220	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	750.000 LF	_____	 _____	_____	 _____
0230	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0240	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 021830.00

Project(s): 021830.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0260	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0270	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0280	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0290	631.212 SMALL PAVEMENT GRINDER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0300	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0310	639.20 FIELD OFFICE TYPE C	1.000 EA	_____	 _____	_____	 _____
0320	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		 LUMP SUM	_____	 _____
0330	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0340	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0350	652.35 CONSTRUCTION SIGNS	600.000 SF	_____	 _____	_____	 _____
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	35.000 CD	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021830.00 Project(s): 021830.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0370	652.38 FLAGGER	40.000 HR	_____	 _____	_____	 _____
0380	652.61 STAGED CONSTRUCTION AND TRAFFIC CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0390	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0400	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____