

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM				
0020	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	374.000 CY				
0030	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	2.000 EA				
0040	202.202 REMOVING PAVEMENT SURFACE	1,440.000 SY				
0050	202.31 PROFILE MILLING CONCRETE WEARING SURFACE	338.000 SY				
0060	203.20 COMMON EXCAVATION	490.000 CY				
0070	203.25 GRANULAR BORROW	730.000 CY				
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	860.000 CY				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	410.000 CY				
0100	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	165.000 T				
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	52.000 T				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	403.211 HOT MIX ASPHALT (SHIMMING)	44.000 T	_____	 _____	_____	 _____
0130	403.213 HOT MIX ASPHALT 12.5 MM BASE	75.000 T	_____	 _____	_____	 _____
0140	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	265.000 T	_____	 _____	_____	 _____
0150	409.15 BITUMINOUS TACK COAT - APPLIED	127.000 G	_____	 _____	_____	 _____
0160	461.131 TEMPORARY PAVEMENT	14.000 T	_____	 _____	_____	 _____
0170	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	620.000 CY	_____	 _____	_____	 _____
0180	502.45 STRUCTURAL CONCRETE APPROACH SLABS	73.000 CY	_____	 _____	_____	 _____
0190	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____
0200	502.565 CONCRETE FILL	3.000 CY	_____	 _____	_____	 _____
0210	503.17 MECHANICAL WELDED SPLICE	68.000 EA	_____	 _____	_____	 _____
0220	507.0834 WYOMING STEEL BRIDGE RAILING	LUMP SUM		LUMP SUM	_____	 _____
0230	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM		_____	_____
0250	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	652.000 SF	_____	_____	_____	_____
0260	518.61 REPAIR OF VERTICAL SURFACES >= 8 IN.	10.000 CY	_____	_____	_____	_____
0270	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP SUM		_____	_____
0280	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM		_____	_____
0290	526.305 PORTABLE CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM	LUMP SUM		_____	_____
0300	526.34 PERMANENT CONCRETE TRANSITION BARRIER	2.000 EA	_____	_____	_____	_____
0310	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	_____	_____	_____
0320	603.159 12 INCH CULVERT PIPE OPTION III	16.000 LF	_____	_____	_____	_____
0330	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	45.000 LF	_____	_____	_____	_____
0340	604.072 CATCH BASIN TYPE A1-C	1.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	604.158 UTILITY VAULT	1.000 EA	_____	 _____	_____	 _____
0360	604.164 REBUILDING CATCH BASIN	1.000 EA	_____	 _____	_____	 _____
0370	604.166 REBUILDING MANHOLE	1.000 EA	_____	 _____	_____	 _____
0380	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	3.000 EA	_____	 _____	_____	 _____
0390	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	12.500 LF	_____	 _____	_____	 _____
0400	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1A	1.000 EA	_____	 _____	_____	 _____
0410	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	 _____	_____	 _____
0420	607.17 CHAIN LINK FENCE - 6 FOOT	20.000 LF	_____	 _____	_____	 _____
0430	609.11 VERTICAL CURB TYPE 1	81.000 LF	_____	 _____	_____	 _____
0440	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	19.000 LF	_____	 _____	_____	 _____
0450	609.221 TERMINAL CURB TYPE 1	15.000 LF	_____	 _____	_____	 _____
0460	609.26 CURB TRANSITION SECTION B TYPE 1	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	609.38 RESET CURB TYPE 1	311.000 LF	_____	 _____	_____	 _____
0480	613.319 EROSION CONTROL BLANKET	22.000 SY	_____	 _____	_____	 _____
0490	615.07 LOAM	18.000 CY	_____	 _____	_____	 _____
0500	618.14 SEEDING METHOD NUMBER 2	2.000 UN	_____	 _____	_____	 _____
0510	619.12 MULCH	2.000 UN	_____	 _____	_____	 _____
0520	619.14 EROSION CONTROL MIX	10.000 CY	_____	 _____	_____	 _____
0530	626.11 PRECAST CONCRETE JUNCTION BOX	3.000 EA	_____	 _____	_____	 _____
0540	626.21 METALLIC CONDUIT	60.000 LF	_____	 _____	_____	 _____
0550	626.22 NON-METALLIC CONDUIT	464.000 LF	_____	 _____	_____	 _____
0560	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	6.000 EA	_____	 _____	_____	 _____
0570	626.411 18 INCH DIAMETER FOUNDATION	33.000 LF	_____	 _____	_____	 _____
0580	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	700.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	500.000 SF	_____	 _____	_____	 _____
0600	627.77 REMOVING PAVEMENT MARKINGS	1,100.000 SF	_____	 _____	_____	 _____
0610	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	3,600.000 LF	_____	 _____	_____	 _____
0620	629.05 HAND LABOR, STRAIGHT TIME	28.000 HR	_____	 _____	_____	 _____
0630	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0640	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0650	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0660	634.160 HIGHWAY LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____
0670	634.712 ORNAMENTAL LIGHTING, INSTALL ONLY	1.000 EA	_____	 _____	_____	 _____
0680	634.72 RELOCATE ORNAMENTAL LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____
0690	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	645.103 DEMOUNT GUIDE SIGN	3.000 EA	_____	 _____	_____	 _____
0710	645.108 DEMOUNT POLE	3.000 EA	_____	 _____	_____	 _____
0720	645.113 REINSTALL GUIDE SIGN	3.000 EA	_____	 _____	_____	 _____
0730	645.118 REINSTALL POLE	3.000 EA	_____	 _____	_____	 _____
0740	652.312 TYPE III BARRICADE	16.000 EA	_____	 _____	_____	 _____
0750	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0760	652.34 CONE	25.000 EA	_____	 _____	_____	 _____
0770	652.35 CONSTRUCTION SIGNS	196.000 SF	_____	 _____	_____	 _____
0780	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0790	652.38 FLAGGER	432.000 HR	_____	 _____	_____	 _____
0800	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	3.000 EA	_____	 _____	_____	 _____
0810	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 1 MAIN ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0820	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0830	803.01 TEST PITS	3.000 EA	_____	_____	_____	_____
0840	910.301 SPECIAL WORK UTILITY CONDUIT - CC - APPR ONLY	LUMP SUM	LUMP	SUM	_____	_____
0850	910.301 SPECIAL WORK UTILITY CONDUIT - CC - BR ONLY	LUMP SUM	LUMP	SUM	_____	_____
0860	910.301 SPECIAL WORK UTILITY CONDUIT - CITY OF AUGUSTA	LUMP SUM	LUMP	SUM	_____	_____
		Section: 1	Total:		_____	_____

11/4/2022

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 13

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 2

STEEL GIRDER

Alt Set ID: AL

Alt Mbr ID: 1

Contractor: _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 2 STEEL GIRDER

Alt Set ID: AL Alt Mbr ID: 1

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0870	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM	_____	_____
0880	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	52,900.000 LB	_____	_____	_____	_____
0890	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	52,900.000 LB	_____	_____	_____	_____
0900	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM		LUMP SUM	_____	_____
0910	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM		LUMP SUM	_____	_____
0920	505.08 SHEAR CONNECTORS	LUMP SUM		LUMP SUM	_____	_____
0930	506.9104 THERMAL SPRAY COATING - SHOP APPLIED	LUMP SUM		LUMP SUM	_____	_____
0940	523.52 BEARING INSTALLATION	16.000 EA	_____	_____	_____	_____
0950	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	8.000 EA	_____	_____	_____	_____
0960	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	8.000 EA	_____	_____	_____	_____
0970	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	61,700.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 2 STEEL GIRDER

Alt Set ID: AL Alt Mbr ID: 1

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0980	530.31 GFRP, REINFORCEMENT BARS, PLACING	61,700.000 LF	_____	_____	_____	_____
	Section: 2		Total:		_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021872.00

Project(s): 021872.00

SECTION: 3 CT GIRDER

Alt Set ID: AL Alt Mbr ID: 2

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0990	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM		
1000	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	52,500.000 LB				
1010	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	52,500.000 LB				
1020	509.743 COMPOSITE TUB GIRDER, FABRICATION	LUMP SUM		LUMP SUM		
1030	509.744 COMPOSITE TUB GIRDER, ERECTION	LUMP SUM		LUMP SUM		
1040	523.52 BEARING INSTALLATION	16.000 EA				
1050	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	8.000 EA				
1060	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	8.000 EA				
1070	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	61,150.000 LF				
1080	530.31 GFRP, REINFORCEMENT BARS, PLACING	61,150.000 LF				
Section: 3			Total:			

Total Bid: _____!