

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	130.000 SY				
0030	203.20 COMMON EXCAVATION	2,060.000 CY				
0040	203.24 COMMON BORROW	10.000 CY				
0050	203.25 GRANULAR BORROW	540.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	400.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,180.000 CY				
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	288.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	8.000 T				
0100	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	703.000 T				
0110	409.15 BITUMINOUS TACK COAT - APPLIED	305.000 G				
0120	461.131 TEMPORARY PAVEMENT	250.000 T				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	501.231 DYNAMIC LOADING TEST	2.000 EA	_____	 _____	_____	 _____
0140	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	294.000 LF	_____	 _____	_____	 _____
0150	501.541 STEEL H-BEAM PILES 117 LBS/FT, IN PLACE	294.000 LF	_____	 _____	_____	 _____
0160	501.903 PILE TIPS - ROCK INJECTOR POINT	12.000 EA	_____	 _____	_____	 _____
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM		LUMP SUM	_____	 _____
0190	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM		LUMP SUM	_____	 _____
0200	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM		LUMP SUM	_____	 _____
0210	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM		LUMP SUM	_____	 _____
0220	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: F	2.000 EA	_____	 _____	_____	 _____
0230	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	25,300.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.13 REINFORCING STEEL, PLACING	25,300.000 LB	_____	 _____	_____	 _____
0250	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	11,900.000 LB	_____	 _____	_____	 _____
0260	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	11,900.000 LB	_____	 _____	_____	 _____
0270	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM		LUMP SUM	_____	 _____
0280	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM		LUMP SUM	_____	 _____
0290	505.08 SHEAR CONNECTORS	LUMP SUM		LUMP SUM	_____	 _____
0300	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		LUMP SUM	_____	 _____
0310	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0320	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM	_____	 _____
0330	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 16FT	LUMP SUM		LUMP SUM	_____	 _____
0340	511.07 COFFERDAM: Abutment 1	LUMP SUM		LUMP SUM	_____	 _____
0350	511.07 COFFERDAM: Abutment 2	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM				
0370	519.60 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	64.000 LF				
0380	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM				
0390	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0400	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	37,740.000 LF				
0410	530.31 GFRP, REINFORCEMENT BARS, PLACING	37,740.000 LF				
0420	603.17 18 INCH CULVERT PIPE OPTION I	46.000 LF				
0430	605.36 DRAINAGE STONE	6.000 CY				
0440	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	300.000 LF				
0450	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA				
0460	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0480	606.47 SINGLE WOOD POST	1.000 EA	_____	 _____	_____	 _____
0490	610.08 PLAIN RIPRAP	13.000 CY	_____	 _____	_____	 _____
0500	610.16 HEAVY RIPRAP	1,608.000 CY	_____	 _____	_____	 _____
0510	613.319 EROSION CONTROL BLANKET	132.000 SY	_____	 _____	_____	 _____
0520	615.07 LOAM	100.000 CY	_____	 _____	_____	 _____
0530	618.14 SEEDING METHOD NUMBER 2	17.000 UN	_____	 _____	_____	 _____
0540	619.12 MULCH	17.000 UN	_____	 _____	_____	 _____
0550	619.14 EROSION CONTROL MIX	200.000 CY	_____	 _____	_____	 _____
0560	620.58 EROSION CONTROL GEOTEXTILE	1,606.000 SY	_____	 _____	_____	 _____
0570	620.66 DRAINAGE GEOCOMPOSITE	50.000 SY	_____	 _____	_____	 _____
0580	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,000.000 LF	_____	 _____	_____	 _____
0590	627.77 REMOVING PAVEMENT MARKINGS	550.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0600	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,300.000 LF	_____	 _____	_____	 _____
0610	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0620	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0630	631.14 GRADER (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0640	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	25.000 HR	_____	 _____	_____	 _____
0650	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0660	637.071 DUST CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0670	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0680	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		 LUMP SUM	_____	 _____
0690	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0700	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0710	652.34 CONE	50.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021876.00

Project(s): 021876.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0720	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	 _____	_____	 _____
0730	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
0740	652.38 FLAGGER	360.000 HR	_____	 _____	_____	 _____
0750	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0760	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____