Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	5.000 EA				
0020	201.24 REMOVING STUMP	5.000 EA				
0030	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	3.000 EA				
0040	202.202 REMOVING PAVEMENT SURFACE	1,010.000 SY				
0050	203.20 COMMON EXCAVATION	3,875.000 CY				
0060	203.2318 DISPOSAL OF SPECIAL WASTE	42.000 T				
0070	203.25 GRANULAR BORROW	440.000 CY				
0080	203.33 SPECIAL FILL	330.000 CY				
0090	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	700.000 CY				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	840.000 CY				
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	231.000 T				
0120	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	43.000 T				

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	403.213 HOT MIX ASPHALT 12.5 MM BASE	336.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	229.000 G				
0150	461.131 TEMPORARY PAVEMENT	175.000 T				
0160	501.231 DYNAMIC LOADING TEST	2.000 EA				
0170	501.54 STEEL H-BEAM PILES 117 LBS/FT, DELIVERED	610.000 LF				
0180	501.541 STEEL H-BEAM PILES 117 LBS/FT, IN PLACE	610.000 LF				
0190	501.90 PILE TIPS	10.000 EA				
0200	501.91 PILE SPLICES	20.000 EA				
0210	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM			
0220	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM			
0230	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP SUM			

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars Cents	Bid Amount Dollars Cents
0240	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP SUM	_____.____
0250	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM	_____.____
0260	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: B	1.000 EA	_____.____	_____.____
0270	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: F	1.000 EA	_____.____	_____.____
0280	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	30,200.000 LB	_____.____	_____.____
0290	503.13 REINFORCING STEEL, PLACING	30,200.000 LB	_____.____	_____.____
0300	503.17 MECHANICAL WELDED SPLICE	70.000 EA	_____.____	_____.____
0310	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	11,700.000 LB	_____.____	_____.____
0320	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	11,700.000 LB	_____.____	_____.____
0330	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP SUM	_____.____
0340	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP SUM	_____.____

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars Cents	Bid Amount Dollars Cents
0350	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP SUM	_____.____
0360	507.08161 STEEL APPROACH RAILING, 4 BAR	2.000 EA	_____.____	_____.____
0370	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP SUM	_____.____
0380	507.0822 STEEL APPROACH RAILING, 3-BAR	2.000 EA	_____.____	_____.____
0390	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP SUM	LUMP SUM	_____.____
0400	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM	_____.____
0410	510.12 SPECIAL DETOUR__FOOT ROADWAY WIDTH, VEHICULAR AND PEDESTRIAN TRAFFIC SEPARATED 29 FT	LUMP SUM	LUMP SUM	_____.____
0420	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP SUM	_____.____
0430	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP SUM	_____.____
0440	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM	_____.____
0450	519.60 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	74.000 LF	_____.____	_____.____

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0460	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM		_____	_____
0470	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0480	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	30,700.000 LF	_____	_____	_____	_____
0490	530.31 GFRP, REINFORCEMENT BARS, PLACING	30,700.000 LF	_____	_____	_____	_____
0500	603.179 18 INCH CULVERT PIPE OPTION III	115.000 LF	_____	_____	_____	_____
0510	603.199 24 INCH CULVERT PIPE OPTION III	120.000 LF	_____	_____	_____	_____
0520	604.092 CATCH BASIN TYPE B1-C	6.000 EA	_____	_____	_____	_____
0530	604.26 CATCH BASIN TYPE B5	1.000 EA	_____	_____	_____	_____
0540	605.09 6 INCH UNDERDRAIN TYPE B	170.000 LF	_____	_____	_____	_____
0550	605.11 12 INCH UNDERDRAIN TYPE C	125.000 LF	_____	_____	_____	_____
0560	605.12 15 INCH UNDERDRAIN TYPE C	352.000 LF	_____	_____	_____	_____
0570	605.13 18 INCH UNDERDRAIN TYPE C	23.000 LF	_____	_____	_____	_____

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0580	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	218.750 LF	_____	_____	_____	_____
0590	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF	_____	_____	_____	_____
0600	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	_____	_____	_____
0610	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0620	606.259 ANCHORAGE ASSEMBLY	1.000 EA	_____	_____	_____	_____
0630	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	_____	_____	_____
0640	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0650	606.47 SINGLE WOOD POST	2.000 EA	_____	_____	_____	_____
0660	609.31 CURB TYPE 3	720.000 LF	_____	_____	_____	_____
0670	610.08 PLAIN RIPRAP	1,000.000 CY	_____	_____	_____	_____
0680	610.18 STONE DITCH PROTECTION	22.000 CY	_____	_____	_____	_____
0690	610.212 STREAMBED ROCK FEATURES	22.000 CY	_____	_____	_____	_____

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	613.319 EROSION CONTROL BLANKET	130.000 SY				
0710	615.07 LOAM	100.000 CY				
0720	618.13 SEEDING METHOD NUMBER 1	4.000 UN				
0730	618.14 SEEDING METHOD NUMBER 2	9.000 UN				
0740	619.12 MULCH	13.000 UN				
0750	619.14 EROSION CONTROL MIX	50.000 CY				
0760	620.58 EROSION CONTROL GEOTEXTILE	130.000 SY				
0770	620.66 DRAINAGE GEOCOMPOSITE	108.000 SY				
0780	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,850.000 LF				
0790	627.77 REMOVING PAVEMENT MARKINGS	200.000 SF				
0800	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	700.000 LF				
0810	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0820	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0830	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0840	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0850	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				
0860	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR				
0870	639.18 FIELD OFFICE TYPE A	1.000 EA				
0880	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM			
0890	652.312 TYPE III BARRICADE	4.000 EA				
0900	652.33 DRUM	20.000 EA				
0910	652.34 CONE	20.000 EA				
0920	652.35 CONSTRUCTION SIGNS	320.000 SF				
0930	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM			

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021882.00 Project(s): 021882.00

SECTION: 1 Initial Group

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0940	652.38 FLAGGER	375.000 HR	_____	_____	_____	_____
0950	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0960	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0970	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____

Section: 1 Total: _____.____

Total Bid: _____.____