

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022252.00

Project(s): 022252.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0020	202.202 REMOVING PAVEMENT SURFACE	622.000 SY	_____	_____	_____	_____
0030	202.31 PROFILE MILLING CONCRETE WEARING SURFACE	102.000 SY	_____	_____	_____	_____
0040	203.20 COMMON EXCAVATION	850.000 CY	_____	_____	_____	_____
0050	203.25 GRANULAR BORROW	250.000 CY	_____	_____	_____	_____
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	530.000 CY	_____	_____	_____	_____
0070	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	30.000 CY	_____	_____	_____	_____
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	650.000 CY	_____	_____	_____	_____
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	119.000 T	_____	_____	_____	_____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	175.000 T	_____	_____	_____	_____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	103.000 G	_____	_____	_____	_____
0120	461.131 TEMPORARY PAVEMENT	98.000 T	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022252.00

Project(s): 022252.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	218.000 CY	_____	 _____	_____	 _____
0140	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP	 SUM	_____	 _____
0150	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	 SUM	_____	 _____
0160	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	 SUM	_____	 _____
0170	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	20,100.000 LB	_____	 _____	_____	 _____
0180	503.13 REINFORCING STEEL, PLACING	20,100.000 LB	_____	 _____	_____	 _____
0190	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	 SUM	_____	 _____
0200	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0210	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 18 FT	LUMP SUM	LUMP	 SUM	_____	 _____
0220	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP	 SUM	_____	 _____
0230	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP	 SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022252.00

Project(s): 022252.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	512.081 FRENCH DRAINS	LUMP SUM	LUMP	SUM	_____	_____
0250	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0260	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0270	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN	_____	_____	_____	_____
0280	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	9,350.000 LF	_____	_____	_____	_____
0290	530.31 GFRP, REINFORCEMENT BARS, PLACING	9,350.000 LF	_____	_____	_____	_____
0300	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP SUM	LUMP	SUM	_____	_____
0310	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	163.000 LF	_____	_____	_____	_____
0320	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA	_____	_____	_____	_____
0330	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0340	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022252.00

Project(s): 022252.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	610.08 PLAIN RIPRAP	240.000 CY	_____	 _____	_____	 _____
0360	610.18 STONE DITCH PROTECTION	10.000 CY	_____	 _____	_____	 _____
0370	613.319 EROSION CONTROL BLANKET	95.000 SY	_____	 _____	_____	 _____
0380	619.14 EROSION CONTROL MIX	80.000 CY	_____	 _____	_____	 _____
0390	620.58 EROSION CONTROL GEOTEXTILE	385.000 SY	_____	 _____	_____	 _____
0400	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,200.000 LF	_____	 _____	_____	 _____
0410	627.77 REMOVING PAVEMENT MARKINGS	335.000 SF	_____	 _____	_____	 _____
0420	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,000.000 LF	_____	 _____	_____	 _____
0430	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0440	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0450	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0460	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022252.00

Project(s): 022252.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	_____
0480	652.312 TYPE III BARRICADE	4.000 EA	_____	_____	_____	_____
0490	652.33 DRUM	25.000 EA	_____	_____	_____	_____
0500	652.34 CONE	50.000 EA	_____	_____	_____	_____
0510	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	_____	_____	_____
0520	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	_____
0530	652.38 FLAGGER	360.000 HR	_____	_____	_____	_____
0540	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0550	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____