

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022278.00

Project(s): 022278.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	502.565 CONCRETE FILL	97.000 CY	_____	 _____	_____	 _____
0020	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	100.000 LB	_____	 _____	_____	 _____
0030	503.13 REINFORCING STEEL, PLACING	150.000 LB	_____	 _____	_____	 _____
0040	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		 LUMP SUM	_____	 _____
0050	515.201 PIGMENTED CONCRETE PROTECTIVE COATING	695.000 SY	_____	 _____	_____	 _____
0060	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		 LUMP SUM	_____	 _____
0070	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	158.000 SF	_____	 _____	_____	 _____
0080	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 8 IN.	10.000 SF	_____	 _____	_____	 _____
0090	518.52 REPAIR OF UPWARD FACING SURFACES >= 8 IN.	5.000 CY	_____	 _____	_____	 _____
0100	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	1,244.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022278.00

Project(s): 022278.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0110	518.61 REPAIR OF VERTICAL SURFACES >= 8 IN.	4.000 CY	_____	 _____	_____	 _____
0120	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	40.000 SF	_____	 _____	_____	 _____
0130	521.52 TROUGH SYSTEM FOR FINGER JOINT	LUMP SUM		LUMP SUM	_____	 _____
0140	523.52 BEARING INSTALLATION	86.000 EA	_____	 _____	_____	 _____
0150	523.5551 POT OR DISC BEARINGS, FIXED	6.000 EA	_____	 _____	_____	 _____
0160	523.5552 POT OR DISC BEARINGS, EXPANSION	80.000 EA	_____	 _____	_____	 _____
0170	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM		LUMP SUM	_____	 _____
0180	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM	_____	 _____
0190	527.33 TRUCK MOUNTED ATTENUATOR	1.000 EA	_____	 _____	_____	 _____
0200	610.08 PLAIN RIPRAP	23.000 CY	_____	 _____	_____	 _____
0210	610.18 STONE DITCH PROTECTION	14.000 CY	_____	 _____	_____	 _____
0220	619.14 EROSION CONTROL MIX	10.000 CY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022278.00

Project(s): 022278.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	620.58 EROSION CONTROL GEOTEXTILE	45.000 SY	_____	 _____	_____	 _____
0240	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1,350.000 SF	_____	 _____	_____	 _____
0250	627.77 REMOVING PAVEMENT MARKINGS	1,350.000 SF	_____	 _____	_____	 _____
0260	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,800.000 LF	_____	 _____	_____	 _____
0270	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR	_____	 _____	_____	 _____
0280	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0290	631.11 AIR TOOL (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0300	631.112 WELDING MACHINE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0310	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0320	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0330	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022278.00

Project(s): 022278.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0350	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0360	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0370	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0380	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	 _____	_____	 _____
0390	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM	_____	 _____
0400	652.38 FLAGGER	200.000 HR	_____	 _____	_____	 _____
0410	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	 _____	_____	 _____
0420	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
0430	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____