

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022340.00

Project(s): 022340.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM				
0020	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	34.000 CY				
0030	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	952.000 LF				
0040	202.202 REMOVING PAVEMENT SURFACE	370.000 SY				
0050	203.20 COMMON EXCAVATION	580.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	420.000 CY				
0070	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	220.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	90.000 T				
0090	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	200.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	120.000 G				
0110	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	17.000 CY				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022340.00

Project(s): 022340.00

SECTION: 1

Project Items

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP	SUM	_____	_____
0130	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0140	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: E	8.000 EA	_____	_____	_____	_____
0150	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	100.000 LB	_____	_____	_____	_____
0160	503.13 REINFORCING STEEL, PLACING	150.000 LB	_____	_____	_____	_____
0170	503.17 MECHANICAL WELDED SPLICE	8.000 EA	_____	_____	_____	_____
0180	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	2,800.000 LB	_____	_____	_____	_____
0190	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	2,800.000 LB	_____	_____	_____	_____
0200	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0210	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0220	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022340.00

Project(s): 022340.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM				
0240	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	100.000 SF				
0250	520.21 EXPANSION DEVICE - GLAND SEAL	2.000 EA				
0260	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM				
0270	524.40 PROTECTIVE SHIELD STEEL GIRDERS	LUMP SUM				
0280	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM				
0290	526.305 TEMPORARY CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM				
0300	527.33 TRUCK MOUNTED ATTENUATOR	2.000 EA				
0310	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				
0320	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	38.000 LF				
0330	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022340.00

Project(s): 022340.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0350	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0360	607.183 CHAIN LINK SNOW FENCE 33 INCH	LUMP SUM	LUMP SUM		_____	 _____
0370	609.38 RESET CURB TYPE 1	510.000 LF	_____	 _____	_____	 _____
0380	615.07 LOAM	24.000 CY	_____	 _____	_____	 _____
0390	618.14 SEEDING METHOD NUMBER 2	4.000 UN	_____	 _____	_____	 _____
0400	619.12 MULCH	4.000 UN	_____	 _____	_____	 _____
0410	619.14 EROSION CONTROL MIX	10.000 CY	_____	 _____	_____	 _____
0420	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,250.000 LF	_____	 _____	_____	 _____
0430	627.77 REMOVING PAVEMENT MARKINGS	370.000 SF	_____	 _____	_____	 _____
0440	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	2,950.000 LF	_____	 _____	_____	 _____
0450	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022340.00

Project(s): 022340.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0470	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0480	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0490	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0500	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	10.000 HR	_____	 _____	_____	 _____
0510	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0520	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0530	652.30 FLASHING ARROW BOARD	2.000 EA	_____	 _____	_____	 _____
0540	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0550	652.33 DRUM	62.000 EA	_____	 _____	_____	 _____
0560	652.34 CONE	62.000 EA	_____	 _____	_____	 _____
0570	652.35 CONSTRUCTION SIGNS	990.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022340.00

Project(s): 022340.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM				
0590	652.38 FLAGGER	240.000 HR				
0600	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA				
0610	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM				
0620	659.10 MOBILIZATION	LUMP SUM				
Section: 1			Total:			
			Total Bid:			