

3/21/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 022476.00

Project(s): 022476.00, 023923.00, 024203.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	3,150.000 SY	_____	 _____	_____	 _____
0020	202.203 REMOVING PAVEMENT SURFACE - MEDIUM CUT DRUM	125,650.000 SY	_____	 _____	_____	 _____
0030	202.203 PAVEMENT BUTT JOINTS	6,363.000 SY	_____	 _____	_____	 _____
0040	211.21 INSLOPE REHABILITATION	9,887.000 LF	_____	 _____	_____	 _____
0050	211.30 DITCH EXCAVATION	9,887.000 LF	_____	 _____	_____	 _____
0060	312.20 HOT IN-PLACE RECYCLING	173,000.000 SY	_____	 _____	_____	 _____
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	795.000 T	_____	 _____	_____	 _____
0080	403.2101 9.5 MM POLYMER MODIFIED HMA	15.000 T	_____	 _____	_____	 _____
0090	403.21041 HMA 9.5 MM – POLYMER MODIFIED THIN LIFT SURFACE TREATMENT	16,288.000 T	_____	 _____	_____	 _____
0100	403.211 HOT MIX ASPHALT (SHIMMING)	590.000 T	_____	 _____	_____	 _____
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	950.000 T	_____	 _____	_____	 _____
0120	409.15 BITUMINOUS TACK COAT - APPLIED	9,325.000 G	_____	 _____	_____	 _____

3/21/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 022476.00

Project(s): 022476.00, 023923.00, 024203.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	410.151 EMULSIFIED ASPHALT SEALCOAT, APPLIED	82,800.000 SY	_____	 _____	_____	 _____
0140	410.161 COVER COAT MATERIAL, SAND	41,400.000 LB	_____	 _____	_____	 _____
0150	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	266.000 CY	_____	 _____	_____	 _____
0160	424.22 ASPHALT RUBBER CRACK SEALER TYPE 2, APPLIED	60,000.000 LB	_____	 _____	_____	 _____
0170	462.301 POLYMER MODIFIED ULTRATHIN BONDED WEARING COURSE	122,400.000 SY	_____	 _____	_____	 _____
0180	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	3.000 EA	_____	 _____	_____	 _____
0190	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	17.000 EA	_____	 _____	_____	 _____
0200	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	275.000 LF	_____	 _____	_____	 _____
0210	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	10.000 EA	_____	 _____	_____	 _____
0220	606.178 GUARDRAIL BEAM	1,900.000 LF	_____	 _____	_____	 _____
0230	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	7.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 022476.00

Project(s): 022476.00, 023923.00, 024203.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	30.000 EA	_____	 _____	_____	 _____
0250	606.362 GUARDRAIL ADJUSTED	17,751.000 LF	_____	 _____	_____	 _____
0260	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	75.000 EA	_____	 _____	_____	 _____
0270	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	2.000 EA	_____	 _____	_____	 _____
0280	608.26 CURB RAMP DETECTABLE WARNING FIELD	200.000 SF	_____	 _____	_____	 _____
0290	608.461 RECONSTRUCT PEDESTRIAN RAMP	16.000 EA	_____	 _____	_____	 _____
0300	609.31 CURB TYPE 3	3,330.000 LF	_____	 _____	_____	 _____
0310	615.10 DIRTY BORROW	693.000 CY	_____	 _____	_____	 _____
0320	618.14 SEEDING METHOD NUMBER 2	324.000 UN	_____	 _____	_____	 _____
0330	619.12 MULCH	324.000 UN	_____	 _____	_____	 _____
0340	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	315,400.000 LF	_____	 _____	_____	 _____
0350	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	9,340.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 022476.00

Project(s): 022476.00, 023923.00, 024203.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	760,400.000 LF	_____	 _____	_____	 _____
0370	629.05 HAND LABOR, STRAIGHT TIME	115.000 HR	_____	 _____	_____	 _____
0380	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	115.000 HR	_____	 _____	_____	 _____
0390	631.133 SKID STEER (INCLUDING OPERATOR)	100.000 HR	_____	 _____	_____	 _____
0400	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	115.000 HR	_____	 _____	_____	 _____
0410	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0420	643.86 TRAFFIC SIGNAL LOOP DETECTORS	10.000 EA	_____	 _____	_____	 _____
0430	652.33 DRUM	5.000 EA	_____	 _____	_____	 _____
0440	652.34 CONE	1,030.000 EA	_____	 _____	_____	 _____
0450	652.35 CONSTRUCTION SIGNS	5,350.000 SF	_____	 _____	_____	 _____
0460	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	164.000 CD	_____	 _____	_____	 _____
0470	652.38 FLAGGER	6,032.000 HR	_____	 _____	_____	 _____

3/21/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 022476.00

Project(s): 022476.00, 023923.00, 024203.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0490	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0500	823.332 GATE VALVE BOX, ADJUST TO GRADE	19.000 EA	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____